

Central Street Bridge Replacement Project Central Street, Manchester-by-the-Sea

# **Notice of Intent**

Town of Manchester-by-the-Sea 10 Central Street Manchester-by-the-Sea, Massachusetts

100% Recyclable 🐔

September 2020

# Tighe&Bond

# Tighe&Bond

M-14760-011 September 11, 2020

Chris Bertoni, Conservation Agent Manchester-by-the-Sea Conservation Commission 10 Central Street Manchester-by-the-Sea, MA 01944-1399

### Re: Notice of Intent (NOI) Central Street Bridge Replacement Project

Dear Agent Bertoni and Conservation Commissioners,

On the behalf of the Town of Manchester-by-the-Sea, Tighe & Bond is submitting a Notice of Intent (NOI) for the Central Street Bridge Replacement Project. This proposed project includes the replacement of the Central Street bridge, the removal of the tide gate structure in Sawmill Brook, and roadway improvements at Central Street.

This NOI is being filed under the Massachusetts Wetlands Protection Act (MA WPA, MGL c. 131 § 40) and its implementing regulations (310 CMR 10.00) and the Town of Manchester-by-the-Sea Wetlands Regulations (Article XVII). Wetland resources within the limit of work include Land Under Ocean (LUO), Coastal Beach, Coastal Bank, the 200-foot Riverfront Area associated with Sawmill Brook, Land Subject to Coastal Storm Flowage (LSCSF), and the 100-foot Buffer Zone to Coastal Bank. The work will also occur within the locally regulated 30-foot No-Disturbance Zone and 50-foot No-Build Zone. A copy of this NOI has been submitted to the Massachusetts Department of Environmental Protection (MassDEP) Northeast Regional Wetlands Program (NERO) and Division of Marine Fisheries (DMF). As a municipal project, there is no filing fee associated with the regulatory review. In compliance with the MA WPA and Manchester-by-the-Sea Wetlands Protection Regulations, notification to abutters regarding this NOI will be made by certified mail at least one week prior to the hearing.

We look forward to having the opportunity to discuss this project with the Manchester-by-the-Sea Conservation Commission at the October 13, 2020 public hearing. We understand that public hearings may need to be held using alternate methods given the current COVID-19 crisis. Should you have any questions or require additional information please contact me at (860) 933-1369 or RCanavan@tighebond.com.

Very truly yours,

TIGHE & BOND, INC.

Miller Canne

Richard Canavan, PWS, PhD Principal Environmental Scientist

Copy: MassDEP NERO DMF - North Shore Office Greg Federspiel, Town Administrator, Manchester-by-the-Sea

# **Tighe&Bond**

CONTENTS

### WPA Form 3

### **Town NOI Checklist**

### Wetland Fee Transmittal Form

### **Section 1 Introduction**

1.1	Project Background and Purpose	1-	1
-----	--------------------------------	----	---

### **Section 2 Existing Conditions**

2.1	Project Site Conditions	2-1	
2.2	Wetland Resource Area Delineation Methodology2		
2.3	Wetland Resource Areas	2-3	
	2.3.1 Land Under Ocean	2-3	
	2.3.2 Coastal Beach	2-3	
	2.3.3 Coastal Bank	2-3	
	2.3.4 Riverfront Area	2-4	
	2.3.5 Land Subject to Coastal Storm Flowage	2-4	
2.4	Rare Species		

### **Section 3 Project Description**

3.1	Alterna	atives Analysis	3-1
	3.1.1	No Action	3-1
	3.1.2	Rehabilitate Bridge and Culvert Structure, Remove Tide Gate	3-1
	3.1.3	Replace Culvert with Bridge, Remove Tide Gate (Preferred)	3-2
3.2	Propos	ed Activities	3-2
3.3	Site Ac	ccess and Construction Staging	3-3
3.4	Anticipated Construction Sequence		3-3
3.5		uction-Period Best Management Practices	
	3.5.1	Limits of Work	3-4
	3.5.2	Catch Basin Protection	3-4
	3.5.3	Erosion Control Barriers	3-4
	3.5.4 (	Cofferdams	3-4
	3.5.5	Dewatering	3-4
	3.5.6	Stockpile Management	3-5
		Site Restoration	

### **Section 4 Regulatory Compliance**

4.1	Massa	chusetts Wetlands Protection Act4-1
	4.1.1	Limited Project Status4-1
	4.1.2	WPA Riverfront Area Exemption4-1
	4.1.3	Summary of WPA Jurisdictional Alterations4-1
		i

	4.1.4	Performance Standards Compliance	4-2
	4.1.5	Abutter Notification	4-5
	4.1.6	Stormwater Management	4-5
4.2	Manch	nester-by-the-Sea Wetlands Bylaw	4-5
	4.2.1	Coastal Bank	4-5
	4.2.2	Riverfront Area	4-6
	4.2.3	No Disturb Zone	4-7
	4.2.4	No Build Zone	4-7

### Appendices

- A Figures/Drawings
  - Figure 1 Site Location
  - Figure 2 Priority Resources
  - Figure 3 Orthophotograph
  - Figure 4 FEMA National Flood Hazard Layer FIRMette
  - Figure 5 Mouth of the River
  - Project Drawings Central Street Bridge Reconstruction (8/2020)
- B Site Photographs
- C Abutter Notification Information List of Abutters Abutter Notification Form Affidavit
- D Stormwater Checklist and Report

J:\M\M1476 Manchester MA Hydro Study\011-Central Street Bridge\Permitting\NOI\Word Docs\3 - Draft Central Street Bridge NOI Narrative.docx

# WPA FORM 3



# Massachusetts Department of Environmental Protection Bureau of Resource Protection - Wetlands


**A. General Information** 

### WPA Form 3 – Notice of Intent Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP:

MassDEP File Number

Document Transaction Number Manchester-by-the-Sea City/Town



Note:
Before
completing this
form consult
your local
Conservation
Commission
regarding any
municipal bylaw
or ordinance.

1.	Project Location (No	ote: electronic filers will of	click on button to locate project sit	te):	
	Central Street (MA-	127) and Elm Street	Manchester-by-the-Sea	01944	
	a. Street Address	,	b. City/Town	c. Zip Code	
			42.575262	-70.772963	
	Latitude and Longitu	ude:	d. Latitude	e. Longitude	
	f. Assessors Map/Plat No	umber	g. Parcel /Lot Number		
2.	Applicant:				
	Gregory		Federspiel		
	a. First Name		b. Last Name		
	Town of Mancheste	r-by-the-Sea			
	c. Organization				
	10 Central Street				
	d. Street Address				
	Manchester-by-the-	Sea	MA	01944	
	e. City/Town		f. State	g. Zip Code	
	(978) 526-2000	(978) 526-2001	federspielg@manchester.ma	a.us	
	h. Phone Number	i. Fax Number	j. Email Address		
	c. Organization				
	d. Street Address				
	e. City/Town		f. State	g. Zip Code	
	h. Phone Number	i. Fax Number	j. Email address		
4.	Representative (if any):				
	Richard		Canavan		
	a. First Name		b. Last Name		
	Tighe & Bond, Inc.				
	c. Company				
	120 Front Street, Su	uite 7			
	d. Street Address				
	Worcester				
			MA	01608	
	e. City/Town		 f. State	01608 g. Zip Code	
	•		f. State	g. Zip Code	
	e. City/Town (508) 471-9631 h. Phone Number	i. Fax Number		g. Zip Code	

### 5. Total WPA Fee Paid (from NOI Wetland Fee Transmittal Form):

N/A - Municipal Project	N/A - Fee Exempt	N/A - Fee Exempt
a. Total Fee Paid	b. State Fee Paid	c. City/Town Fee Paid



### Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands

# WPA Form 3 – Notice of Intent

Provided by MassDEP:

MassDEP File Number

Document Transaction Number Manchester-by-the-Sea City/Town

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

### A. General Information (continued)

6. General Project Description:

The Central Street bridge replacement project includes removing the tide gate and replacing the existing Central Street culvert with a 20-foot wide arch culvert. In addition, Central Street will have minimal roadway improvements conducted.

7a. Project Type Checklist:	(Limited Project Types see Section A. 7b.)
-----------------------------	--

1. Single Family Home	2.  Residential Subdivision
3. Commercial/Industrial	4. Dock/Pier
5. Utilities	6. 🗌 Coastal engineering Structure
7. Agriculture (e.g., cranberries, forestr	y) 8. 🛛 Transportation

- 9. 🗌 Other
- 7b. Is any portion of the proposed activity eligible to be treated as a limited project (including Ecological Restoration Limited Project) subject to 310 CMR 10.24 (coastal) or 310 CMR 10.53 (inland)?

1 IXI YASI I NO	If yes, describe which limited project applies to this project. (See 310 CMR 10.24 and 10.53 for a complete list and description of limited project types)	
310 CMR 10.24(7)(c)(2)	and 310 CMR 10.24(7)(c)(1)	
2. Limited Project Type		

If the proposed activity is eligible to be treated as an Ecological Restoration Limited Project (310 CMR10.24(8), 310 CMR 10.53(4)), complete and attach Appendix A: Ecological Restoration Limited Project Checklist and Signed Certification.

8. Property recorded at the Registry of Deeds for:

Essex	
a. County	b. Certificate # (if registered land)
881	173
c. Book	d. Page Number

### B. Buffer Zone & Resource Area Impacts (temporary & permanent)

- 1. Buffer Zone Only Check if the project is located only in the Buffer Zone of a Bordering Vegetated Wetland, Inland Bank, or Coastal Resource Area.
- 2. Inland Resource Areas (see 310 CMR 10.54-10.58; if not applicable, go to Section B.3, Coastal Resource Areas).

Check all that apply below. Attach narrative and any supporting documentation describing how the project will meet all performance standards for each of the resource areas altered, including standards requiring consideration of alternative project design or location.



### Massachusetts Department of Environmental Protection Bureau of Resource Protection - Wetlands Provided by MassDEP:

# WPA Form 3 – Notice of Intent

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

MassDEP File Number

Document Transaction Number Manchester-by-the-Sea City/Town

### B. Buffer Zone & Resource Area Impacts (temporary & permanent) (cont'd)

	<u>Resour</u>	<u>ce Area</u>	Size of Proposed Alteration	Proposed Replacement (if any)	
For all projects affecting other	a. 🗌 b. 🗍	Bank Bordering Vegetated	1. linear feet	2. linear feet	
Resource Areas, please attach a	<u>о</u> . Ш	Wetland	1. square feet	2. square feet	
narrative explaining how the resource	c. 🗌	Land Under Waterbodies and	1. square feet	2. square feet	
area was delineated.		Waterways	3. cubic yards dredged		
	<u>Resour</u>	ce Area	Size of Proposed Alteration	Proposed Replacement (if any)	
	d. 🗌	Bordering Land	A annual fact		
		Subject to Flooding	1. square feet	2. square feet	
	_		3. cubic feet of flood storage lost	4. cubic feet replaced	
	e. 🔛	Isolated Land Subject to Flooding	1. square feet		
			2. cubic feet of flood storage lost	3. cubic feet replaced	
	f. 🛛	Riverfront Area	Sawmill Brook (coastal) 1. Name of Waterway (if available) - <b>spe</b>	cify coastal or inland	
	2.	Width of Riverfront Area	(check one):		
		25 ft Designated D	ensely Developed Areas only		
		100 ft New agricult	ural projects only		
		🛛 200 ft All other proj	jects		
	3.	Total area of Riverfront Are	ea on the site of the proposed projec	ct: 4,4 <u>14 (in limit-of-work)</u> square feet	
	4.	Proposed alteration of the I	Riverfront Area:		
	4,4	414 (temporary)	4,414	0	
	a. t	total square feet	b. square feet within 100 ft.	c. square feet between 100 ft. and 200 ft.	
	5.	Has an alternatives analysi	is been done and is it attached to th	is NOI? Yes No	
	6.	Was the lot where the activ	vity is proposed created prior to Aug	ust 1, 1996? 🛛 🛛 Yes 🗌 No	
3	3. 🛛 Coa	astal Resource Areas: (See	e 310 CMR 10.25-10.35)		
	Note:	for coastal riverfront areas,	, please complete Section B.2.f. ab	ove.	



### Massachusetts Department of Environmental Protection Provided by MassDEP:

Bureau of Resource Protection - Wetlands

WPA Form 3 – Notice of Intent Massachusetts Wetlands Protection Act M.G.L. c. 131, §40 MassDEP File Number

Document Transaction Number Manchester-by-the-Sea City/Town

# B. Buffer Zone & Resource Area Impacts (temporary & permanent) (cont'd)

Check all that apply below. Attach narrative and supporting documentation describing how the project will meet all performance standards for each of the resource areas altered, including standards requiring consideration of alternative project design or location.

Online Users: Include your document		Resour	<u>ce Area</u>	Size of Proposed	Alteration	Proposed Replacement (if any)
transaction number		а. 🗌	Designated Port Areas	Indicate size un	der Land Under	the Ocean, below
(provided on your receipt page) with all supplementary information you		b. 🔀	Land Under the Ocean	0 (alteration), 35 (restoration) 80 2. cubic yards dredge		
submit to the Department.		с. 🗌	Barrier Beach	Indicate size und	er Coastal Beac	hes and/or Coastal Dunes below
		d. 🛛	Coastal Beaches	900 (temporary) 1. square feet		0 2. cubic yards beach nourishment
		e. 🗌	Coastal Dunes	1. square feet		2. cubic yards dune nourishment
				Size of Proposed	Alteration	Proposed Replacement (if any)
		f. 🛛	Coastal Banks	80 (temporary), 1 (permanent)	10	
		g. 🗌	Rocky Intertidal Shores	1. square feet		
		h. 🗌	Salt Marshes	1. square feet		2. sq ft restoration, rehab., creation
		i. 🗌	Land Under Salt Ponds	1. square feet		
		_		2. cubic yards dredge	ed	
		j. 🛄	Land Containing Shellfish	1. square feet		
		k. 🗌	Fish Runs			s, inland Bank, Land Under the Waterbodies and Waterways,
				1. cubic yards dredge	ed	
		I. 🛛	Land Subject to	6,058		
	4.	If the p	footage that has been enter			esource area in addition to the e, please enter the additional
		a. square	e feet of BVW		b. square feet of Sa	alt Marsh
	5.	🛛 Pro	oject Involves Stream Cros	sings		
					1	
		a. numbe	er of new stream crossings		b. number of replace	cement stream crossings



### Provided by MassDEP: Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands

# WPA Form 3 – Notice of Intent

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

MassDEP File Number

**Document Transaction Number** Manchester-by-the-Sea City/Town

### C. Other Applicable Standards and Requirements

This is a proposal for an Ecological Restoration Limited Project. Skip Section C and complete Appendix A: Ecological Restoration Limited Project Checklists - Required Actions (310 CMR 10.11).

### Streamlined Massachusetts Endangered Species Act/Wetlands Protection Act Review

1. Is any portion of the proposed project located in Estimated Habitat of Rare Wildlife as indicated on the most recent Estimated Habitat Map of State-Listed Rare Wetland Wildlife published by the Natural Heritage and Endangered Species Program (NHESP)? To view habitat maps, see the Massachusetts Natural Heritage Atlas or go to http://maps.massgis.state.ma.us/PRI\_EST\_HAB/viewer.htm.

a. 🗌 Yes 🛛 No	If yes, include proof of mailing or hand delivery of NOI to:
	Natural Heritage and Endangered Species Program
	Division of Fisheries and Wildlife
August 1, 2017	1 Rabbit Hill Road Westborough, MA 01581
b. Date of map	Westbolough, MA 01501

If yes, the project is also subject to Massachusetts Endangered Species Act (MESA) review (321 CMR 10.18). To qualify for a streamlined, 30-day, MESA/Wetlands Protection Act review, please complete Section C.1.c, and include requested materials with this Notice of Intent (NOI); OR complete Section C.2.f, if applicable. If MESA supplemental information is not included with the NOI, by completing Section 1 of this form, the NHESP will require a separate MESA filing which may take up to 90 days to review (unless noted exceptions in Section 2 apply, see below).

c. Submit Supplemental Information for Endangered Species Review\*

(a) within wetland Resource Area

percentage/acreage

(b) outside Resource Area

percentage/acreage

- 2. Assessor's Map or right-of-way plan of site
- 2. Project plans for entire project site, including wetland resource areas and areas outside of wetlands jurisdiction, showing existing and proposed conditions, existing and proposed tree/vegetation clearing line, and clearly demarcated limits of work \*\*
  - (a) Project description (including description of impacts outside of wetland resource area & buffer zone)
  - Photographs representative of the site (b)

<sup>\*</sup> Some projects not in Estimated Habitat may be located in Priority Habitat, and require NHESP review (see https://www.mass.gov/maendangered-species-act-mesa-regulatory-review).

Priority Habitat includes habitat for state-listed plants and strictly upland species not protected by the Wetlands Protection Act.

<sup>\*\*</sup> MESA projects may not be segmented (321 CMR 10.16). The applicant must disclose full development plans even if such plans are not required as part of the Notice of Intent process.



### Massachusetts Department of Environmental Protection Provided by MassDEP:

Bureau of Resource Protection - Wetlands

# WPA Form 3 – Notice of Intent

MassDEP File Number

Document Transaction Number Manchester-by-the-Sea City/Town

### Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

# C. Other Applicable Standards and Requirements (cont'd)

(c) MESA filing fee (fee information available at <u>https://www.mass.gov/how-to/how-to-file-for-a-mesa-project-review</u>).

Make check payable to "Commonwealth of Massachusetts - NHESP" and *mail to NHESP* at above address

Projects altering 10 or more acres of land, also submit:

- (d) Vegetation cover type map of site
- (e) Project plans showing Priority & Estimated Habitat boundaries
- (f) OR Check One of the Following
- 1. Project is exempt from MESA review. Attach applicant letter indicating which MESA exemption applies. (See 321 CMR 10.14, <u>https://www.mass.gov/service-details/exemptions-from-review-for-projectsactivities-in-priority-habitat</u>; the NOI must still be sent to NHESP if the project is within estimated habitat pursuant to 310 CMR 10.37 and 10.59.)

2.	Separate MESA review engoing		
2.	Separate MESA review ongoing.	a. NHESP Tracking #	b. Date submitted to NHESP

- 3. Separate MESA review completed. Include copy of NHESP "no Take" determination or valid Conservation & Management Permit with approved plan.
- 3. For coastal projects only, is any portion of the proposed project located below the mean high water line or in a fish run?

a. Not applicable – project is in inland resource area only	b. 🛛 Yes	🗌 No
---	----------	------

If yes, include proof of mailing, hand delivery, or electronic delivery of NOI to either:

South Shore - Cohasset to Rhode Island border, and North Shore - Hull to New Hampshire border: the Cape & Islands:


Division of Marine Fisheries -Southeast Marine Fisheries Station Attn: Environmental Reviewer 836 South Rodney French Blvd. New Bedford, MA 02744 Email: <u>dmf.envreview-south@mass.gov</u> Division of Marine Fisheries -North Shore Office Attn: Environmental Reviewer 30 Emerson Avenue Gloucester, MA 01930 Email: dmf.envreview-north@mass.gov

Also if yes, the project may require a Chapter 91 license. For coastal towns in the Northeast Region, please contact MassDEP's Boston Office. For coastal towns in the Southeast Region, please contact MassDEP's Southeast Regional Office.

c. Is this an aquaculture project?

d. 🗌	Yes	$\square$	No
u. 🔛	163		110

If yes, include a copy of the Division of Marine Fisheries Certification Letter (M.G.L. c. 130, § 57).



Applicants must include the following with this Notice of Intent (NOI). See instructions for details.

**Online Users:** Attach the document transaction number (provided on your receipt page) for any of the following information you submit to the Department.

- 1. USGS or other map of the area (along with a narrative description, if necessary) containing sufficient information for the Conservation Commission and the Department to locate the site. (Electronic filers may omit this item.)
- 2. Plans identifying the location of proposed activities (including activities proposed to serve as a Bordering Vegetated Wetland [BVW] replication area or other mitigating measure) relative to the boundaries of each affected resource area.



### Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands

# WPA Form 3 – Notice of Intent

Provided by MassDEP:

MassDEP File Number

Document Transaction Number Manchester-by-the-Sea City/Town

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

### D. Additional Information (cont'd)

- 3. Identify the method for BVW and other resource area boundary delineations (MassDEP BVW Field Data Form(s), Determination of Applicability, Order of Resource Area Delineation, etc.), and attach documentation of the methodology.
- 4.  $\square$  List the titles and dates for all plans and other materials submitted with this NOI.

Tighe & Bond, Inc.	David Loring, PE		
b. Prepared By	c. Signed and Stamped by		
	Varies		
d. Final Revision Date	e. Scale		
	September 2020		
f. Additional Plan or Document Title	g. Date		

- 6. Attach proof of mailing for Natural Heritage and Endangered Species Program, if needed.
- 7. Attach proof of mailing for Massachusetts Division of Marine Fisheries, if needed.
- 8. Attach NOI Wetland Fee Transmittal Form
- 9. Attach Stormwater Report, if needed.

### E. Fees

1. Kee Exempt: No filing fee shall be assessed for projects of any city, town, county, or district of the Commonwealth, federally recognized Indian tribe housing authority, municipal housing authority, or the Massachusetts Bay Transportation Authority.

Applicants must submit the following information (in addition to pages 1 and 2 of the NOI Wetland Fee Transmittal Form) to confirm fee payment:

2. Municipal Check Number	3. Check date
4. State Check Number	5. Check date
6. Payor name on check: First Name	7. Payor name on check: Last Name



### Massachusetts Department of Environmental Protection Provid Bureau of Resource Protection - Wetlands

WPA Form 3 – Notice of Intent

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP:

MassDEP File Number

Document Transaction Number Manchester-by-the-Sea City/Town

### F. Signatures and Submittal Requirements

I hereby certify under the penalties of perjury that the foregoing Notice of Intent and accompanying plans, documents, and supporting data are true and complete to the best of my knowledge. I understand that the Conservation Commission will place notification of this Notice in a local newspaper at the expense of the applicant in accordance with the wetlands regulations, 310 CMR 10.05(5)(a).

I further certify under penalties of perjury that all abutters were notified of this application, pursuant to the requirements of M.G.L. c. 131, § 40. Notice must be made by Certificate of Mailing or in writing by hand delivery or certified mail (return receipt requested) to all abutters within 100 feet of the property line of the project location.

1. Signature of Applicant

3. Signature of Property Owner (if different)

5. Signature of Representative (if any)

2. Date

4. Date 9/3/2020

6. Date

### For Conservation Commission:

Two copies of the completed Notice of Intent (Form 3), including supporting plans and documents, two copies of the NOI Wetland Fee Transmittal Form, and the city/town fee payment, to the Conservation Commission by certified mail or hand delivery.

### For MassDEP:

One copy of the completed Notice of Intent (Form 3), including supporting plans and documents, one copy of the NOI Wetland Fee Transmittal Form, and a **copy** of the state fee payment to the MassDEP Regional Office (see Instructions) by certified mail or hand delivery.

### Other:

If the applicant has checked the "yes" box in any part of Section C, Item 3, above, refer to that section and the Instructions for additional submittal requirements.

The original and copies must be sent simultaneously. Failure by the applicant to send copies in a timely manner may result in dismissal of the Notice of Intent.



### Massachusetts Department of Environmental Protection Bureau of Resource Protection - Wetlands **NOI Wetland Fee Transmittal Form**

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Important: When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.



1. Location of Proje	ect:		
Central Street (N	IA-127) and Elm Street	Manchester-by-the-Sea	
a. Street Address		b. City/Town	
		N/A - Fee Exempt as a M	unicipal Project
c. Check number		d. Fee amount	
2. Applicant Mailing	g Address:		
Gregory		Federspiel	
a. First Name		b. Last Name	
Town of Manche	ster-by-the-Sea		
c. Organization			
10 Central Stree	t		
d. Mailing Address			
Manchester-by-t	he-Sea	MA	01944
e. City/Town		f. State	g. Zip Code
(978) 526-2000	(978) 526-2001	federspielg@manchester.	ma.us
h. Phone Number	i. Fax Number	j. Email Address	
3. Property Owner	(if different):		
a. First Name		b. Last Name	
c. Organization			
d. Mailing Address			
e. City/Town		f. State	g. Zip Code
h. Phone Number	i. Fax Number	i. Email Address	

To calculate filing fees, refer to the category fee list and examples in the instructions for filling out WPA Form 3 (Notice of Intent).

**B.** Fees

Fee should be calculated using the following process & worksheet. Please see Instructions before filling out worksheet.

Step 1/Type of Activity: Describe each type of activity that will occur in wetland resource area and buffer zone.

Step 2/Number of Activities: Identify the number of each type of activity.

Step 3/Individual Activity Fee: Identify each activity fee from the six project categories listed in the instructions.

Step 4/Subtotal Activity Fee: Multiply the number of activities (identified in Step 2) times the fee per category (identified in Step 3) to reach a subtotal fee amount. Note: If any of these activities are in a Riverfront Area in addition to another Resource Area or the Buffer Zone, the fee per activity should be multiplied by 1.5 and then added to the subtotal amount.

Step 5/Total Project Fee: Determine the total project fee by adding the subtotal amounts from Step 4.

Step 6/Fee Payments: To calculate the state share of the fee, divide the total fee in half and subtract \$12.50. To calculate the city/town share of the fee, divide the total fee in half and add \$12.50.



### Massachusetts Department of Environmental Protection Bureau of Resource Protection - Wetlands NOI Wetland Fee Transmittal Form

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

### B. Fees (continued)

Step 1/Type of Activity	Step 2/Number of Activities	Step 3/Individual Activity Fee	Step 4/Subtotal Activity Fee
Category 4.f.	1	\$1,450	N/A - Fee Exempt
		otal Project Fee	
	Step 6/	Fee Payments:	
	Total	Project Fee:	N/A - Fee Exempt a. Total Fee from Step 5
	State share	of filing Fee:	N/A - Fee Exempt b. 1/2 Total Fee less \$12.50
	City/Town share	e of filling Fee:	N/A - Fee Exempt c. 1/2 Total Fee <b>plus</b> \$12.50

### **C. Submittal Requirements**

a.) Complete pages 1 and 2 and send with a check or money order for the state share of the fee, payable to the Commonwealth of Massachusetts.

Department of Environmental Protection Box 4062 Boston, MA 02211

b.) **To the Conservation Commission:** Send the Notice of Intent or Abbreviated Notice of Intent; a **copy** of this form; and the city/town fee payment.

**To MassDEP Regional Office** (see Instructions): Send a copy of the Notice of Intent or Abbreviated Notice of Intent; a **copy** of this form; and a **copy** of the state fee payment. (E-filers of Notices of Intent may submit these electronically.)

### Manchester Conservation Commission Instruction Checklist for Notices of Intent

### REVISION DATE: 6/18/20

- Fill out the "WPA Form 3 Notice of Intent" and the "NOI Wetland Fee Transmittal Form." These can be found at: <u>http://www.mass.gov/eea/agencies/massdep/service/approvals/wpa-form-3.html</u>. (Please note that the property owner MUST sign the NOI.)
- 2. Calculate the Manchester Wetlands Filing Fee. The fee schedule can be found on the Conservation webpage. In addition to the filing fees, submit \$50.00 to place the hearing notice in the Manchester Cricket (make check out to the Town of Manchester).
- 3. Applications must be accompanied by a narrative of the project, addressing how the project will meet the performance standards of the affected resource areas under both the Wetlands Protection Act (WPA) *and* the Manchester Wetlands By-Law. Be sure to include details of any mitigating measures such as erosion controls, wetlands plantings, etc. In addition, if you are proposing work in the 30-foot No-Disturb Zone or 50-foot No-Build Zone, you may have to submit an Alternatives Analysis per the local bylaw. Check with the Conservation Administrator.
- 4. Include engineered plans\* that show <u>all</u> resource areas including the following buffer zones:
  - a. 100-foot buffer
  - b. 50-foot No-Build Zone (local bylaw)
  - c. 30-foot No-Disturbance Zone (local bylaw)
- 5. Obtain a certified abutter's list from the Assessor's Office. This includes all abutters within 300 feet of your property line. (Make a copy for submittal with your application.)
- 6. Fill out the Notification to Abutters Under the Massachusetts Wetland Protection Act form, including the hearing date, and make one copy for each abutter. Send the "Notification to Abutters" form certified mail or by certificates of mailing to all abutters. Keep receipts of each certified mailing and submit these with your Notice of Intent application or at the first hearing. (Be sure to include the name and address of the abutter on each receipt or certificate.)
- 7. After notifying abutters, complete the Affidavit of Service form and submit it with your application.
- 8. Make packets (and copies) as described under "Submissions" below. Note that materials MUST BE collated into packets including *folded* plans.
- 9. Create electronic copies for submittal to the Conservation Office of all forms, plans and documentation (PDFs are preferred). Electronic copies may be submitted on a CD or e-mailed to the Conservation Administrator at: <u>bertonic@manchester.ma.us</u>. For files too large to email, contact the Administrator for more info.

\*See details of plan requirements in Appendix B (Section 1.6) of the Manchester Wetlands By-Law Regulations.

### eDEP Filing

Consider using DEP's online filing system (eDEP). This allows you to file *Notice of Intent* and *Abbreviated Notice of Resource Area Delineation* applications electronically with the state.

You may print a copy of your online filing and submit it as part of your application package as outlined below. Note that you must continue to submit hard-copy packages to the Manchester Conservation Office even if you file electronically with eDEP.

Go to: <u>www.mass.gov/dep/service/compliance/edeponlf.htm</u> for more information.

**NOTE:** Copies should be <u>double-sided</u> on recycled paper (at least 30% post-consumer content if possible). Do *not* include plastic covers or bindings.

### Please deliver the following to the Conservation Office by NOON pm on the Deadline Date:

- 1. Eight (8) Full Packages as described below, plus one additional set for MassDEP.
- 2. An electronic version of the package (e-mailed or contact the Conservation Administrator).
- 3. Three checks made out to the "Town of Manchester" for the following:
  - N/A D Town portion of State Filing Fee (Fee Exempt-Municipal Project)
  - N/A D By-Law Filing Fee (Fee Exempt- Municipal Project)
    - $\checkmark$  \$50.00 fee for the hearing notice to be placed in the Manchester Cricket

### FULL Package includes:

	Completed and <u>signed</u> NOI Form		Detailed narrative of the project and an Alternatives Analysis (if applicable)		Stormwater Report and Checklist (if applicable)
Ø	Completed NOI Wetland Fee Transmittal Form and copy of all checks	$\checkmark$	Any other supporting information to help describe the project	Ø	Receipts of certified mailing or certificates of mailing (due by first hearing)
	Full size plans, stamped and signed by a Professional Engineer or Land Surveyor		Certified abutters list from the Assessor's office	<ul><li>✓</li><li>1.</li><li>2.</li><li>3.</li></ul>	Fees: Town portion of WPA fee Town by-law filing fee Check to town for hearing notice
Ø	Affidavit of Service for abutter notification		Wetland delineation forms (if applicable)		Stormwater Calculations (if applicable)

### **MassDEP Submittal**

Mail a Full Package to <u>Mass DEP</u> Northeast Regional Office: MassDEP Northeast Regional Office

205B Lowell Street Wilmington, Massachusetts 01887

Mail the completed "NOI Wetland Fee Transmittal Form" and check to: Commonwealth of Massachusetts Department of Environmental Protection, Box 4062 Boston, MA 02211

Email a full Package to <u>NERO\_NOI@mass.gov</u> with the <u>required subject line</u>:

MANCHESTER – NOI – Street Address – Applicant name

(Note: the maximum file size MassDEP can receive is 15MB. For emailed submissions that exceed 15MB (e.g. NOIs), please break them into more than one email, with each email having the same subject line shown above, with 1, 2, 3...etc. at the end.)

*Please direct any questions to:* 

Chris Bertoni, Manchester Conservation Administrator bertonic@manchester.ma.us or 978-526-4397

### PLEASE ENSURE THAT <u>ALL ITEMS</u> ARE INCLUDED. INCOMPLETE APPLICATIONS MAY DELAY YOUR HEARING DATE!

# **PROJECT NARRATIVE**

# **Tighe&Bond**

**SECTION 1** 

# Section 1 Introduction

This Notice of Intent (NOI) is being submitted on behalf of the Town of Manchester-bythe-Sea (Town) for the Central Street Bridge Replacement Project (Project). The proposed project consists of the replacement of the Central Street Bridge through demolition of the existing 16-foot span and replacement with a 20-foot pre-cast concrete arch bridge. During the demolition of the exiting bridge an existing tide gate structure at the downstream face of the bridge will also be demolished and removed. The tide gate removal and increased hydraulic opening of the replacement bridge will significantly improve the tidal flushing at Sawmill Brook and Central Pond upstream of this road crossing and restore fish passage for the rainbow smelt; a "Species of Concern."

The bridge replacement includes roadway improvements at Central Street, including new ADA compliant sidewalks and curb ramps to enhance the walkability and accessibility of downtown Manchester-by-the-Sea.

# **1.1 Project Background and Purpose**

The Town of Manchester-by-the-Sea is a vibrant coastal community with an abundance of natural coastal resources, a stable population, and thriving year-round and seasonal businesses. Flooding events have severely impacted these assets in the past, including economic loss from businesses closed due to floods and disrupted utilities, flood related safety concerns due to impassable roadways and constrained access for emergency vehicles, inoperable wastewater and stormwater systems, and environmental concerns due to loss of habitat from tidal restrictions and erosion by flood waters.

Many areas of the Town of Manchester-by-the-Sea are subject to flooding during extreme storm events. Flooding is a particular problem within the Sawmill Brook watershed, particularly in the lower reaches of the Brook. Flood events during extreme storm events are due to the combination of storm surge, hydraulic restrictions from undersized culverts and the tide gate, stormwater runoff from impervious areas, the channelized stream system in the lower portion of the watershed, and poor infiltration conditions. In the lower reaches of Sawmill Brook, undersized culverts and an improperly functioning tide gate have caused stream banks to overtop, leading to stream bank erosion. The Fire Station and several residential and business properties surrounding Central Pond are periodically impacted by minor property flooding.

The Central Street tide gate and related structures are in need of modification to provide better functionality for drainage and fish passage. The tide gate and bridge at Central Street impede stream flows in Sawmill Brook, especially during coastal storm events, resulting in localized flooding. The Central Street Bridge structure currently overtops during extreme storm events and is structurally deficient. Seepage through the seawall due to hydrostatic pressure from the tide gate is damaging the roadbed. Culvert arch stones are becoming unstable. The tide gate and weir at the Central Street Bridge have been identified by the Division of Marine Fisheries as an impediment to fish passage, notably impacting rainbow smelt (*Osmerus mordax*), a diadromous fish species designated by the National Marine Fisheries Service as a "Species of Concern", a precursor to listing under the Federal Endangered Species Act. Numerous State and Federal agencies are supporting partners in the work to improve fish passage at the Central Street crossing of Sawmill Brook, providing grant funding, technical guidance, and public outreach support. These include Massachusetts Coastal Zone Management (CZM), Division of Ecological Restoration (DER), the Massachusetts Environmental Trust (MET), the Massachusetts Division of Marine Fisheries (DMF), and the National Oceanic and Atmosphere Administration (NOAA) Restoration Center.

The project has been further supported by dedicated Town Staff, the Board of Selectmen, the Manchester Coastal Resilience Advisory Group (CRAG), and Manchester Stream Team volunteers.

An Ecological Restoration Notice of Intent for the Central Pond and Sawmill Brook Restoration Project (MassDEP File number 039-0824), that includes the repair and replacement of failing retaining walls, the construction of living shoreline stabilization elements, and native plantings in order to enhance ecological conditions and coastal resiliency upstream of Central Street Bridge was issued an Order of Conditions on June 4, 2020. Additional approvals for the restoration project are pending review. An Environmental Notification Form (ENF, EEA #16127) was submitted to MEPA in December 2019 for both the Central Street Bridge Replacement Project and the Central Pond/Sawmill Brook Restoration Project, and a Certificate of the Secretary of Energy and Environmental Affairs on the ENF was received on January 10, 2020. These projects were separated in permit applications following the ENF because it is anticipated that funding sources for the bridge replacement will not be applicable to the ecological restoration and slope stabilization work.

A Site Locus Map (Figure 1), MassDEP Priority Resource Area Map (Figure 2), and Existing Conditions Map (Figure 3) are provided in Appendix A, that also includes project plans showing existing and proposed conditions. Photographs of the existing site are provided in Appendix B.

# **Tighe&Bond**

**SECTION 2** 

# Section 2 Existing Conditions

This section provides a description of the project area and a characterization of the wetland resources present at the site. Land use in the general vicinity of the project area was determined based on a review of information available through Massachusetts Geographic Information Systems (MassGIS) and site observations.

# **2.1 Project Site Conditions**

Sawmill Brook and associated tributaries have a five square mile watershed in the central portion of the Town of Manchester-by-the-Sea. Sawmill Brook flows to Manchester Harbor through a 16-foot wide bridge at Central Street (Route 127) that has a tide gate at the downstream face of the bridge. The crossing is constructed of three integrated parts including a bridge, tide gate and coastal wingwall. The bridge consists of a 16-foot span mortared stone masonry circular arch bridge with stone masonry wingwalls and headwalls. Timber cribs functioning as weirs are imbedded into the bottom of the stream bed. A concrete and iron tide gate abuts the bridge to the south. The bridge was rebuilt around the mid 1900's and a tide gate was installed to control the Brook and create Central Pond just upstream. A stone and masonry wingwall abuts the bridge in the southwest quadrant, functioning as a seawall.

Tighe & Bond evaluated the bridge and tide gate in June 2015. The passage under the bridge discharges flow from Sawmill Brook via a narrow, channelized reach, with 12-foot high granite walls and buildings abutting either side. The bridge has historically suffered due to the tide gate impound waters upstream of the bridge, causing seepage and loss of backfill material when large precipitation events and high tide elevations are concurrent. Multiple hydrologic and hydraulic models of the watershed and bridge indicate that the bridge opening is undersized to pass current design storm events without over-topping with concurrent tail water impacts due to storm surge.

In June of 2016, the bridge underwent interim repairs intended to temporarily stabilize the structure. The open joints were grouted using a pressure injection method and the void below the footing was formed and filled with cast-in-place concrete. An August 13, 2018 site visit confirmed the conditions observed in the 2015 site visit, including water seepage paths, damming conditions caused by the tide gate, separation and settlement of culvert arch stones, and concrete degradation.

The bridge is referenced in the Manchester Village National Register of Historic Places registration form as appearing to be of modern construction, and marks the entrance to downtown Manchester-by-the-Sea. Water, drainage, sewer, electric, and gas utilities are located within the roadbed over the arch bridge.

Downstream of the Central Street Bridge is the tide gate that consists of a concrete gravity weir surrounding the Sawmill Brook outlet. The Sawmill Brook passes through an opening in the weir restricted by a 6.5 by 5.5 foot cast iron slide gate controlled with an electric actuator. The actuator is located on a modern galvanized catwalk above the gate.

The tide gate serves as a major hydraulic restriction for Sawmill Brook. When the tide gate is closed, it reduces tidal fluctuations within Sawmill Brook and Central Pond,

Central Street Bridge Replacement Project NOI Narrative

although it is overtopped during very high tides. During rainstorms, it causes flooding of low-lying properties abutting Central Pond. To alleviate this flooding the slide gate has been left open, partially restoring upstream tidal flows.

The existing tide gate structure has a top of wall elevation just above mean higher high water level (MHHW), making this a significant obstruction to rainbow smelt passage during many high tides. Tidal water levels will rise over these walls on spring high tides (full moon or new moon) and during higher than predicted tides associated with atmospheric low pressure or wind setup, and such conditions will periodically allow rainbow smelt to swim over the walls when the tide gate is closed. This tide gate wall overtopping on spring high tides and storm surge tides does indicate that the tide gate is not effective in preventing seawater flooding.

Recent preliminary topographic survey indicates Central Street at this location is within about 1 foot of tidal flooding, based on recorded high tides from the storm of 1978 (NOAA Boston tide record at 93% height correction for Manchester). This was confirmed during the January 4, 2018 record high tide event during Winter Storm Grayson. The frequency of tidal flooding of the roadway will be increasing based on the current mean sea level rise relative to land (including land subsidence) of 0.92 feet per 100 years recorded in Boston (NOAA), and also based on forecast predictions of an increasing rate of relative sea level rise (IPCC).

This tide gate is a bottom opening gate that is not suitable to partial opening for smelt passage due to the head pressure and high flow velocities associated with a limited gate opening needed to maintain the impoundment pond. Full opening of the gate during smelt migration is feasible, though velocities during rainfall events would need to be checked relative to smelt swimming speeds. Even with the tide gate open to allow for fish passage, there are two more weirs inside the stone arch culvert. Since the smelt are not able to jump up weirs, the tide will need to rise to at least 2/3 of mean high tide to allow smelt to swim upstream past these weirs. The DER has selected this area as a provisional Massachusetts Priority Project due to the potential restoration benefits that can be realized in this location, and the level of commitment demonstrated by the community to accomplish these goals.

## 2.2 Wetland Resource Area Delineation Methodology

Tighe & Bond wetland scientists conducted an evaluation of wetland resource areas on April 18 and 19, 2019. Wetland resource areas regulated by the Massachusetts Wetland Protection Act (WPA) and the Manchester-by-the-Sea General Wetlands Bylaw (Article XVII) and regulations in the vicinity of the proposed work were delineated in accordance with 310 CMR 10.00 and MassDEP guidelines.

The following wetland resource areas were identified within the project area per WPA and the Town of Manchester-by-the-Sea Wetlands Bylaw:

- Coastal Bank
- Coastal Beach
- Land Under Ocean
- Riverfront Area
- 100-foot Buffer Zone

- Land Subject to Coastal Storm Flowage (LSCSF)
- 50-foot No Build Zone (Local Bylaw)
- 30-foot No Disturb Zone (Local Bylaw)

Descriptions of these resource areas are provided in the following sections.

## 2.3 Wetland Resource Areas

As noted above, resources areas subject to jurisdiction under the WPA and Article XVII were identified at the project site. Mean High Water (MHW) boundaries are shown on the project plans based on the elevation 3.1 feet (NAVD88). Note that the Sawmill Brook and Central Pond are both in transition from inland wetland resource areas to coastal resource areas and that as the restoration of tidal influence improves with removal of the tide gate, areas that may have previously been inland resource areas are now being characterized as coastal resource areas.

### 2.3.1 Land Under Ocean

Land Under Ocean (LUO) consists of the land beneath Sawmill Brook as it flows to Manchester Harbor. The upper limit of LUO is the Mean Low Water (MLW). Mean Lowest Low Water (MLLW) in the bay is estimated to be approximately -5.5 feet (NAVD88) based on the NOAA long-term tide water level monitoring station (ID 8443970). With the tide gate open the upstream bridge invert would become the control, so MLLW would need to be greater than the elevation of the upstream bridge invert, -0.2 feet. Tighe & Bond used data loggers upstream of Central Street from November 27, 2017 to May 4, 2018 to monitor water levels. Based on available data when the tide gate was open, MLW would be at approximately one foot within the pond and upstream areas of Sawmill Brook.

### 2.3.2 Coastal Beach

A regulatory definition of Coastal Beach (310 CMR 10.27) includes tidal flats, which are areas of land at elevations between MLW and MHW. The intertidal area within Sawmill Brook in the project area includes a range of substrates from bedrock through cobbles and coarse sand. This area was classified in the delineation as Coastal Beach and not Rocky Intertidal Shore because the area is not limited only to rocky substrates. The increased velocity of flows in Sawmill Brook at the relatively narrow bridge reduce the amount of fine grained sediment in the project area relative to the harbor or Central Pond.

### 2.3.3 Coastal Bank

Sawmill Brook is a tidal river. The banks confining this tidal waterway constitute a regulatory Coastal Bank consisting of elevated landforms abutting land subject to tidal action. The toe of the Coastal Bank is located along the MHW line of Sawmill Brook. The upper boundary (*i.e.*, top) of Coastal Bank was determined utilizing cross-sectional transects based upon field survey data as outlined in the *Massachusetts Department of Environmental Protection Coastal Banks Policy* (Wetlands Program Policy 92-1) and the *Applying the Massachusetts Coastal Wetlands Regulations* ("Coastal Manual") prepared by the CZM and MassDEP.

The eastern and western banks by the bridge have no regulatory WPA Coastal Bank based on the cross-sectional transect. Due to the location of the current infrastructure and nearby development, the transects encountered buildings. The transects stopped at the base of the buildings. The landform behind the retaining wall is considered Coastal Bank in this area. The Bank is armored with a wall in this section. The top of Bank generally consists of impervious surfaces associated with roadways, sidewalks, and parking lots, as well as maintained commercial lawns.

### **2.3.4 Riverfront Area**

The Sawmill Brook is shown as a perennial stream on the USGS topographic map (Marblehead North, Massachusetts; 1985); therefore, this river is afforded a 200-foot Riverfront Area. The Riverfront Area extends horizontally from the MHW line of Sawmill Brook. Riverfront Area at this site consists of commercial and residential development with maintained lawns. The mouth of coastal rivers mapping for Sawmill Brook (referred to Causeway Brook in the MA DEP mapping dated 3/1/2005, Figure 5) indicates that the tide gate and bridge at Central Street is the mouth of the coastal river and end of Riverfront Area.

### 2.3.5 Land Subject to Coastal Storm Flowage

According to the FEMA Flood Insurance Rate Map (FIRM) No. 25009C0434G (revised to reflect Letter of Map Revision (LOMR) effective 1/2/2017), the project area is within Zone A (1% Chance Flood with No Base Flood Elevation (BFE)). A Zone AE flood area is designated downstream of the project area with a BFE of 10 feet (NAVD88). The adjacent Zone AE elevation of 10 feet is used to provide the limit of Land Subject to Coastal Storm Flowage (LSCSF) within the project area. A detailed map of the FIRM at the project area is provided in Appendix A (Figure 4).

## 2.4 Rare Species

The Massachusetts Natural Heritage and Endangered Species Program (NHESP) Atlas, 14<sup>th</sup> Edition, effective August 1, 2017, was consulted during preparation of this application. According to this source, the proposed project area is not located within designated *Priority Habitats of Rare Species* or *Estimated Habitats of Rare Wildlife* and therefore will not require review pursuant to the Massachusetts Endangered Species Act.

# **Tighe&Bond**

**SECTION 3** 

# Section 3 Project Description

## 3.1 Alternatives Analysis

During a June 2015 in-water walk-through to view existing conditions evidence of advanced deterioration were observed at the Central Street bridge, including separation of joints, cracked blocks, wall seepage, and foundation undermining. Emergency repairs were made in June 2016 to temporarily stabilize the existing arch barrel and footing, but continued deterioration due to water seepage, scour, settling, and stone separation is inevitable without major repairs or replacement. The existing tide gate and bridge at Central Street impede flow from Sawmill Brook, especially during coastal storm events, resulting in localized flooding.

As the existing Central Street bridge is in deteriorating condition and is physically associated with the tide gate and adjacent Central Pond / Sawmill Brook, off-site alternatives would not meet project goals and were therefore not considered. On-site alternatives considered for the project included a no action alternative, repair, or replacement of the Central Street culvert/bridge. Factors considered in the evaluation of alternatives include environmental impacts, public safety, climate change resiliency, and rainbow smelt spawning condition improvements.

In both the repair and replacement alternatives, the existing tide gate is proposed to be removed as it has been identified by DMF, DER, and NOAA as an impediment to rainbow smelt fish passage. The existing deteriorated bridge is proposed to be rehabilitated or replaced to address public safety concerns. Alternatives for the bridge structure are limited by depth to bedrock, the presence of buildings immediately adjacent to the bridge and roadway, and constraints imposed by numerous utilities on the site.

### 3.1.1 No Action

The no action scenario would result in no immediate direct impacts or costs, but will result in increasing safety and functionality concerns over time, if deterioration of the bridge and tide gate is allowed to continue at the current pace. Impacts from flooding associated with the tide gate would continue to negatively affect adjacent property owners and rainbow smelt spawning conditions. As the no action alternative does not meet project goals of addressing failing infrastructure, reducing flooding and increasing resiliency, and improving habitat conditions and possibility for rainbow smelt, it is not preferred.

### 3.1.2 Rehabilitate Bridge and Culvert Structure, Remove Tide Gate

Rehabilitating the existing bridge and culvert structure and removing the tide gate structure is anticipated to result in improved hydraulic capacity, habitat restoration, improvements to aesthetics and water quality, and a reduction in upstream flooding due to the removal of the tide gate.

However, rehabilitation would only provide a temporary solution to the continued deterioration of the bridge and culvert structure, would not allow for implementation of pedestrian and traffic safety improvements, and would not maximize the bridge opening for the brook.

### 3.1.3 Replace Culvert with Bridge, Remove Tide Gate (Preferred)

The Town has identified the existing narrow roadway width of the Central Street bridge as a safety issue with respect to pedestrian, bicycle, and automobile traffic. Although options to widen the roadway are limited due to abutting businesses, even a modest increase in roadway width will improve safety. Concerns with the replacement alternative include temporary water quality impacts, a change in hydrology and increased tidal range relative to existing conditions, a shift in species, and temporary water quality impacts.

Replacing the existing culvert with a precast concrete bridge structure and removing the existing tide gate is anticipated to result in improved hydraulic capacity, habitat restoration, improvements to aesthetics and water quality, improvements to roadway safety, and a reduction in upstream flooding.

### **3.2 Proposed Activities**

The proposed condition improvements include removing the tide gate and replacing the existing Central Street culvert with a 20-foot wide arch culvert. The proposed culvert would maintain the existing upstream and downstream invert elevations (-0.2 feet NAVD88, and -4 feet NAVD88, respectively), and provide a constant low chord elevation of 6 feet NAVD88.

Removal of the tide gate and enlargement of the culvert will improve fish passage and increase the hydraulic capacity of Sawmill Brook reducing upstream flooding. Removing the tide gate will also limit the hydraulic pressure behind the seawall and reduce safety concerns. Restoration of the seawall and guard rail will improve traffic safety. Stream restoration will improve habitat and aesthetics in the downtown area. The public location is also ideal for educational signage about Sawmill Brook's natural history.

The proposed project includes:

- **Removal of the tide gate.** This work will include demolition of the concrete tide gate structure, slide gate, catwalk, and associated infrastructure to restore the unrestricted flow of Sawmill Brook into Manchester Harbor.
- **Replacement of the Central Street Bridge.** The existing bridge, including the concrete beam span section on the downstream side and upstream stone arch culvert, with be demolished and replaced with a concrete arch culvert with a span of approximately 20 feet, which will have greater capacity than the existing structure. The visible elements of the replacement structure and street furnishings will have a stone appearance in keeping with the aesthetic of the adjacent stone sea wall.
- **Central Street roadway improvements.** The roadway portion of this project is an isolated bridge reconstruction and not part of larger corridor improvement. Conscious effort was made to minimize the overall footprint of the work to limit impacts and cost. The existing horizontal and vertical alignments were matched to the extent practicable, roadway function was matched, and drainage patterns were preserved. Minor improvements were made to curb line geometry to improve overall traffic operation.

The proposed roadway section matches with the objectives of the Town of Manchester-by-the-Sea to have a more pedestrian friendly downtown village environment. The Town has taken a "complete streets" approach to the downtown

area including recent corridor improvement studies. The proposed roadway crosssection is consistent with the overall plan for the area and will interface well with future improvements. The design includes new ADA compliant sidewalks and curb ramps to enhance the walkability and accessibility of downtown. The design also includes a curb extension ("bump-out") on the bridge to enhance pedestrian safety and provide traffic calming along the corridor. Given the limited right-of-way, bicycle accommodation is provided in the travel lane. A "take-the-lane" cycling approach is appropriate through the downtown due to low motor vehicle speeds and ample sight distance.

The proposed project will be performed with measures to minimize potential construction disturbances. As noted below, in some instances specific construction means and methods will be determined by the contractor. Due to construction safety concerns, the contractor will be responsible for providing public safety protection measures, including safety signage and observation to ensure that the public stays at a safe distance from active equipment and does not enter potentially unsafe active work areas.

### **3.3 Site Access and Construction Staging**

Access to the proposed work area will be from Central Street. Staging of equipment and materials will likely be handled in the municipal parking lot along Church Street. Should this happen, existing parking on Church Street will be impacted temporarily. Staging areas will be surrounded with compost filter tube erosion barriers on the downhill side. During and after construction, all paved road and driveway surfaces are to be scraped and swept free of excavated materials on a daily basis. Final location of staging and material handling will be further defined during later stages of design development.

## **3.4 Anticipated Construction Sequence**

The following is a broad overview of a typical construction sequence for a project of this nature. The sequence may vary depending on the contractor's proposed schedule and means and methods.

- Notify pertinent regulatory agencies of the construction schedule
- Post MassDEP File Number sign at the entrance to the work areas
- Install erosion and sedimentation controls and establish work areas
- Schedule and conduct site walks with pertinent regulatory agencies to inspect construction-phase BMPs
- Install coffer dams, turbidity curtain, and oil booms for water control for phased construction at one abutment then the other
- Construct temporary Elm Street roadway and establish detours and road closures
- Provide temporary utilities as necessary for demolition
- Remove tide gate and existing bridge structure with demolition shielding
- Reconstruct Central Street bridge with roadway improvements
- Remove coffer dam, temporary stream access points and in-channel BMPs
- Restore disturbed areas in-kind

• Remove erosion and sedimentation controls pending approval from the Manchester-by-the-Sea Conservation Commission

### **3.5 Construction-Period Best Management Practices**

The following Best Management Practices (BMPs) will be implemented during construction to minimize the potential for impacts to jurisdictional resource areas. The Town will reserve the right to require supplemental and/or alternative construction BMPs during work depending on site and weather conditions. Additional details are provided on the Project Plans provided in Appendix A.

### **3.5.1 Limits of Work**

The upgradient boundary of work areas will be lined with orange safety fencing before the start of site clearing activities, except where chain link fencing is required to restrict public access.

### 3.5.2 Catch Basin Protection

Silt sacks will be installed in existing catch basins during construction.

### **3.5.3 Erosion Control Barriers**

Wetland resource areas at the site will be protected by compost filter tubes, or the approved equivalent. Protective measures will be placed in a fashion that restricts the contractor to the areas necessary to conduct the work and will define the limits of work. The locations of these barriers are illustrated on the Project Drawings provided in Appendix A and will also be used as staging and stockpile areas where appropriate. The Contractor will be required to maintain a reserve supply of compost filter tubes on-site to make repairs as necessary. Protective measures will be inspected after significant precipitation events and repaired as necessary.

### 3.5.4 Cofferdams

Cofferdams constructed of supersacks wrapped in impervious plastic liner with native alluvium backfill on the isolated side of the cofferdam are proposed to be placed upstream and downstream of the bridge replacement work area as shown on Sheets C-005 in the Project Plans provided in Appendix A. Dewatering pump discharge from within cofferdam work areas shall be released into sediment traps away from Sawmill Brook and construction activities, all return flows must meet permit requirements for turbidity, and pump intakes will be screened for fish protection. The cofferdam placement will be staged with demolition and construction work occurring at one of the bridge abutments and then switching to the opposite side. This will allow for continuous flow of Sawmill Brook throughout construction. The contractor will be required to submit a staging and dewatering plan for engineering review to ensure that adequate areas for flow in the channel are maintained. Additional cofferdam details are provided on Sheet C-504 in the Project Plans.

### 3.5.5 Dewatering

Construction dewatering shall be required during portions of construction which require excavation or other activities where groundwater may interfere with the work. Construction dewatering discharges shall be pre-treated for sediment removal by passing through an appropriately sized filter sock, silt bag, fractionation /sedimentation tank, or sediment trap prior to discharge, as necessary. The work will seek to minimize dewatering through the use of the cofferdams and avoiding work at high tides.

### 3.5.6 Stockpile Management

Stockpiles of materials removed during construction activities will be surrounded with an erosion control barrier around the perimeter of the stockpile. Stockpiles of erodible material are to be covered prior to inclement weather with a minimum of 20 mil polyethylene sheeting. Stockpiles left undisturbed longer than 14 days will be seeded or covered.

### 3.5.7 Site Restoration

Stabilization of disturbed areas or new soil fills shall be implemented within 14 days after grading or construction activities have permanently ceased. Appropriate vegetative soil stabilization is to be used to minimize erosion. Temporary and permanent vegetative cover is to be established in accordance with the Project plans provided in Appendix A. Restoration of upland areas will consist of replacement of topsoil or placement of imported loam as needed such that a minimum of 4 inches of suitable material is present and appropriately limed, fertilized, graded, and scarified. Disturbed upland areas shall then be hydroseeded with an approved dry site restoration seed mix at the rate recommended by the manufacturer. Final stabilization shall be considered complete when all soil-disturbing activities have been completed and a uniform, perennial vegetative cover with a density of eighty percent has been established or equivalent stabilization measures (such as the use of mulches or erosion control matting) have been employed on all unpaved areas and areas not covered by permanent structures.

# **Tighe&Bond**

**SECTION 4** 

# Section 4 Regulatory Compliance

The proposed project has been designed to avoid environmental impacts when possible, minimize unavoidable impacts when practicable, and provide mitigation that is commensurate with the proposed alterations. Descriptions of the project's compliance with the regulatory requirements of the WPA and the Manchester-by-the-Sea Wetlands Bylaw and Regulations (Article 17) are provided in the following sections.

# **4.1 Massachusetts Wetlands Protection Act**

### 4.1.1 Limited Project Status

The proposed bridge replacement qualifies for consideration as a Limited Project in accordance with 310 CMR 10.24(7)(c)(2):

The maintenance, repair and improvement (but not substantial enlargement except when necessary to reduce or eliminate a tidal restriction) of structures, including buildings, piers, towers, headwalls, bridges and culverts which existed on November 1, 1987.

The proposed roadwork replacement qualifies for consideration as a Limited Project in accordance with 310 CMR 10.24(7)(c)(1):

The maintenance and improvement of existing roadways, but limited to widening less than a single lane, adding shoulders, correcting substandard intersections, and improving inadequate drainage systems.

### 4.1.2 WPA Riverfront Area Exemption

The proposed bridge replacement is considered to be exempt from the requirements of the Riverfront Area performance standards in accordance with 310 CMR 10.02(2)(a)(2) as it consists of:

"activities conducted to maintain, repair or replace, but not substantially change or enlarge an existing and lawfully located structure... provided said work utilizes the best practical measures to avoid or minimize impacts to wetland resource areas outside the footprint of said structure or facility."

These activities within Riverfront Area are exempt under the WPA.

### 4.1.3 Summary of WPA Jurisdictional Alterations

Portions of the proposed activities will occur within areas subject to protection and jurisdiction under the WPA. These areas include Coastal Bank, LUO, Coastal Beach, Riverfront Area, LSCSF, and the 100-foot Buffer Zone. Both temporary and permanent impacts will occur in these areas. Table 5.1 provides a breakdown of temporary and permanent impact areas by resource area, as regulated under the WPA and Article XVII. The figures and project plans in Appendix A also depict the proposed activities and Resource Areas.

Resource Area	Resource Area Activity		Permanent Impacts (sf)	Total Disturbance (sf)
Coastal Bank <sup>a</sup>	Bridge Replacement	80 lf	10 lf	90 lf
Land Under Ocean	Tide gate removal	0	+353	353
Coastal Beach	Temporary cofferdam area	900	0	900
Riverfront Area – Inner 100 ft	Limits-of-work	4,414	0	4,414
LSCSF b Tide gate removal, limits-of- work		6,058	0	6,058
Total <sup>c</sup>		7,372	353	7,725

<sup>a</sup> Coastal Bank impacts are given in linear feet (lf), not square feet (sf)

<sup>b</sup> LSCSF is located within the 200 ft Riverfront Area

<sup>c</sup> Total impacts are in sf and therefore do not include If of Coastal Bank impacts

Wetland resource area impacts are primarily associated with temporary constructionperiod impacts during the bridge reconstruction. Construction-period impacts to existing, disturbed buffer zone to Coastal Bank are also anticipated. The Coastal Bank buffer zone is located within LSCSF and Riverfront Area. The work will only occur within the first 100 feet of Riverfront Area. As discussed previously, the tide gate and bridge at Central Street is the mouth of the coastal river and end of Riverfront Area.

As the proposed bridge reconstruction is located within the overall footprint of the existing bridge and roadway, there are minimal anticipated permanent impacts associated with that phase of the project. The permanent impacts associated with the tide gate removal result in a net increase in resource areas size for LUO and Coastal Beach.

#### **4.1.4 Performance Standards Compliance**

The following sections present the WPA performance standards for the impacted wetland resource areas (in *italic* font) and the proposed activities' compliance with these standards (in normal font). Impact areas presented in this section were calculated in AutoCAD using surveyed topography, delineated resource areas, and other site features.

#### 4.1.4.1 Land Under Ocean

The proposed tide gate removal and bridge replacement will result in permanent impacts to LUO, totaling approximately 353 square feet (sf). LUO will be restored in an approximately 353 sf area with the tide gate is removal. In addition, approximately 35 cubic yards (cy) will be dredged in order to install the bridge footings and remove the tide gate. The performance standards for LUO are set forth at 310 CMR 10.25(2), and a discussion of how the proposed project complies with these standards follows. Performance standards at 10.25(3) and (4) address navigation dredging and are not applicable to this project.

(5) Projects not included in 310 CMR 10.25(3) or (4) which affect nearshore areas of land under the ocean shall not cause adverse effects by altering the bottom topography so as to increase storm damage or erosion of coastal beaches, coastal banks, coastal dunes, or salt marshes. The proposed project is designed to minimize alterations of the LUO topography, only altering the areas necessary to remove the existing tide gate and to install the footings for the replacement bridge. The project involves the excavation of material to replace the existing bridge. These temporary impacts are necessary in order to reduce storm damage within the project area and within the riverine system. In addition, the bottom topography will be restored following the completion of construction.

(6) Projects not included in 310 CMR 10.25(3) which affect land under the ocean shall if water-dependent be designed and constructed, using best available measures, so as to minimize adverse effects, and if non-water-dependent, have no adverse effects, on marine fisheries habitat or wildlife habitat caused by:

(a) alterations in water circulation; (b) destruction of eelgrass (Zostera marina) or widgeon grass (Rupia maritina) beds; (c) alterations in the distribution of sediment grain size; (d) changes in water quality, including, but not limited to, other than natural fluctuations in the level of dissolved oxygen, temperature or turbidity, or the addition of pollutants; or (e) alterations of shallow submerged lands with high densities of polychaetes, mollusks or macrophytic algae.

The project is water dependent due to the placement of the existing infrastructure. The goal of the project is to improve natural tidal flow conditions in the project area by removing the existing tide gate to facilitate ecological restoration within the riverine system. Construction period impacts the conditions and resources listed in this performance standard will be minimized by limiting the open work area and by isolating in water work from stream and tidal flows. Best management practices outlined in Section 3.5 will be utilized during construction to minimize impacting the resource areas.

(7) Notwithstanding the provisions of 310 CMR 10.25(3) through (6), no project may be permitted which will have any adverse effect on specified habitat sites of rare vertebrate or invertebrate species, as identified by procedures established under 310 CMR 10.37.

The proposed project is intended to improve the existing habitat and fish passage within Sawmill Brook by removing the existing tide gate and restoring the tidal flow within the Brook. The impacts to the resource area are temporary and necessary to accomplish this goal. In addition, this area is not located within *Estimated Habitat of Rare Wildlife* or *Priority Habitat of Rare Species*.

#### 4.1.4.2 Coastal Beach

The proposed bridge replacement and tide gate removal will result in temporary impacts to Coastal Beach, totaling approximately 900 sf. Approximately 900 sf of Coastal Beach will be temporarily impacted as a result of the coffer dam placement which will facilitate the bridge replacement. The performance standards for Coastal Beach are set forth at 310 CMR 10.27(2), and a discussion of how the proposed project complies with these standards follows.

(3) Any project on a coastal beach, except any project permitted under 310 CMR 10.30(3)(a), shall not have an adverse effect by increasing erosion, decreasing the volume or changing the form of any such coastal beach or an adjacent or downdrift coastal beach.

The project's alteration of Coastal Beach is limited and is a result of the temporary installation of cofferdams to facilitate work in the dry for the bridge replacement and the tide gate removal.

(4) Any groin, jetty, solid pier, or other such solid fill structure which will interfere with littoral drift, in addition to complying with 310 CMR 10.27(3), shall be constructed as follows:

(a) It shall be the minimum length and height demonstrated to be necessary to maintain beach form and volume. In evaluating necessity, coastal engineering, physical oceanographic and/or coastal geologic information shall be considered.

(b) Immediately after construction any groin shall be filled to entrapment capacity in height and length with sediment of grain size compatible with that of the adjacent beach.

(c) Jetties trapping littoral drift material shall contain a sand by-pass system to transfer sediments to the downdrift side of the inlet or shall be periodically re-dredged to provide beach nourishment to ensure that downdrift or adjacent beaches are not starved of sediments.

This standard is not applicable to our project because the project is not in a littoral drift area.

(5) Notwithstanding 310 CMR 10.27(3), beach nourishment with clean sediment of a grain size compatible with that on the existing beach may be permitted.

Beach nourishment is not proposed as part of the project. Thus, this standard does not apply to the project.

#### 4.1.4.3 Coastal Bank

The proposed tide gate removal and bridge replacement will result in both temporary and permanent impacts to Coastal Bank, totaling approximately 90 linear feet (If). Approximately 80 If of Coastal Bank will be temporarily impacted as a result of the bridge replacement. Coastal Bank will be permanently impacted by a loss of approximately 10 If as the replacement bridge has a wider span. The Coastal Bank at the project site is a structural bank and does not serve as a source of sediment supply to an adjacent Coastal Bank are set forth at 310 CMR 10.30(6) through (8) and are addressed below.

The regulations at 310 CMR 10.30 state, "When a Coastal Bank is determined to be significant to storm damage prevention or flood control because it is a vertical buffer to storm waters, 310 CMR 10.30(6) through (8) shall apply:"

(6) Any project on such a coastal bank or within 100 feet landward of the top of such coastal bank shall have no adverse effects on the stability of the coastal bank.

The Coastal Bank is armored with a wall above and below the Central Street bridge. The proposed work will protect physical stability of the bank within these areas by maintaining the existing walls. The bank stability within the project area is not anticipated to be adversely affected by the bridge replacement or tide gate removal.

(7) Bulkheads, revetments, seawalls, groins or other coastal engineering structures may be permitted on such a coastal bank except when such bank is significant to storm damage prevention or flood control because it supplies sediment to coastal beaches, coastal dunes, and barrier beaches.

The Coastal Bank within the project area is classified as a structural bank as it serves as a vertical buffer to tidal water. The bank does abut a regulatory Coastal Beach, but it is not a significant supplier of sediment to those resource areas as the existing Coastal Bank is armored. The proposed project is not anticipated to interfere with the bank's function in terms of flood control and/or storm damage protection. The expansion of the existing hydraulic opening of the bridge is intended to improve the flood conditions within the area. As this Coastal Bank is not a sediment supply to a beach and is a structural bank, the replacement of the bridge and the tide gate removal are not anticipated to adversely affect the functions of this bank relative to sediment supply.

(8) Notwithstanding the provisions of 310 CMR 10.30(3) through (7), no project may be permitted which will have any adverse effect on specified habitat sites of rare vertebrate or invertebrate species, as identified by procedures established under 310 CMR 10.37.

The proposed project will not adversely affect the quality or degree of habitat on-site. As mentioned above, this area is not located within *Estimated Habitat of Rare Wildlife* or *Priority Habitat of Rare Species*.

#### 4.1.5 Abutter Notification

Abutters were notified in accordance with the requirements set forth by the WPA and Article XVII. The abutter notification form and a copy of the certified list of abutters prepared by the Manchester-by-the-Sea Assessors Office is provided in Appendix C.

#### 4.1.6 Stormwater Management

As described in the Stormwater Checklist and Report provided in Appendix D, the proposed redevelopment project does not create any new point source discharge of stormwater runoff to Sawmill Brook, and will not result in a net change in impervious ground surface over existing conditions. The project is not considered to be a Land Use with Higher Potential Pollutant Loads (LUHPPL). The project design includes conveyance of runoff from the proposed roadway improvement areas to a stormwater treatment unit prior to discharge, as described in the Long-Term Pollution Prevention Plan in Appendix D. Construction-period erosion and sedimentation controls are identified on the Project Plans provided in Appendix A.

#### 4.2 Manchester-by-the-Sea Wetlands Bylaw

The proposed activities are also subject to the Town of Manchester-by-the-Sea Wetlands Protection By-law (Article XVII of the General By-laws) and Town of Manchester-by-the-Sea Wetlands Regulations. The proposed work will occur within Riverfront Area, Coastal Bank, LUO, Coastal Beach, the No Disturb Zone, and the No Build Zone. The following sections will discuss the resource areas with stricter performance standards than are set forth under the WPA.

#### 4.2.1 Coastal Bank

Section 9.6 of the Town of Manchester-by-the-Sea Wetlands Regulations establishes additional Coastal Bank performance standards from the WPA as follows:

Prior to the issuance of a permit for work or activity which Alters a Coastal Bank, the Applicant shall demonstrate by Clear and Convincing Evidence as set forth in an Alternatives Analysis that there is no Practicable Alternative to the work or activity proposed.

Due to the existing placement of the infrastructure, work needs to be performed on the Coastal Bank in order to repair the existing wall and stabilize the area.

The preferred stabilization methods for coastal banks include, but are not limited to, protective plantings and other non-structural stabilization techniques. Any Alteration which includes new, or the expansion of existing, coastal engineering structures such as, but not limited to, bulkheads, revetments, seawalls, or groins shall not be permitted without Clear and Convincing Evidence that:

9.6.1 the structure can be constructed to maintain structural integrity and stability for at least twenty-five (25) years at the locus; and 9.6.2 there is no other technically feasible method of protecting a building or property other than the proposed coastal engineering structure and that any such structure shall not have an adverse impact on adjacent or nearby coastal banks, beaches or dunes.

and

9.6.2 there is no other technically feasible method of protecting a building or property other than the proposed coastal engineering structure and that any such structure shall not have an adverse impact on adjacent or nearby coastal banks, beaches or dunes

The proposed project involves the replacement of an existing bridge located in downtown Manchester-by-the-Sea. The replacement bridge will be located within the footprint of the old bridge, so no new structure is proposed. The new bridge will have an increase hydraulic capacity so will improve the in-stream resource conditions. The anticipated design life of the bridge is approximately 75 years. Due to the location of existing buildings east and west of the bridge and the existing ecology of the stream, plantings and non-structural stabilization techniques are not feasible within this area. As stated above, the Coastal Bank serves as a structural Bank and the replacement of it in-kind is not anticipated to have any adverse impact on the Coastal Beach or other resource areas.

#### 4.2.2 Riverfront Area

Section 9.8 of Article XVII establishes additional Riverfront Area performance standards from the WPA.

*9.8.1 there is no practicable alternative to the proposed project with less adverse effects; and* 

9.8.2 such activities, including proposed mitigation measures, will have no significant adverse impact on the areas or values protected by this By-Law.

Section 3.1 details the alternative analysis for Riverfront Area. As stated previously, due to the location of the existing infrastructure, the project cannot be moved to another location. The only practical alternative to address the current condition of the infrastructure is to replace the current bridge. In addition, the removal of the tide gate will improve the ecological conditions within the Sawmill Brook.

#### 4.2.3 No Disturb Zone

Section 10.1 of Article XVII establishes a 30-foot No Disturb Zone (NDZ). The NDZ consists of residential and commercial buildings, paved roadways and commercial parking lots, and commercial lawns. The proposed bridge replacement and roadway improvements.

#### 4.2.3.1 No Disturb Zone Waiver Request

Due to the location of the existing infrastructure, it is not possible to move the project outside of the NDZ to avoid impacts to this area. The project has been designed to limit the impacts to the NDZ to the extent practicable. The current conditions involve frequent flooding of the nearby infrastructure, including the Fire Department. The replacement of the bridge includes design elements to improve conditions relating to flooding, fish passage, and roadway safety. The temporary disturbance would be negligible compared to the continued deterioration of the bridge and roadway. Therefore, the Town respectfully requests a variance to conduct work within the NDZ.

#### 4.2.4 No Build Zone

The No Build Zone (NBZ) is defined as the 50-foot area landward of resource areas, in accordance with Section 10.1 of Article XVII. The NBZ consists of residential and commercial buildings with maintained lawns, and paved roadways and commercial parking lots. The project proposes to replace the existing bridge and conduct roadway improvements within the NBZ.

#### 4.2.4.1 No Build Zone Waiver Request

Due to the location of the existing infrastructure, it is not possible to move the project to another location. The Town respectfully requests a variance to conduct work within the No Build Zone.

J:\M\M1476 Manchester MA Hydro Study\011-Central Street Bridge\Permitting\NOI\Word Docs\3 - Draft Central Street Bridge NOI Narrative.docx

APPENDIX A

FIGURES



Central Street Bridge Replacement/

September 2019


Sawmill Brook Restoration Project Manchester-by-the-Sea, Massachusetts

Tighe&Bond Based on USGS Topographic Map for Marblehead North, MA Revised 1985. Contour Interval Equals 3-Meters. Circles indicate 500-foot and half-mile radii Engineers | Environmental Specialists

1:24,000 D 1.000 2,000 Ń Feet


476\CentralSt\_Bridge\_MA\Maps\CentralSt\_Bridge\_MA\_Topo.mxd [Exported By: kjw, 9/19/2019, 1:15:59 PM

Limit of Work



V:\Projects\M\m1476\CentralSt\_Bridge\_MA\Maps\CentralSt\_Bridge\_MA\_Resource.mxd [Exported By: kjw, 9/19/2019, 1:17:02 PM]

M-14







September 2019


Central Street Bridge Replacement/ Sawmill Brook Restoration Project Manchester-by-the-Sea, Massachusetts


V:\Projects\M\m1476\CentralSt\_Bridge\_MA\Maps\CentralSt\_Bridge\_MA\_Aerial.mxd [Exported By: kjw, 9/19/2019, 1:15:21 PM]

# National Flood Hazard Layer FIRMette


70°46'41"W 42°34'42"N








regulatory purposes.



# TOWN OF MANCHESTER-BY-THE-SEA, MASSACHUSETTS CENTRAL STREET BRIDGE RECONSTRUCTION PROJECT NO: M1476-011 SEPTEMBER 2020

	LIST OF DRAWINGS		
SHEET NO.	SHEET TITLE		
	COVER		
G-001	LEGEND, ABBREVIATIONS, AND GENERAL NOTES		
C-001	CENTRAL STREET SURVEY 1 OF 4		
C-002	CENTRAL STREET SURVEY 2 OF 4		
C-003	CENTRAL STREET SURVEY 3 OF 4		
C-004	CENTRAL STREET SURVEY 4 0F 4		
C-005	DEMOLITION PLAN & SITE PREPARATION PLAN		
C-101	SITE PLAN AND PROFILE		
C-102	UTILITY PLAN		
C-103	TEMPORARY ROAD & UTILITY PLAN		
C-501 TO C-502	CONSTRUCTION DETAILS		
C-503	COASTAL BANK PLAN		
C-504 TO C-505	CONTROL OF WATER NOTES AND DETAILS		
C-701	TEMPORARY TRAFFIC CONTROL PLAN - GENERAL		
C-702	TEMPORARY TRAFFIC CONTROL PLAN - DETOUR		
S-001 TO S-103	BRIDGE DRAWINGS		

PERMIT SET **NOT FOR CONSTRUCTION** 



LOCATION MAP SCALE: 1" = 2000'

PREPARED FOR:

TOWN OF MANCHESTER-BY-THE-SEA DEPARTMENT OF PUBLIC WORKS CHUCK DAM, DIRECTOR

BOARD OF SELECTMEN ELI BOLING, CHAIR JEFFERY BODMER-TURNER, VICE CHAIR ANN HARRISON **BECKY JAQUES** JOHN ROUND





# **COMPLETE SET 23 SHEETS**

	NERAL NOTES	LEGEND
1.	BASE PLAN ENTITLED "MASSACHUSETTS DEPARTMENT OF TRANSPORTAION PLAN OF TOPOGRAPHIC SURVEY OF CENTRAL STREET, MANCHESTER BY THE SEA" PREPARED BY DOUCET SURVEY INC. ON NOVEMBER 9, 2018.	EXISTIN
2.	THE HORIZONTAL DATUM IS BASED ON THE NORTH AMERICAN DATUM OF 1983 (NAD83). THE VERTICAL DATUM IS BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88).	C UP
3.	BOLD TEXT AND LINES INDICATES PROPOSED WORK. LIGHT TEXT AND LINES INDICATES APPROXIMATE EXISTING CONDITIONS.	
ŀ.	WETLAND RESOURCE AREAS WERE DELINEATED BY TIGHE & BOND ON APRIL 18, 2018.	OE 
<b>.</b>	SOIL BORINGS WERE PERFORMED BY NEW ENGLAND BORING CONTRACTORS ON AUGUST 9, 2018.	
•	NOTIFY "DIGSAFE" AT 1-888-344-7233 TO ARRANGE FOR MARKING OUT EXISTING UNDERGROUND UTILITIES AT LEAST 72 HOURS (EXCLUDING SATURDAYS, SUNDAYS, AND HOLIDAYS) PRIOR TO BEGINNING EXCAVATION AT ANY GIVEN LOCATION.	ሮ
	UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR BE ALLOWED TO START ANY KIND OF EXCAVATION WORK PRIOR TO OBTAINING ALL THE NECESSARY INFORMATION REGARDING THE LOCATION OF UNDERGROUND UTILITIES AT THE SITE. ACCOMPLISH ALL EXCAVATION SO THAT UNDERGROUND UTILITIES OR STRUCTURES ARE NOT DAMAGED. CONTRACTOR	þ
	SHALL BE RESPONSIBLE FOR ANY DAMAGE INCURRED DURING EXCAVATION OPERATIONS. REPAIR ANY EXISTING PIPE OR UTILITY DAMAGED DURING CONSTRUCTION AT NO ADDITIONAL COST TO THE OWNER.	
7.	THE OWNER AND ENGINEER ASSUME NO RESPONSIBILITY FOR THE LOCATION OF EXISTING UTILITIES. THE ENGINEER AND OWNER MAKE NO GUARANTEE AS TO THE UNDERGROUND CONDITIONS THAT MAY BE ENCOUNTERED.	
3.	FIELD MEASURE TO VERIFY EXISTING AND CONTRACT INTERFACE DIMENSIONS, LOCATIONS, AND OTHER CONDITIONS.	
-	TEST PITS TO LOCATE EXISTING UTILITIES ARE STRONGLY ENCOURAGED AND MAY BE ORDERED BY THE ENGINEER.	- <b>-</b>
0.	IF CHANGES TO THE DESIGN ARE PROPOSED, THE CHANGES SHALL BE SUBMITTED TO THE OWNER/ENGINEER FOR REVIEW AND APPROVAL PRIOR TO CONSTRUCTION.	345.4
1.	MAKE NECESSARY ARRANGEMENTS TO PERFORM ANY WORK NEAR THE OVERHEAD UTILITIES PRIOR TO THE START OF CONSTRUCTION.	<ul> <li>1B−6</li> </ul>
2.	EXISTING UTILITY POLES IN CLOSE PROXIMITY TO CONSTRUCTION MAY REQUIRE TEMPORARY SUPPORT BY THE UTILITY COMPANY. INCLUDE COST UNDER THE PRICES BID FOR THE VARIOUS ITEMS OF WORK.	
3.	NO OPEN TRENCHES WILL BE ALLOWED OVERNIGHT. THE USE OF ROAD PLATES TO PROTECT THE EXCAVATION WILL BE	
4.	CONSIDERED UPON REQUEST, BUT BACKFILLING IS PREFERRED. STORE FUEL, OIL, PAINT, OR OTHER HAZARDOUS MATERIALS IN A SECONDARY CONTAINER AND REMOVE FROM THE SITE TO	
	A LOCKED INDOOR AREA WITH AN IMPERVIOUS FLOOR DURING NON-WORK HOURS.	
	IMMEDIATELY REPORT SPILLS OF OIL AND/OR HAZARDOUS MATERIALS (OHM) TO THE MASSDEP. PROVIDE A SUFFICIENT SUPPLY OF ABSORBENT SPILL RESPONSE MATERIALS, SUCH AS BOOMS OR BLANKETS, AT THE	
	CONSTRUCTION SITE AT ALL TIMES TO CLEAN UP POTENTIAL SPILLS OF HAZARDOUS MATERIALS.	
/.	FURNISH AND INSTALL TRAFFIC CONTROL/SAFETY DEVICES TO ENSURE SAFE VEHICULAR TRAFFIC THROUGH THE WORK AREA OR FOR SAFELY IMPLEMENTING DETOURS AROUND THE WORK AREA.	
<u>SL</u>	RFACE RESTORATION NOTES	
1.	RESTORE ALL AREAS DISTURBED BY THE CONTRACTOR BEYOND THE LIMITS OF WORK TO ORIGINAL CONDITIONS AT NO ADDITIONAL COST TO THE OWNER.	
2.	ALL PAVEMENT DAMAGED BY THE CONTRACTOR'S OPERATIONS SHALL BE REPLACED IN ACCORDANCE WITH THE	
3.	CONTRACT DOCUMENTS. PROTECT SURFACE FEATURES (E.G., WALLS, FENCES, MAIL BOXES, SIGNS, SIDEWALKS, CURBING, STAIRS, WALKWAYS, TREES, ECT.) FROM DAMAGE DURING CONSTRUCTION, INCLDING PROVIDING TEMPORARY SUPPORTS, WHEN	
4	TREES, ECT.) FROM DAMAGE DURING CONSTRUCTION, INCLDING PROVIDING TEMPORARY SUPPORTS, WHEN APPROPRIATE.	
4.	IF REMOVAL OF SURFACE FEATURES IS REQUIRED IN ORDER TO PERFORM THE PROPOSED WORK, REMOVE THOSE SITE FEATURES ONLY UPON APPROVAL OF ENGINEER. REPLACE ALL REMOVED SITE FEATURES; NEW ITEMS SHALL BE EQUAL OR BETTER IN QUALITY AND CONDITION TO THE ITEMS REMOVED.	
5.	EXISTING SURVEY MONUMENTS DISTURBED BY THE CONTRACTOR SHALL BE REPLACED BY A LAND SURVEYOR LICENSED	
6.	IN THE STATE IN WHICH THE WORK IS PERFORMED AT NO ADDITIONAL COST TO THE OWNER. REPAIR DISTURBED PAVED SURFACES AT THE END OF EACH WORK WEEK, UNLESS OTHERWISE APROVED/REQURIED BY	
0.	THE OWNER.	

## END


#### EXISTING NEW IRON PIPE FOUND UTILITY POLE ு UP \_ \_\_ \_\_ \_\_ BURIED DRAIN PIPE - -- -- ---\_\_\_\_\_ OVERHEAD UTILITY WIRES DF \_\_\_\_\_ FENCE (SIZE AND TYPE NOTED) GUARDRAIL \_\_\_\_\_ APPROXIMATE PROPERTY LINE · \_\_\_\_\_ SIGN AND POST TREE LINE · · · · · · -490-INDEX CONTOUR \_\_\_\_\_ INTERMEDIATE CONTOUR STONEWALL BORING B-1351.3 PROFILE ELEVATIONS 5.4 B-6 WETLAND FLAGS WETLAND SYMBOL LAND SUBJECT TO COASTAL STORM FLOWAGE 100-FOOT BUFFER ZONE 200-FOOT RIVERFRONT AREA 30-FOOT NO DISTURBANCE ZONE 50-FOOT NO BUILD ZONE \_\_\_\_ COASTAL BANK \_ \_ \_\_\_\_ TEMPORARY COFFER DAM EROSION CONTROL BARRIERS


SURVEYED EDGE OF WATER (APRIL 2018)

#### ABBREVIATIONS

GENERAL	
ABAN	ABANDON
ADJ	ADJUST
APPROX	APPROXIMATE
ASTM	AMERICAN SOCIETY OF TESTING MATERIALS
BIT	BITUMINOUS
BOS	BOTTOM OF SLOPE
BVW	BORDERING VEGETATIVE WETLANDS
СС	CONCRETE CURB
CCW	CEMENT CONCRETE WALK
CEM	CEMENT
CLF	CHAIN LINK FENCE
СМР	CORRUGATED METAL PIPE
CONC	CONCRETE
CS	CUT SPIKE
CW	CONCRETE WALK
DIM	DIMENSION
DPW	DEPARTMENT OF PUBLIC WORKS
EOP	EDGE OF PAVEMENT
EXIST	EXISTING
I	FEET/FOOT
FDN	FOUNDATION
FND	FOUND
GC	GRANITE CURB
GE	GRANITE EDGING
GRAN	GRANITE
HMA "	HOT MIX ASPHALT
	INCH IN FRONT OF
IFO IP	IRON PIN
LSCSF	LAND SUBJECT TO COASTAL STORM FLOWAGE
MASSDEP	MASSACHUSETTS DEPARTMENT OF ENVIRONMENTAL PROTECTION
MAX	MAXIMUM
MIN	MINIMUM
MHD	MASSACHUSETTS HIGHWAY DEPARTMENT
М	MHD MATERIAL REFERENCE
MISC	MISCELLANEOUS
N/F	NOW/FORMERLY
NTS	NOT TO SCALE
PREF	PREFERRED
PROP	PROPOSED
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
PVMT	PAVEMENT
QTY	QUANTITY
REMOD	REMODEL
REM	REMOVE
REQD	REQUIRED
RET	RETAIN
R&D	REMOVE AND DISPOSE
R&R	REMOVE AND RESET
R&S SB	REMOVE AND STACK STONE BOUND
SF	SQUARE FEET
SPKS	SURVEY SPIKE
TOS	TOP OF SLOPE
ТҮР	TYPICAL
VGC	VERTICAL GRANITE CURB
WCR	WHEELCHAIR RAMP
YD	YARD

<u>01</u>	ILITIES
C	ASBESTOS CEMENT PIPE
	ASPHALT COATED CORRUGATED METAL PIPE
CAP CB	CORRUGATED ALUMINUM PIPE CATCH BASIN
CI	CAST IRON PIPE
CIT	CHANGE IN TYPE
СМР	CORRUGATED METAL PIPE
CNO	COULD NOT OPEN
COND CPP	CONDUIT CORRUGATED PLASTIC PIPE
CS	CURB STOP
DIA	DIAMETER
DI	DUCTILE IRON PIPE
омн	DRAIN MANHOLE
ЕМН	ELECTRIC MANHOLE
<sup>-</sup> &C	FRAME AND COVER
=&G	FRAME AND GRATE
SSO IH	GAS SHUT OFF HANDHOLE
HYD	HYDRANT
INV	INVERT ELEVATION
CΝ	MECHANICAL JOINT
мw	MONITORING WELL
PVC	POLYVINYLCHLORIDE PIPE
RCP	REINFORCED CONCRETE PIPE
RP SC	RECORD PLAN STORM WATER TREATMENT UNIT
SD	STORM DRAIN LINE
SMH	SEWER MANHOLE
rsv&B	TAPPING SLEEVE, VALVE AND BOX
JP	UTILITY POLE
WG WSO	WATER GATE WATER SHUT OFF
AI IGNMI	NT/PROFILE
٩D	ENT/PROFILE ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE
AD BL CC	ALGEBRAIC DIFFERENCE
AD BL CC	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST
AD BL CC EL/ELEV	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION
AD BL CC EL/ELEV GB	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION GRANITE BOUND
AD EC EL/ELEV GB	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION
ND EC EL/ELEV BB	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION GRANITE BOUND RATE OF VERTICAL CURVATURE
ND EC EL/ELEV BB	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION GRANITE BOUND RATE OF VERTICAL CURVATURE LENGTH
AD EC EL/ELEV GB C T N DC	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION GRANITE BOUND RATE OF VERTICAL CURVATURE LENGTH LEFT NORTH ON CENTER
AD AD CC EL/ELEV GB C T N DC PC	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION GRANITE BOUND RATE OF VERTICAL CURVATURE LENGTH LEFT NORTH ON CENTER POINT OF CURVE
AD C C C C C C C C C C C C C	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION GRANITE BOUND RATE OF VERTICAL CURVATURE LENGTH LEFT NORTH ON CENTER POINT OF CURVE POINT OF COMPOUND CURVE
AD AD CC EL/ELEV GB C T N DC PC PC PK/SPIKE	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION GRANITE BOUND RATE OF VERTICAL CURVATURE LENGTH LEFT NORTH ON CENTER POINT OF CURVE
AD EC EL/ELEV GB C T I DC PC PCC PK/SPIKE	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION GRANITE BOUND RATE OF VERTICAL CURVATURE LENGTH LEFT NORTH ON CENTER POINT OF CURVE POINT OF COMPOUND CURVE SURVEY NAIL
AD AD CC CC CC CB CC CC PC PC PC PC PC PC PC PC	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION GRANITE BOUND RATE OF VERTICAL CURVATURE LENGTH LEFT NORTH ON CENTER POINT OF CURVE POINT OF CURVE SURVEY NAIL PROPERTY LINE
AD AD AD AD AD AD AD AD AD AD	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION GRANITE BOUND RATE OF VERTICAL CURVATURE LENGTH LEFT NORTH ON CENTER POINT OF CURVE POINT OF COMPOUND CURVE SURVEY NAIL PROPERTY LINE POINT OF REVERSE CURVE POINT OF REVERSE CURVE
AD AD AD AD AD AD AD AD AD AD	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION GRANITE BOUND RATE OF VERTICAL CURVATURE LENGTH LEFT NORTH ON CENTER POINT OF CURVE POINT OF COMPOUND CURVE SURVEY NAIL PROPERTY LINE POINT OF REVERSE CURVE POINT OF REVERSE CURVE POINT OF VERTICAL CURVE POINT OF VERTICAL CURVE
AD BL CC E EL/ELEV GB C GB C T N DC PC PC PC PC PK/SPIKE PRC PT PVC PVC PVC	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION GRANITE BOUND RATE OF VERTICAL CURVATURE LENGTH LEFT NORTH ON CENTER POINT OF CURVE POINT OF CURVE SURVEY NAIL PROPERTY LINE POINT OF REVERSE CURVE POINT OF TANGENT POINT OF VERTICAL CURVE POINT OF VERTICAL CURVE
AD BL CC E EL/ELEV GB C - - T N DC PC PC PC PC PC PC PC PC PC P	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION GRANITE BOUND RATE OF VERTICAL CURVATURE LENGTH LEFT NORTH ON CENTER POINT OF CURVE POINT OF CURVE SURVEY NAIL PROPERTY LINE POINT OF REVERSE CURVE POINT OF TANGENT POINT OF VERTICAL CURVE POINT OF VERTICAL CURVE POINT OF VERTICAL COMPOUND CURVE POINT OF VERTICAL COMPOUND CURVE
AD AD AD AD AD AD AD AD AD AD	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION GRANITE BOUND RATE OF VERTICAL CURVATURE LENGTH LEFT NORTH ON CENTER POINT OF CURVE POINT OF CURVE POINT OF COMPOUND CURVE SURVEY NAIL PROPERTY LINE POINT OF REVERSE CURVE POINT OF VERTICAL CURVE POINT OF VERTICAL CURVE POINT OF VERTICAL CURVE POINT OF VERTICAL COMPOUND CURVE POINT OF VERTICAL REVERSE CURVE POINT OF VERTICAL REVERSE CURVE
AD AD AD AD AD AD AD AD AD AD	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION GRANITE BOUND RATE OF VERTICAL CURVATURE LENGTH LEFT NORTH ON CENTER POINT OF CURVE POINT OF CURVE SURVEY NAIL PROPERTY LINE POINT OF REVERSE CURVE POINT OF TANGENT POINT OF VERTICAL CURVE POINT OF VERTICAL CURVE POINT OF VERTICAL COMPOUND CURVE POINT OF VERTICAL COMPOUND CURVE
AD BL CC E E L/ELEV GB K L T N DC PC PC PC PC PC PC PC PC PC P	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION GRANITE BOUND RATE OF VERTICAL CURVATURE LENGTH LEFT NORTH ON CENTER POINT OF CURVE POINT OF CURVE POINT OF COMPOUND CURVE SURVEY NAIL PROPERTY LINE POINT OF REVERSE CURVE POINT OF VERTICAL REVERSE CURVE POINT OF VERTICAL REVERSE CURVE POINT OF VERTICAL REVERSE CURVE
AD BL CC E EL/ELEV GB C C C C C C C C C C C C C	ALGEBRAIC DIFFERENCE CONSTRUCTION BASELINE CENTER OF CURVE EAST ELEVATION GRANITE BOUND RATE OF VERTICAL CURVATURE LENGTH LEFT NORTH ON CENTER POINT OF CURVE POINT OF COMPOUND CURVE SURVEY NAIL PROPERTY LINE POINT OF REVERSE CURVE POINT OF VERTICAL REVERSE CURVE POINT OF VERTICAL REVERSE CURVE POINT OF VERTICAL REVERSE CURVE POINT OF VERTICAL REVERSE CURVE POINT OF VERTICAL TANGENT RADIUS
AD AD AD AD AD AD AD AD AD AD	ALGEBRAIC DIFFERENCECONSTRUCTION BASELINECENTER OF CURVEEASTELEVATIONGRANITE BOUNDRATE OF VERTICAL CURVATURELENGTHLEFTNORTHON CENTERPOINT OF CURVEPOINT OF COMPOUND CURVESURVEY NAILPOINT OF REVERSE CURVEPOINT OF VERTICAL CURVEIPOINT OF VERTICAL CURVEPOINT OF VERTICAL COMPOUND CURVEPOINT OF VERTICAL REVERSE CURVEPOINT OF VERTICAL REVERSE CURVEPOINT OF VERTICAL TANGENTRADIUSRIGHT OF WAYRIGHTSOUTHSTATION
AD AD AD AD AD AD AD AD AD AD	ALGEBRAIC DIFFERENCEALGEBRAIC DIFFERENCECONSTRUCTION BASELINECENTER OF CURVEEASTELEVATIONGRANITE BOUNDRATE OF VERTICAL CURVATURELENGTHLEFTNORTHON CENTERPOINT OF CURVESURVEY NAILPROPERTY LINEPOINT OF REVERSE CURVEPOINT OF VERTICAL CURVEIPOINT OF VERTICAL CURVEPOINT OF VERTICAL REVERSE CURVEPOINT OF VERTICAL REVERSE CURVEPOINT OF VERTICAL REVERSE CURVEPOINT OF VERTICAL TANGENTRADIUSRIGHT OF WAYRIGHTSOUTHSTATIONVERTICAL CURVE
AD AD AD AD AD AD AD AD AD AD	ALGEBRAIC DIFFERENCECONSTRUCTION BASELINECENTER OF CURVEEASTELEVATIONGRANITE BOUNDRATE OF VERTICAL CURVATURELENGTHLEFTNORTHON CENTERPOINT OF CURVEPOINT OF COMPOUND CURVESURVEY NAILPOINT OF REVERSE CURVEPOINT OF VERTICAL CURVEIPOINT OF VERTICAL CURVEPOINT OF VERTICAL COMPOUND CURVEPOINT OF VERTICAL REVERSE CURVEPOINT OF VERTICAL REVERSE CURVEPOINT OF VERTICAL TANGENTRADIUSRIGHT OF WAYRIGHTSOUTHSTATION







STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
MA	-	4	х
	PROJECT FILE NO.	XXXXXX	< (

#### **TITLE SHEET, LEGEND & ABBREVIATIONS**

#### LEGEND

[	
	APPROX. ABUTTERS LOT LINE (SEE NOTE 9)
	GAS LINE
	SEWER LINE
	TELEPHONE LINE
	WATER LINE
	UNDERGROUND ELECTRIC LINE
	SHRUB LINE
	OVERHEAD WIRE
x	CHAIN-LINK FENCE
	HAND RAIL
x	OTHER FENCE
10'	MAJOR CONTOUR LINE
8'	MINOR CONTOUR LINE
10'	RIVER BED MAJOR CONTOUR LINE (SEE NOTE 10)
	RIVER BED MINOR CONTOUR LINE (SEE NOTE 10)
	BRICK
□ CB	CATCH BASIN - SQUARE
<u></u>	CLEANOUT
DSK	DISK (CA/T, USC&GS, LAND COURT, ETC.)
D	DRAIN MANHOLE
D EHH	ELECTRIC HANDHOLE
E	ELECTRIC MANHOLE
O EM	ELECTRIC METER
	FLAG POLE
• GG	GAS GATE
@ GM	GAS METER
မိုင်	GAS SHUTOFF VALVE
Ŷ	FIRE HYDRANT
-X-	LIGHT POLE
M	OTHER MANHOLE
	SQUARE POST
<u> </u>	SEWER MANHOLE
	TELEPONE MANHOLE
● 22"M	TREE
	SIGN
	UTILITY POLE
• WG	WATER GATE
• WSO	WATER SHUTOFF
BB	BITUMINOUS BERM
CIP	CAST IRON PIPE
CONC	CONCRETE
CS	COBBLESTONE
DBYL	DOUBLE YELLOW LINE
	DRAIN MANHOLE
DMH	
DS	DOWN SPOUT
DSK	
EL	
EP	
ETW	EDGE OF TRAVELED WAY
FF	FINISHED FLOOR
GRAN	GRANITE
HDW	HEADWALL
PLUG	LEAD PLUG WITH ESCUTCHEON PIN
RET	RETAINING
SWL	SOLID WHITE LINE
ТҮР	TYPICAL
VGC	VERTICAL GRANITE CURB

ME: 5521A_SV		
OOK. NO: XXXX		
BY: W.D.C.	CHECKED BY: W.J.D.	
HIEF: XXX	PARS. NO: XXXXXXX	DA

#### MASSACHUSETTS DEPARTMENT OF TRANSPORTATION PLAN OF TOPOGRAPHIC SURVEY OF

#### **CENTRAL STREET**

(BRIDGE NO. X-XX-XXX)

IN THE (T/C) OF

### MANCHESTER BY THE SEA

AS ORDERED BY THE MASSACHUSETTS DEPARTMENT OF TRANSPORTATION, HIGHWAY DIVISION

SHEET 1 OF 4

#### **REFERENCE PLANS:**

- 1. "PLAN OF A PORTION OF THE MAIN ROAD IN MANCHESTER SHOWING THE PROPOSED WIDENINGS" DONE BY CHARLES A. PUTNAM, DATED NOVEMBER 23, 1871. COUNTY OF ESSEX RECORD #1230.
- 2. "PLAN OF A PORTION OF CENTRAL STREET AT THE JUNCTION OF SCHOOL STREET AND UNION STREET IN THE TOWN OF MANCEHSTER AS ALTERED" DONE BY CLINTON C. BARKER COUNTY ENGINEER DATED SEPTEMBER 1947. S.E.D.R.D. PLAN #76-35.
- 3. "PLAN OF A PORTION OF CENTRAL STREET FROM ELM STREET TO SCHOOL STREET IN THE TOWN OF MANCEHSTER AS ALTERED" BY JOHN O. MARMAALA COUNTY ENGINEER DATED SEPTEMBER 1953. S.E.D.R.D. PLAN #84-8.
- 4. "PLAN OF LAND IN MANCHESER, MASS FOR JEAN E. GRELET" DATED MARCH 20, 1959 BY DANA F. PERKINS & SONS, INC. S.E.D.R.D. PLAN #92-74.
- 5. "PLAN OF A PORTION OF ELM STREET FROM CENTRAL STREET 700 FEET NORTHERLY IN THE TOWN OF MANCHESTER AS LAID OUT" BY EARL H. PAGE DATED OCTOBER 25, 1966. S.E.D.R.D. PLAN #107-91.
- 6. "PLAN OF LAND IN MANCHESTER, MASSACHUSETTS COUNTY OF ESSEX FOR ANN N. KILEY & DOROTHY B. KILEY" DATED FEBRUARY 14, 1985. DONE BY W. C. CAMMETT ENGINEERING, INC. S.E.D.R.D. PLAN #233-32.
- 7. "SITE PLAN 27 CENTRAL ST. CONDOMINIUMS" DONE BY W. C. CAMMETT ENGINEERING, INC. DATED FEBRUARY 1985. S.E.D.R.D. PLAN #233-33.
- 8. "PLAN OF LAND BELONGING TO SAMUEL KNIGHT SONS CO." DATED SEPTEMBER 27, 1946 BY RICHARD A. WIRLING. S.E.D.R.D. PLAN #1946-824.
- 9. "PLAN OF LAND IN MANCHESTER OT BE CONVEYED FROM F. J. MERRILL TO THE CRICKET PRESS, INC." FEBRUARY 15, 1923, BY RAYMOND C. ALLEN, S.E.D.R.D. PLAN #2549-181.
- 10. "LAND OF JOHN W. MARSHALL HEIRS" DATED OCTOBER 28, 1944 BY WARREN A. CROMBIE. S.E.D.R.D. PLAN #3465-1.
- 11. "PLAN OF LAND BELONGING TO SAMUEL KNIGHT SONS, CO." DATED DECEMBER 10, 1946 BYRICHARD A. WIRLING, S.E.D.R.D. PLAN #3521-600.
- 12. "PROPERTY OF JEAN E. GRELET, CENTRAL ST, MANCHESTER MASS" DATED NOVEMBER 8, 1952 S.E.D.R.D. PLAN #3925-1.
- 13. "PLAN OF LAND IN MANCHESTER PROPERTY OF SEA ROCK ESTATE, INC." DATED DECEMBER 18, 1970, BY ESSEX SURVEY SERVICE, INC. S.E.D.R.D. PLAN #5765-800.
- 14. "PLAN OF LAND IN MANCHESTER PROPERTY OF SEA ROCK ESTATE, INC." DATED MAY 3, 1971 BY ESSEX SURVEY SERVICE, INC. S.E.D.R.D. PLAN #5835-1.
- 15. "PLAN OF LAND IN MANCHESTER PEELE HOUSE SQUARE" FOR SEA ROCK ESTATE, INC. DATED JULY 11, 1972 BY ESSEX SURVEY SERVICE, INC. S.E.D.R.D. PLAN #5961-297.
- 16. "PLAN OF LAND IN MANCHESTER PEELE HOUSE SQUARE" FOR SEA ROCK ESTATE, INC. DATED MAY 8, 1973. BY ESSEX SURVEY SERVICE, INC. S.E.D.R.D. PLAN #6025-1.
- 17. "PLAN OF LAND IN MANCHESTER PROPERTY OF ARTHUR A. & MARJOIRE SECHER" DATED JUNE 11, 1984. BY ESSEX SURVEY SERVICE, INC. S.E.D.R.D. PLAN #7688-133.
- 18. "PLAN TO ACCOMPANY PETITION OF THE TOWN OF MANCHESTER. TO CONSTRUCT A **RETAINING WALL AND FILL SOLID MANCHESTER HARBOR" DATED NOVEMBER 3, 1921.** BY RAYMOND C. ALLEN. S.E.D.R.D. PLAN #36-31.
- 19. PLAN TITLED "MANCHESTER-BY-THE-SEA DOWNTOWN ATLAS, MANCHESTER-BY-THE-SEA, MASSACHUSETTS, ESSEX COUNTY" PREPARED BY DGT SURVEY GROUP DATED 6-10-2015.



nighway Division		•
REVISIONS		
COMMENTS	DATE	- sc
SMH INVERTS, ADD MISC. FEATURES	10/18/18	
ADD REF. PLAN 19, MISC. UPDATES	11/09/18	FILE NAME
		FIELD BOO
	_	DRAWN B
· · · · · · · · · · · · · · · · · · ·	******	FIELD CHI
	REVISIONS	REVISIONS         COMMENTS       DATE         SMH INVERTS, ADD MISC. FEATURES       10/18/18

Massachusetts Department of Transportation

DMH 1245 RIM ELEV.=11.5'(1215) 12" PVC INV.=9.3' (12" PVC\*\*) (A) VERY RECESSED (12" CLARY FROM CB 1246\*\*) WATER ELEV.=9.3' SUMP ELEV.=8.3'

CB 1246

RIM FLEV = 11.2'

(A) 12" UNKN INV.=9.6'

(10" OR 12" CLAY TO DMH 1245\*\*)

\*\*INDICATES PIPE SIZE/DIA. INFO.

**IS PER REF. PLAN 19** 

DMH 1228 RIM ELEV. = 10.1'(1245) 10" CLAY INV.=6.4' (10" CLAY\*\*) (1215) 15" CMP INV.=5.5'

CB 1215 RIM ELEV.=9.2' (1228) 15" CMP INV.=2.6' (A) 8" METAL INV.=1.6' (B) 8" METAL INV.=1.5'

CB 1196 RIM ELEV.=9.2' (OUTFALL) 12" CLAY INV.=5.3' (10" CONC\*\*) (A) 12" CLAY INV.=5.2' (12"\*\*)

CB 1153 RIM ELEV.=10.1' SUMP ELEV.=7.8' CONC. CHANNEL TO OUTFALL

DRAINAGE STRUCTURES CB 1104 RIM ELEV.=14.2'(A) 4" CIP INV.=12.1' (4" METAL\*\*) (B) 10" CMP INV.=10.5' (8"\*\*)

# \*\*INDICATES PIPE SIZE/DIA. INFO. **IS PER REF. PLAN 19**

SMH 1248 RIM ELEV.=13.7' (A) 8" UNKN INV.=6.7' (B) 8" UNKN INV.=0.1' (1155) 12" UNKN INV.=-0.3' (15" PIPE\*\*) (C) 12" UNKN INV.=-0.4' (12" PIPE\*\*) (D) 12" UNKN INV = -0.4

CC = -0.6'

SMH 1155 RIM ELEV. = 10.2'(A) 4" PVC INV.=4.7' (B) 4" PVC INV.=0' (C) UNKN INV.=-0.3' (6" PIPE\*\*) (1248) UNKN INV.=-0.6' (15" PIPE\*\*) (1081) UNKN INV.=-0.6' (12" PIPE\*\*)

SMH 1109 RIM ELEV.=14.6' (1081) 15" UNKN INV.=-2.1' (15" PIPE\*\*) (A) 15" UNKN INV.=-2.6' (B) 15" UNKN INV.=-2.7' (18" PIPE\*\*)

SMH 1081 RIM ELEV.=12.4'CC = -1.1'(1155) UNKN BC=-1.2' (12" PIPE\*\*) (1109) UNKN BC=-1.3' (15" PIPE\*\*)

SEWER STRUCTURES

	ST	CITY/TOW REET/ROUTE #		ΛE	
	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
	MA	-	4	х	
		PROJECT FILE NO.	XXXXXX	<	
TL	E SH	EET, LEGEND &	ABBRE	VIATIO	NS


#### OTHER STRUCTURES MH 1063 RIM ELEV.=11.5'SUMP ELEV.=6.8'


DRY NO PIPES W/ WATER SHUT OFF

MH 1550 RIM ELEV.=13.8'


SUMP ELEV.=9.9' DRY NO PIPES W/ ELECTRIC METER AND CHANNEL TO FOUNTAIN


PREPARED BY:			N	MASSACHUSETTS DEPARTMENT OF TRANSPORTATION PLAN OF TOPOGRAPHIC SURVEY OF <b>CENTRAL STREET</b> (BRIDGE NO. X-XX-XXX) IN THE (T/C) OF				
Serving Your Professional Surveying & Mapping Needs http://www.doucetsurvey.com								
SCALE: 10 FEET TO THE INCH         FILE NAME: 5521A_SV         FIELD BOOK. NO: XXXX			MANCHESTER BY THE SE	A				
			AS ORDERED BY					
		THE MASSACHUSETTS DEPARTMENT OF						
			TRANSPORTATION, HIGHWAY DIVIS					
	DRAWN BY: W.D.C. CHECKED BY: W.J.D.							
	FIELD CHIEF: XXX	PARS. NO: XXXXXXX	DATE:		SHEET	2	OF	4








5521A\_SV.DWG Plotted on

























SILTSACK<sup>®</sup> OR APPROVED EQUAL













# **TRANSECT 1**

			20
			20
1		ZONE A (ELEV: 10')	10
6	SEAWA		
		MEAN HIGH HIGH WATER (ELEV: 4.8')	
		MEAN HIGH WATER (ELEV: 3.1')	•
			0
			-1

# **TRANSECT 3**

		20
	ZONE A (ELEV: 10')	10
SEAWALL	MEAN HIGH HIGH WATER (ELEV: 4.8')	
	MEAN HIGH WATER (ELEV: 3.1')	0
		-10

# TRANSECT 4

BEST MANAGEMENT PRACTICES INSPECTION AND MAINTENANCE • SEDIMENT, EROSION CONTROLS, AND BEST MANAGEMENT PRACTICES (BMPS) SHALL BE INSTALLED PRIOR TO COMMENCING CONSTRUCTION AT THE SITE. NO WORK WHICH SHALL DISTURB THE SITE OR CREATE THE POTENTIAL FOR SEDIMENT RELEASE SHALL COMMENCE UNTIL THE SEDIMENT AND EROSION CONTROLS HAVE BEEN INSPECTED AND APPROVED BY THE OWNER, ENGINEER, AND REGULATORY AGENCIES. ALL CONTROLS AND BMPS SHALL BE SUBJECT TO INSPECTION BY THE OWNER, HIS REPRESENTATIVE, AND REGULATORY AGENCIES AT ANYTIME THEREAFTER. • PERIODIC INSPECTION, MAINTENANCE, AND CLEANING OF TEMPORARY EROSION OF SEDIMENT CONTROL MEASURES AND BMPS SHALL BE REQUIRED. ALL CONTROLS AND BMPS SHALL BE INSPECTED EVERY 7 DAYS AND WITHIN 24 HOURS OF RAINFALL EVENTS OF 0.25 INCHES OR GREATER. ROUTINE INSPECTION AND MAINTENANCE WILL REDUCE THE CHANCE OF POLLUTING STORMWATER BY FINDING AND CORRECTING PROBLEMS BEFORE THE NEXT RAIN EVENT. THE FOCUS OF THE INSPECTION WILL BE TO DETERMINE: 1. WHETHER OR NOT THE MEASURE WAS INSTALLED / PERFORMED CORRECTLY; 2. WHETHER OR NOT THERE HAS BEEN ANY DAMAGE TO THE MEASURE SINCE IT WAS INSTALLED OR PERFORMED; AND 3. WHAT SHOULD BE DONE TO CORRECT ANY PROBLEMS WITH THE MEASURE. EACH MEASURE IS TO BE OBSERVED TO DETERMINE IF IT IS STILL EFFECTIVE. IN SOME CASES, SPECIFIC MEASUREMENTS MAY BE TAKEN TO DETERMINE IF MAINTENANCE OF THE MEASURES IS REQUIRED. • PRIOR TO CONSTRUCTION, A SITE MANAGER WILL BE DESIGNATED BY THE CONTRACTOR TO BE RESPONSIBLE FOR INSTALLATION, MONITORING, INSPECTION, AND CORRECTION OF EROSION AND SEDIMENT CONTROL MEASURES. CONSTRUCTION SITE ENTRANCE • TO REDUCE THE TRACKING OF SEDIMENT FROM THE CONSTRUCTION SITE ONTO OTHER AREAS OF THE PROPERTY AND/OR PUBLIC ROADS, AS WELL AS THE PRODUCTION OF AIRBORNE DUST, A STABILIZED CONSTRUCTION ENTRANCE IS TO BE ESTABLISHED AT ANY PERMANENT CONSTRUCTION STAGING AREA. THE ENTRANCE IS TO CONSIST OF A 6-INCH THICK PAD OF CRUSHED STONE UNDERLAIN WITH FILTER FABRIC OR A BITUMINOUS CONCRETE APRON. IT IS TO BE REMOVED AND THE AREA RESTORED FOLLOWING CONSTRUCTION. SITE CLEARING • DURING SITE CLEARING, EXISTING VEGETATION WITHIN THE OVERALL LIMITS OF CLEARING AND GRUBBING SHALL BE REMOVED, EXCEPT AS OTHERWISE DIRECTED. PRIOR TO ANY SITE CLEARING ACTIVITIES, SEDIMENT CONTROL BARRIERS SHALL BE PLACED ALONG THE OUTER LIMIT OF DISTURBANCE. CLEARING IS TO BE LIMITED TO THOSE AREAS OF PROPOSED WORK. DISTURBED AREAS ARE TO BE KEPT TO A MINIMUM. NO TREE WITH A BREAST HEIGHT DIAMETER OF GREATER THAN 6 INCHES SHALL BE CLEARED FROM AREAS OUTSIDE THE LIMITS OF CLEARING AND GRUBBING WITHOUT PRIOR APPROVAL FROM THE OWNER. • STANDARD DUST CONTROL MEASURES, INCLUDING SPRAYING AND MISTING SHALL BE USED AS NECESSARY. CALCIUM CHLORIDE SHALL NOT BE ALLOWED ON THIS PROJECT. STAGING AREAS • THE CONTRACTOR SHALL COORDINATE LAYDOWN STAGING AREAS FOR STORING EQUIPMENT AND MATERIALS WITH THE OWNER. STAGING AREAS SHALL BE SURROUNDED WITH COMPOST FILTER TUBE EROSION BARRIERS ON THE DOWNHILL SIDE. DURING AND AFTER CONSTRUCTION, ALL PAVED ROAD AND DRIVEWAY SURFACES ARE TO BE SCRAPED AND BROOMED FREE OF EXCAVATED MATERIALS ON A DAILY BASIS, UNLESS APPROVED BY THE OWNER. STOCKPILED MATERIALS • STOCKPILES OF SOIL CREATED DURING CONSTRUCTION ACTIVITIES ARE TO BE SURROUNDED WITH AN EROSION CONTROL BARRIER AROUND THE PERIMETER OF THE STOCKPILE. STOCKPILES OF ERODIBLE MATERIAL ARE TO BE COVERED PRIOR TO INCLEMENT WEATHER WITH A MINIMUM OF 20 MIL POLYETHYLENE SHEETING. STOCKPILES LEFT UNDISTURBED LONGER THAN 14 DAYS SHALL BE SEEDED OR COVERED. EQUIPMENT FUELING • EQUIPMENT FUELING AND OTHER ACTIVITIES INVOLVING PETROLEUM, OIL, OR OTHER POTENTIALLY HAZARDOUS SUBSTANCES ARE TO BE PERFORMED AT PRE-APPROVED, DESIGNATED AREAS WITH APPROPRIATE SPILL PREVENTION AND CONTROL MEASURES. PORTABLE SECONDARY CONTAINMENT IS TO BE USED, AND SORBENT MATERIALS ARE TO BE PLACED AROUND THE PERIMETER OF THE FUELING AREA. CONSTRUCTION DEWATERING • CONSTRUCTION DEWATERING SHALL BE REQUIRED DURING PORTIONS OF CONSTRUCTION WHICH REQUIRE EXCAVATION OR OTHER ACTIVITIES WHERE GROUNDWATER MAY INTERFERE WITH THE WORK. CONSTRUCTION DEWATERING DISCHARGES SHALL BE PRE-TREATED FOR SEDIMENT REMOVAL BY PASSING THROUGH AN APPROPRIATELY SIZED FILTER SOCK, SILT BAG, FRACTIONATION / SEDIMENTATION TANK, OR SEDIMENT TRAP PRIOR TO DISCHARGE, AS NECESSARY. • THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING DEWATERING TECHNIQUES AND MAINTAINING DEWATERING PROCEDURES THROUGHOUT THE DURATION OF THE PROJECT. OUTLET PROTECTION • APPROPRIATE OUTLET PROTECTION, CONSISTING OF RIPRAP CHANNEL LINING, A LEVEL SPREADER, OR OTHER SUCH MEASURE SHALL BE PROVIDED AT THE OUTLET OF ANY DEWATERING CONDUIT OR STORMWATER CULVERT OR CHANNEL OUTFALL TO REDUCE VELOCITIES AND ENHANCE SEDIMENTATION PRIOR TO DISCHARGE. LIMITS OF WORK • THE CONTRACTOR SHALL LINE THE UPGRADIENT BOUNDARY OF WORK AREAS WITH ORANGE SAFETY FENCING BEFORE THE START OF SITE CLEARING ACTIVITIES EXCEPT WHERE CHAIN-LINK FENCING IS NEEDED TO RESTRICT PUBLIC ACCESS. SURFACE WATER CONTROL • THE CONTRACTOR MUST MAINTAIN THE SITE FLOWAGE OF SURFACE WATER THROUGH THE WORK AREA IN ACCORDANCE WITH THE SPECIFICATIONS. ALL COFFERDAMS SHALL CONSIST OF NON-ERODIBLE MATERIAL. THE CONTRACTOR SHALL SUBMIT A WATER CONTROL PLAN THAT WILL ADDRESS EMERGENCY MEASURES TO IMPLEMENT IN THE EVENT A STORM OCCURS DURING CONSTRUCTION. TURBIDITY MONITORING AND CONTROL • TURBIDITY SHALL BE MONITORED AND CONTROLLED BY THE CONTRACTOR. A TURBIDITY CURTAIN SHALL BE INSTALLED SURROUNDING AREAS OF EXCAVATION AT AND BELOW THE IMPOUNDMENT WATER LINE. • IF TURBIDITY LEVELS ARE UNACCEPTABLE AS JUDGED BY THE OWNER, ENGINEER, OR REGULATORY AGENCY, ADDITIONAL MEASURES SHALL BE IMPLEMENTED AT NO EXPENSE TO THE OWNER. **TEMPORARY STABILIZATION** • WHEN NECESSARY, TEMPORARY SLOPE PROTECTION SHALL BE PROVIDED BY INSTALLING SEDIMENT TRAP BARRIERS AT THE TOE OF FILLS OR CUT SLOPES. IF ADDITIONAL STABILIZATION IS NEEDED, THEN THE CONTRACTOR SHALL INSTALL MULCH LOGS, MATTING, SUCH AS STRAW, JUTE, WOOD FIBER, OR BIODEGRADABLE MESH. A TACKIFIER SHALL BE USED ON LOOSE MATERIALS USED FOR TEMPORARY EROSION CONTROL. • IN THE EVENT THAT DISTURBED AREAS AT THE SITE ARE TO BE LEFT UN-WORKED FOR MORE THAN TWO WEEKS, THE AREAS SHALL BE MULCHED WITH STRAW AT A RATE OF 100 LBS. PER 1,000 S.F. TO HELP CONTROL EROSION. 100% BIODEGRADABLE EROSION CONTROL BLANKETS OR TWO INCHES OF WOOD CHIP MULCH MAY ALSO BE USED AS TEMPORARY COVER. • IN THE EVENT THAT DISTURBED AREAS AT THE SITE ARE TO BE LEFT UN-WORKED FOR MORE THAN ONE MONTH, THE AREAS SHALL BE TOPSOILED AND SEEDED AS PER THE SPECIFICATIONS AND AT NO ADDITIONAL COST TO THE OWNER. LEAVE THE SURFACE OF ALL EXCAVATIONS AND FILLS IN A FIRM AND STABLE CONDITION AT THE END OF EACH DAY. ROLL OR OTHERWISE TREAT THE SURFACE AS NEEDED. SITE RESTORATION • STABILIZATION OF DISTURBED AREAS OR NEW SOIL FILLS SHALL BE IMPLEMENTED WITHIN 14 DAYS AFTER GRADING OR CONSTRUCTION ACTIVITIES HAVE PERMANENTLY CEASED. APPROPRIATE VEGETATIVE SOIL STABILIZATION IS TO BE USED TO MINIMIZE EROSION. TEMPORARY AND PERMANENT VEGETATIVE COVER IS TO BE ESTABLISHED IN ACCORDANCE WITH THE PROJECT PLANS AND SPECIFICATIONS. • THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORATION OF PREVIOUSLY VEGETATED UPLAND AREAS DISTURBED BY CONSTRUCTION ACTIVITIES. RESTORATION OF UPLAND AREAS CONSIST OF REPLACEMENT OF TOPSOIL OR PLACEMENT OF IMPORTED LOAM AS NEEDED SUCH THAT A MINIMUM OF 4 INCHES OF SUITABLE MATERIAL IS PRESENT AND APPROPRIATELY LIMED, FERTILIZED, GRADED, AND SCARIFIED. FIELDS DISTURBED OR COMPACTED BY CONSTRUCTION ACTIVITIES SHALL BE PLOWED TO LOOSEN THE SOIL, HARROWED TO PROVIDE AN EVEN SURFACE, AND APPROPRIATELY PREPARED FOR PLANTING. DISTURBED UPLAND AREAS SHALL THEN BE HYDROSEEDED WITH AN APPROVED SEED MIX AT THE RATE RECOMMENDED BY THE MANUFACTURER. SEEDING RATE SHALL BE DOUBLED FOR DORMANT SEEDING. SEED MIX SHALL BE DRY SITE RESTORATION SEED MIX UNLESS OTHERWISE NOTED OR AS APPROVED BY THE ENGINEER. • 100% BIODEGRADABLE EROSION CONTROL BLANKETS MUST BE USED FOR STABILIZATION OF SLOPES IN EXCESS OF 3H:1V AND MAY BE USED IN LIEU OF HYDROSEEDING AT THE CONTRACTOR'S DISCRETION TO PROVIDE ADDITIONAL EROSION PROTECTION. • FINAL STABILIZATION SHALL BE CONSIDERED COMPLETE WHEN ALL SOIL-DISTURBING ACTIVITIES HAVE BEEN COMPLETED AND A UNIFORM, PERENNIAL VEGETATIVE COVER WITH A DENSITY OF EIGHTY PERCENT HAS BEEN ESTABLISHED OR EQUIVALENT STABILIZATION MEASURES (SUCH AS THE USE OF MULCHES OR EROSION CONTROL MATTING) HAVE BEEN EMPLOYED ON ALL UNPAVED AREAS AND AREAS NOT COVERED BY PERMANENT STRUCTURES. • THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE OF ALL VEGETATED SURFACES, INCLUDING WATERING, FERTILIZING, REPAIRING EROSION, INVASIVE PLANT REMOVAL, AND RE-SEEDING UNTIL ESTABLISHMENT CONDITIONS ARE MET AND UNTIL THE END OF THE CONTRACTUAL MAINTENANCE PERIOD.

EROSION CONTROL NOTES

- 1. CONTRACTOR MUST FINALIZE AND IMPLEMENT THE EROSION AND SEDIMENT CONTROL PLAN (ESCP).
- 2. THE ESCP SHALL BE UPDATED AS CONSTRUCTION PROGRESSES. IT SHOULD REFLECT CURRENT OWNERSHIP, RESPONSIBILITIES, OPERATIONS AND FINDINGS. THE PLAN SHALL BE REVISED NO LATER THAN 7 DAYS AFTER THE INSPECTION. IF HAZARDOUS CONDITIONS OCCUR THE PLAN NEEDS TO BE MODIFIED BEFORE PROCEEDING WITH WORK. STEPS TO PREVENT THE REOCCURRENCE OF SUCH RELEASES WILL BE IDENTIFIED IN A PLAN REVISION AND IMPLEMENTED.
- 3. MAINTAIN AN ADDITIONAL SUPPLY OF EROSION CONTROL MEASURES THROUGHOUT THE CONSTRUCTION PERIOD.
- 4. MAINTAIN ALL EROSION CONTROL MEASURES IN GOOD WORKING CONDITION. THIS MAY REQUIRE CLEANING, REPAIRING, REPLACEMENT, AND SEDIMENT DISPOSAL. MAINTENANCE SHALL BE INITIATED WITHIN 24 HOURS OF IDENTIFICATION. SEDIMENT BARRIERS SHOULD HAVE SEDIMENT CLEANED OUT WHEN THE BARRIER IS 50% OF CAPACITY. SOIL AND DEBRIS ON ADJOINING PROPERTIES OR STREETS SHALL BE MINIMIZED. HAZARDOUS MATERIAL SPILLS SHOULD BE REMOVED IMMEDIATELY AND REMEDIAL ACTIONS FOR PREVENTION MUST BE TAKEN. HAZARDOUS MATERIALS SHALL BE CLEANED UP BY REMOVING AND DISPOSING OF CONTAMINATED MATERIALS PROPERLY.
- 5. SILT TRAPPED AT BARRIERS SHALL BE REMOVED AND DISPOSED OF IN UPLAND AREAS OUTSIDE BUFFER ZONES. MATERIALS DEPOSITED IN ANY TEMPORARY SETTLING BASIN SHALL BE REMOVED AT THE COMPLETION OF THE PROJECT. ALL DISTURBED AREAS SHALL BE RESTORED.
- 6. THE ESCP MEASURES SHOWN ON THIS PLAN ARE THE BASE REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, UPGRADE THESE MEASURES AS NEEDED TO COMPLY WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL EROSION AND SEDIMENT CONTROL REGULATIONS.
- 7. EROSION AND SEDIMENT CONTROL MEASURES INCLUDING PERIMETER SEDIMENT CONTROL MUST BE IN PLACE BEFORE VEGETATION IS DISTURBED AND MUST REMAIN IN PLACE AND BE MAINTAINED, CLEANED, REPAIRED OR REPLACED, AND PROMPTLY IMPLEMENTED FOLLOWING PROCEDURES ESTABLISHED FOR THE DURATION OF CONSTRUCTION, INCLUDING PROTECTION FOR ACTIVE STORM DRAIN INLETS AND CATCH BASINS AND APPROPRIATE NON-STORMWATER POLLUTION CONTROLS.
- 8. PHASE CLEARING AND GRADING TO THE MAXIMUM EXTENT PRACTICAL TO PREVENT EXPOSED INACTIVE AREAS FROM BECOMING A SOURCE OF EROSION. CONSTRUCTION ACTIVITIES MUST AVOID OR MINIMIZE UNSTABILIZED EXCAVATION AND CREATION OF BARE GROUND DURING WET WEATHER.
- 9. PROTECT NEW WORK FROM FLOODING. PROPERLY SLOPE GRADING IN THE AREAS SURROUNDING ALL EXCAVATIONS TO PREVENT WATER FROM RUNNING INTO THE EXCAVATED AREA OR TO ADJACENT PROPERTIES. UPON COMPLETION OF THE WORK, RESTORE ALL AREAS IN A SATISFACTORY MANNER.
- 10. IDENTIFY, MARK, AND PROTECT (BY FENCING OFF OR OTHER MEANS) CRITICAL RIPARIAN AREAS AND VEGETATION INCLUDING ALL TREES AND ASSOCIATED ROOTING ZONES, AND VEGETATION AREAS NOT SPECIFICALLY IDENTIFIED FOR REMOVAL. MARK IN THE FIELD VEGETATIVE BUFFER ZONES BETWEEN THE SITE AND SENSITIVE AREAS (E.G., WETLANDS), AND OTHER AREAS TO BE PRESERVED, ESPECIALLY IN PERIMETER AREAS.
- 11. THE INTENTIONAL WASHING OF SEDIMENT INTO SAWMILL BROOK MUST NOT OCCUR. VACUUMING OR DRY SWEEPING AND MATERIAL PICKUP MUST BE USED TO CLEANUP SEDIMENTS.
- 12. STABILIZE THE AREAS OF CONSTRUCTION ACTIVITIES AT THE CLOSE OF EACH CONSTRUCTION DAY. CHECK EROSION CONTROLS AT THIS TIME AND MAINTAIN OR REINFORCE IF NECESSARY.
- 13. APPLY TEMPORARY AND/OR PERMANENT SOIL STABILIZATION MEASURES ON ALL DISTURBED AREAS AS GRADING PROGRESSES AND FOR ALL ROADWAYS INCLUDING GRAVEL ROADWAYS.
- 14. ESTABLISH CONCRETE TRUCK AND OTHER CONCRETE EQUIPMENT CONTAINED WASHOUT AREAS BEFORE BEGINNING CONCRETE WORK. CONCRETE WASHOUT MUST BE CONTAINED AWAY FROM DRAINAGE AREAS. IT MUST BE CLEARLY MARKED AND ACCESSIBLE.
- 15. ESTABLISH MATERIAL AND WASTE STORAGE AREAS, AND OTHER NON-STORMWATER CONTROLS. DISPOSAL OF MATERIALS AND WASTE SHALL COMPLY WITH STATE AND LOCAL WASTE DISPOSAL. SANITARY WASTE AND OTHER HAZARDOUS WASTE SHALL BE DISPOSED OF IN COMPLIANCE WITH LOCAL, STATE, AND FEDERAL REGULATIONS.
- 16. DEWATER AS NECESSARY TO KEEP CONSTRUCTION AREAS FREE OF WATER, DISCHARGE WATER FROM DEWATERING TO THE APPROPRIATE LOCATION AND WITHOUT SEDIMENT.
- 17. ALL SILT-LADEN WATER MUST BE SETTLED OR FILTERED TO REMOVE ALL SEDIMENTS IN A SEDIMENTATION BASIN OR FILTER BAG LOCATED DOWNSTREAM, PRIOR TO RELEASE TO A WATERWAY OR EXISTING DRAINAGE SYSTEM.
- 18. PREVENT TRACKING OF SEDIMENT OUTSIDE OF PROJECT LIMITS USING BMPS SUCH AS: GRAVELED (OR PAVED) EXITS AND PARKING AREAS, GRAVEL ALL UNPAVED ROADS LOCATED ONSITE, OR USE AN EXIT TIRE WASH. THESE BMPS MUST BE IN PLACE PRIOR TO LAND-DISTURBING ACTIVITIES. AT THE END OF EACH WORK DAY, ANY SEDIMENTS TRACKED ONTO PUBLIC RIGHT-OF-WAYS BEYOND THE PROJECT LIMITS SHALL BE SWEPT AWAY.
- 19. WHEN TRUCKING SATURATED SOILS FROM THE SITE, EITHER USE WATER-TIGHT TRUCKS OR DEWATER LOADS ON SITE.
- 20. BMP'S SHOULD BE IMPLEMENTED AND MONITORED THROUGHOUT THE PROJECT. USE BMPS TO PREVENT OR MINIMIZE STORMWATER EXPOSURE TO POLLUTANTS FROM SPILLS; VEHICLE AND EQUIPMENT FUELING, MAINTENANCE, AND STORAGE; OTHER CLEANING AND MAINTENANCE ACTIVITIES; AND WASTE HANDLING ACTIVITIES. THESE POLLUTANTS INCLUDE FUEL, HYDRAULIC FLUID, AND OTHER OILS FROM VEHICLES AND MACHINERY, AS WELL AS DEBRIS, LEFTOVER PAINTS, SOLVENTS, AND GLUES FROM CONSTRUCTION OPERATIONS.
- 21. WRITTEN SPILL PREVENTION AND RESPONSE PROCEDURES, EMPLOYEE TRAINING ON SPILL PREVENTION AND PROPER DISPOSAL PROCEDURES, SPILL KITS IN ALL VEHICLES, REGULAR MAINTENANCE SCHEDULE FOR VEHICLES AND MACHINERY, MATERIAL DELIVERY AND STORAGE CONTROLS, TRAINING AND SIGNAGE, AND COVERED STORAGE AREAS FOR WASTE AND SUPPLIES. HAZARDOUS MATERIALS SHOULD BE STORED AWAY FROM THE STREAM TO ELIMINATE CHANCES FOR ACCIDENTAL SPILL SHALL BE IMPLEMENTED.
- 22. IF A TREATMENT (FOR EXAMPLE, ELECTRO-COAGULATION, FLOCCULATION, FILTRATION, ETC.) FOR SEDIMENT OR OTHER POLLUTANT REMOVAL IS EMPLOYED, SUBMIT AN OPERATION AND MAINTENANCE PLAN (INCLUDING SYSTEM SCHEMATIC, LOCATION OF SYSTEM, LOCATION OF INLET, LOCATION OF DISCHARGE, DISCHARGE DISPERSION DEVICE DESIGN, AND A SAMPLING PLAN AND FREQUENCY) BEFORE OPERATING THE TREATMENT SYSTEM. OBTAIN ENGINEER'S PLAN REVIEW BEFORE OPERATING THE TREATMENT SYSTEM. OPERATE AND MAINTAIN THE TREATMENT SYSTEM ACCORDING TO MANUFACTURER'S SPECIFICATIONS.
- 23. TEMPORARILY STABILIZE SOILS AT THE END OF THE SHIFT BEFORE HOLIDAYS AND WEEKENDS. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT SOILS ARE STABLE DURING EVENTS AT ANY TIME.
- 24. STABILIZING PRACTICES : SEEDING WITH MULCH AND ROLLED EROSION CONTROL MATTING. ANY AREAS NOT SUBJECT TO CONSTRUCTION ACTIVITY FOR 14 DAYS MUST BE STABILIZED IMMEDIATELY. PRESERVE EXISTING VEGETATION IN AREAS NOT DISTURBED DURING CONSTRUCTION. ANY ON SITE STOCK PILES SHALL BE STABILIZED WITHIN 14 DAYS AFTER CONSTRUCTION ACTIVITY HAS CEASED WITH SEDIMENT BARRIERS INSTALLED.
- 25. FINAL STABILIZATION: MEANS THAT ALL SOIL DISTURBING ACTIVITIES AT THE SITE HAVE BEEN COMPLETED AND THAT A UNIFORM PERENNIAL VEGETATIVE COVER WITH A DENSITY OF 70% FOR THE AREA HAS BEEN ESTABLISHED OR EQUIVALENT STABILIZATION MEASURES HAVE BEEN EMPLOYED.



Tighe&Bond

Digitally signed by David Loring Date: 2020.09.09 15:57:04-04'00'

Permit Set Not For Construction


# **Central Street** Bridge Replacement

Department of Public Works


MassDOT Bridge No. M-02-001, BIN 8AM


Town of Manchester-By-The-Sea, Massachusetts

0	6/20/2019	6/20/2019 DRAFT 25% PLANS							
MARK	MARK DATE DESCRIPTION								
PROJE	PROJECT NO: M1476 - 011								
DATE:	DATE: 06/20/2019								
FILE:	M1476-011-C	-501.dwg							
DRAWI	N BY:	DWB							
CHECK	CHECKED: ADF								
APPRO	APPROVED: DLL								
CONTROL OF WATER NOTES									
SCAL	E:	AS NOTED							
	С	-504							









#### FORMULAS FOR DETERMINING TAPER LENGTHS

L = WS

SPEED LIMIT (S)	TAPER LENGTH (L) FEET
40 MPH OR LESS	$L = \frac{WS^2}{60}$
11	

WHERE: L = TAPER LENGTH IN FEET

W = WIDTH OF OFFSET IN FEET

S = POSTED SPEED LIMIT, OR OFF-PEAK 85TH-PERCENTILE SPEED PRIOR TO WORK STARTING, OR THE ANTICIPATED OPERATING SPEED IN MPH

#### **NOTES:**

ONE LANE ROAD

XXX

XX M.P.H. W20-4

W13-1p

-----

 $\rightarrow$ 


1. ALL TEMPORARY TRAFFIC CONTROL WORK SHALL CONFORM TO THE LATEST EDITION OF THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" (MUTCD) AND ALL REVISIONS, UNLESS SUPERCEDED BY THESE PLANS.

45 MPH OR MORE


- 2. ALL SIGN LEGENDS, BORDERS, AND MOUNTING SHALL BE IN ACCORDANCE WITH THE MUTCD.
- 3. TEMPORARY CONSTRUCTION SIGNING AND ALL OTHER TRAFFIC CONTROL DEVICES SHALL BE IN PLACE PRIOR TO THE START OF ANY WORK.
- 4. TEMPORARY CONSTRUCTION SIGNING, BARRICADES, AND ALL OTHER NECESSARY WORK ZONE TRAFFIC CONTROL DEVICES SHALL BE REMOVED FROM THE HIGHWAY OR COVERED WHEN THEY ARE NOT REQUIRED FOR CONTROL OF TRAFFIC.
- 5. SIGNS AND SIGN SUPPORTS LOCATED ON OR NEAR THE TRAVELED WAY, CHANNELIZING DEVICES, BARRIERS, AND CRASH ATTENUATORS MUST PASS THE CRITERIA SET FORTH IN NCHRP REPORT 350, "RECOMMENDED PROCEDURES FOR THE SAFETY PERFORMANCE EVALUATION OF HIGHWAY FEATURES" AND/OR "MANUAL FOR ASSESSING SAFETY HARDWARE" (MASH).
- NOTIFY EACH ABUTTER AT LEAST 24 HOURS IN ADVANCE OF THE START OF ANY WORK THAT WILL 6. REQUIRE THE TEMPORARY CLOSURE OF ACCESS, SUCH AS CONDUIT INSTALLATION, EXISTING PAVEMENT EXCAVATION, TEMPORARY DRIVEWAY PAVEMENT PLACEMENT, AND SIMILAR OPERATIONS.
- 7. THE ADVISORY SPEED LIMIT, IF REQUIRED, SHALL BE DETERMINED BY THE ENGINEER.
- 8. DISTANCES ARE A GUIDE AND MAY BE ADJUSTED IN THE FIELD BY THE ENGINEER.
- 9. MAXIMUM SPACING OF TRAFFIC DEVICES IN A TAPER (DRUMS OR CONES) IS EQUAL IN FEET TO THE 21. WATER FLOW IN THE GUTTER SY SPEED LIMIT IN MPH.
- 10. MINIMUM LANE WIDTH IS TO BE 11 FEET UNLESS OTHERWISE SHOWN. MINIMUM LANE WIDTH TO BE MEASURED FROM THE EDGE OF DRUMS OR MEDIAN BARRIER.


- 11. ALL SIGNS SHALL BE MOUNTED
- 12. TEMPORARY PEDESTRIAN WALK AND ENGINEER TO DETERMINE
- 13. TEMPORARY PEDESTRIAN WALK
- 14. TEMPORARY PEDESTRIAN WALK REPLACE TREES IN KIND.
- 15. CURB RAMPS SHALL BE 60 IN. MI
- 16. PROTECTIVE EDGING WITH A 2 IN OR LANDING PLATFORM HAS A V STEEPER THAN 1:3 (33%). PROTE OR LANDING PLATFORMS HAVE
- 17. DETECTABLE EDGING WITH 6 IN. ON ALL CURB RAMP LANDINGS V
- 18. CURB RAMPS AND LANDINGS SH
- 19. CLEAR SPACE OF 48x48 IN. MININ
- 20. THE CURB RAMP WALKWAY EDG MARKING. THE MARKING IS OPTI
- 22. LATERAL JOINTS OR GAPS BETW
- 23. CHANGES BETWEEN SURFACE H VERTICAL UP TO 0.25 IN. HIGH, A

	Tighe&Bond Engineers   Environmental Specialists
TRAVEL WAY TRAVEL	Digitally signed by David Loring Date: 2020.09.09 15:57:47-04'00'
LIMIT OF EXCAVATION DIRECTION OF TRAFFIC TEMPORARY BIT. CONC. PAVEMENT GRAVEL BORROW/SUBBASE * - INCREASE SLOPE RATIO FOR HIGHER SPEEDS LONGITUDINAL DROP-OFF DETAIL	
NO SCALE	Permit Set Not For Construction Central Street Bridge Replacement
	Department of Public Works MassDOT Bridge No.
ON THEIR OWN STANDARD SIGN SUPPORTS.	M-02-001, BIN 8AM
WAY LOCATION TO BE DETERMINED IN THE FIELD. CONTRACTOR	Town of
TREE REMOVAL ALONG DETOUR PATH. (WAY TO CONFORM WITH ADA STANDARDS.	Manchester-By- The-Sea,
WAY TO CONFORM WITH ADA STANDARDS.	Massachusetts
INIMUM WIDTH WITH A FIRM, STABLE AND NON-SLIP SURFACE. N. MINIMUM HEIGHT SHALL BE INSTALLED WHEN THE CURB RAMP /ERTICAL DROP OF 6 IN. OR GREATER OR HAS A SIDE APRON SLOP ECTIVE EDGING SHOULD BE CONSIDERED WHEN THE CURB RAMPS A VERTICAL DROP OF 3 IN. OR MORE.	
. MINIMUM HEIGHT AND CONTRASTING COLOR SHALL BE INSTALLED WHERE THE WALKWAY CHANGES DIRECTION (TURNS).	
HOULD HAVE A 1:50 (2%) MAX CROSS-SLOPE.	0     6/20/2019     DRAFT 25% PLANS       MARK     DATE     DESCRIPTION
MUM SHALL BE PROVIDED ABOVE AND BELOW THE CURB RAMP.	PROJECT NO:         M1476 - 011           DATE:         06/20/2019
GE SHALL BE MARKED WITH A CONTRASTING COLOR 2 TO 4 IN. WIDE	FILE: M1476-011-C-701.dwg DRAWN BY: DWB
IONAL WHERE COLOR CONTRASTING EDGING IS USED. YSTEM SHALL HAVE MINIMAL RESTRICTION.	CHECKED: ADF APPROVED: DLL
VEEN SURFACES SHALL BE LESS THAN 0.5 IN. WIDTH.	TEMPORARY TRAFFIC CONTROL PLAN - GENERAL
HEIGHTS SHOULD NOT EXCEED 0.5 IN. LATERAL EDGES SHOULD BE	SCALE: AS NOTED
AND BEVELED AT 1:2 BETWEEN 0.25 IN. AND 0.5 IN. HEIGHT.	C-701



CODE	DESCRIPTION
W20-1-a	ROAD WORK AHEAD
W20-3	ROAD CLOSED AHEAD
R11-2	ROAD CLOSED
R11-4	ROAD CLOSED TO THRU TR
M4-10L	DETOUR
M4-10R	DETOUR
M4-9L	DETOUR
M4-9R	DETOUR
M4-8a	END DETOUR





#### BRIDGE DRAWING INDEX

S-001	BRIDGE KEY PLAN, PROFILES, LOCUS, AND INDEX
S-002	BRIDGE NOTES
S-003	BORING LOGS & BORING NOTES
S-101	GENERAL BRIDGE PLAN AND ELEVATION
S-102	BRIDGE FRAMING AND LAYOUT PLAN
S-103	BRIDGE SECTION & DETAILS

HYDRAULIC DATA					
AINAGE AREA	5.0 SQ. MILES				
TER CONTROL FLOOD DISCHARGE (2 YR)	254 CFS				
SIGN FLOOD DISCHARGE (25 YR)	1,363 CFS				
SIGN FLOOD ANNUAL CHANCE (RETURN FREQUENCY)	4% (25-YEARS)				
SIGN FLOOD VELOCITY (25 YR)	7.5 FPS				
SIGN FLOOD ELEVATION (25 YR)	5.7 FEET				
BASE (100-YR) FLOOD DATA					
SE FLOOD DISCHARGE (100 YR)	2,267 CFS				
SE FLOOD ELEVATION (100 YR)	*7.7 FEET				
DESIGN AND CHECK SCOUR DATA					
OUR DESIGN FLOOD ANNUAL CHANCE (RETURN FREQUENCY)	2% (50-YEARS)				
SIGN FLOOD ABUTMENT SCOUR DEPTH	LEFT: 2 FT RIGHT: 2 FT				
OUR CHECK FLOOD ANNUAL CHANCE (RETURN FREQUENCY)	1% (100-YEARS)				
ECK FLOOD ABUTMENT SCOUR DEPTH	LEFT: 2 FT RIGHT: 2 FT				
FLOOD OF RECORD					
SCHARGE	UNKNOWN				
EQUENCY (IF KNOWN)	N/A				
XIMUM ELEVATION	N/A				
TE	N/A				
STORY OF ICE FLOES	UNKNOWN				
DENCE OF SCOUR AND EROSION	UNKNOWN				
UE 7 7 ELEVATION IC THE MODELED 100 YEAR RECIPITATI					

\* THE 7.7' ELEVATION IS THE MODELED 100-YEAR PRECIPITATION EVENT DISCHARGE ELEVATION AT THE BRIDGE

20

10

0

- -10

	Digitally signed by David Loring Date: 2020.09.09 15:58:36-04'00'
	Permit Set Not For Construction
	Central Street Bridge Replacement
	Department of Public Works
	MassDOT Bridge No. M-02-001, BIN 8AM
	Town of Manchester-By- The-Sea, Massachusetts
	MARKDATEDESCRIPTIONPROJECT NO:M1476 - 011
	DATE: JUNE 2019
	FILE:M1476-011-S-001.dwgDRAWN BY:D.BISHOPCHECKED:EAO
ts BLE	FILE: M1476-011-S-001.dwg DRAWN BY: D.BISHOP

Tighe&Bond Engineers | Environmental Specialists

COMMONWEALTH OF MASSACHUSET MassDOT, Highway Division CONCEPTUAL DESIGN IS ACCEPTAI TO MASSDOT FOR CONTRACTING

S-001

1.	DESIGN LOADING:	HL-93		AND DETAIL DRAW
2.	DESIGN:	LOAD AND RESISTANCE FACTOR DESIGN (LRFD) IN ACCORDANCE WITH: AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, 8TH	19	. TAKE ALL NECESSA BARRIERS OF SUFF OPEN EXCAVATION
		AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, 8TH ED., 2017 AS AMENDED MASSDOT 2013 LRFD BRIDGE DESIGN MANUAL, AS AMENDED	20	. ALL EXPOSED EDG NOTED.
3.	SPECIFICATIONS:	MASSDOT 1988 STANDARD SPECIFICATIONS AS AMENDED	21	. SHEAR KEYS SHAL ELEMENT, CENTERI
4.	FOUNDATION DATA:	ABUTMENTS AND U-WINGWALL: SPREAD FOOTINGS SUPPORTED ON SOUND BEDROCK WITH A NOMINAL BEARING CAPACITY OF 100.0 TSF IN	22	PEEL AND STICK B (SUBSIDIARY) AND
		COMBINATION WITH A RESISTANCE FACTOR OF 0.45. PRECAST GUARD TRANSITION: TRANSITION BASE ON CONTROLLED DENSITY FILL (NON EXCAVATABLE) ON COMPACTED GRAVEL BORROW OR	23	EXPANSION AND C . APPLY PAVEMENT J PAVEMENT PASSES
		UNDISTURBED SOIL.		ARMORING PRIOR
5.	REINFORCING STEEL:	AASHTO M31 (ASTM A 615) GRADE 60 ALL BARS SHALL BE HOT-DIPPED GALVANIZED (ASTM A767 & ASTM A1094)		. FOR SURVEY CONT
6.	CONCRETE:	PRECAST ACRH, PEDESTAL FOOTINGS, CURBS/HEADWALLS,		. FOR HYDRAULIC D
		GUARD TRANSITIONS, U-WINGWALL, AND U-WINGWALL FOOTINGS: 5000 PSI, 3/4", 685 HP CEMENT CONCRETE	27	. FOR ROAD CLOSUR
7.	SEISMIC:	PEAK GROUND ACCELERATION (PGA) = 0.125g	<u>BRI</u>	DGE REMOVAL NOTE
		SITE CLASS = C SEISMIC DESIGN CATEGORY = A	1.	THE CONTRACTOR'S N SUBMITTED TO THE E COMMENCEMENT OF A
	<u>NERAL NOTES:</u> PLANS OF THE EXISTI	NG BRIDGE ARE NOT AVAILABLE.	2.	REMOVAL OF EXISTIN REMOVAL OF THE ARC C-005 (CIVIL SHEETS)
		BY NEW ENGLAND BORING CONTRACTORS ON 9/8/2018.	3.	REFER TO SHEET [FILI SEQUENCING.
3.		E DISCS REPRESENTING STATE BENCHMARKS OR SURVEY ITS MUST NOT BE DISTURBED. WHEN THE WORK CALLED FOR	FOI	INDATION NOTES:
	INVOLVES DISTURBIN ENGINEER SUFFICIEN	IS MOST NOT BE DISTORBED. WHEN THE WORK CALLED FOR IG A BRONZE DISC THE CONTRACTOR SHALL NOTIFY THE TLY IN ADVANCE OF THE WORK TO PERMIT THE STATE TO ATE THE AFFECTED MARKER.		FOUNDATION MAY BE DURING CONSTRUCTI
4.		1PLY WITH OSHA'S LATEST STANDARDS. ALL REQUIREMENTS OF	2.	CONCRETE SHALL NO
	INCLUDING, BUT NOT	STANDARDS SHALL BE PROVIDED BY THE CONTRACTOR LIMITED TO, THE PROVISION FOR A COMPETENT PERSON ON RED DOCUMENTATION THAT MAY REQUIRE CERTIFICATION BY A NEER.	3.	BOTTOM OF FOUNDAT CONSIDERED MINIMU MATERIAL AS REQUIR
5.		TRACTOR'S RESPONSIBILITY TO MAINTAIN ALL UTILITIES	4.	ALL FINISHED EXCAVA PRIOR TO PLACEMENT
	OF THE PROJECT. ALL CONTRACT SHALL BE	RLY IN THE AREAS UNDER CONSTRUCTION PRIOR TO COMPLETION _ PIPES AND STRUCTURES WITHIN THE LIMITS OF THIS LEFT IN A CLEAN AND OPERABLE CONDITION AT THE COMPLETION ONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO	5.	ALL EXCAVATIONS FO ALL FINISHED EXCAV/ CONCRETE PLACEMEN
	PREVENT SAND AND S CONTRACTOR IS RESP	SILT FROM DISTURBED AREAS FROM ENTERING THE SYSTEM. PONSIBLE FOR DAMAGE SUSTAINED TO ANY EXISTING UTILITIES	6.	ALL BACKFILL UNDER PLACED IN ACCORDAN
	AND IT IS HIS RESPO	NSIBILITY TO MAKE REPAIRS TO THE REQUIREMENTS OF THE E UTILITY COMPANY.	7.	PRIOR TO PLACEMENT OWNER'S DESIGNATE
6.	CURBING, SURPLUS M	SHED BUILDING MATERIALS, STRUCTURES, PIPES, PAVEMENT, IATERIAL, AND SITE RUBBLE SHALL BE DISPOSED OF BY THE		
		TE AT HIS EXPENSE AND IN ACCORDANCE WITH ALL APPLICABLE ENVIRONMENTAL REGULATIONS.		DTECHNICAL DESIGN
7.	DOES NOT FALL ON A	ALL TAKE ALL NECESSARY MEASURES TO ENSURE THAT DEBRIS NY ROADWAY, RAILROAD, OR WATERWAY BELOW THE EXISTING	1.	MINIMUM EMBEDME SURFACE.
	TEMPORARY STRUCTU	STS INCLUDING ERECTION, MAINTENANCE AND REMOVAL OF IRES OR OTHER SUCH APPROVED METHODS, SHALL BE APPROPRIATE ITEMS OF WORK BEING PERFORMED.	2.	FACTORED STRENG FOOT a. THE BRIDGE
8.	SPECIFICATIONS FOR	METHODS ARE TO COMPLY WITH THE MASSDOT STANDARD HIGHWAYS AND BRIDGES, DATED 1988, AND ITS LATEST		THE FINAL B EMBEDMENT
٥	REVISIONS.	S SHALL BE LOAMED & SEEDED UNLESS OTHERWISE SPECIFIED.		MAXIMUM ALLOWAE
	OVER EXCAVATE LOAN	M & SEED AREAS AS REQUIRED TO MEET GRADE.	4.	MINIMUM LATERAL I a. STATIC = 61 FLUID PRESS
	CONSTRUCTION. ONC	THE DESIGNER OF RECORD FOR REVIEW AND APPROVAL PRIOR TO E THESE REVISIONS ARE APPROVED BY THE MUNICIPALITY'S D, THEY SHALL THEN BE SUBMITTED TO MASSDOT FOR FILING.		b. SURCHARGE DISTRIBUTEI SURCHARGE c. SEISMIC = 3
11.	ALL DIMENSIONS ARE FAHRENHEIT.	HORIZONTAL AND VERTICAL, AND ARE GIVEN AT 68 DEGREES	F	THE WALL
12.		D BY THE CONTRACTOR SHALL COMPLY WITH ALL FEDERAL, EGULATIONS AND REQUIREMENTS.	5.	a. STATIC = 35 b. SURCHARGE DISTRIBUTEI
13.		ALL REVIEW AND UNDERSTAND ALL APPLICABLE ENVIRONMENTAL E THAT ALL CONSTRUCTION CONDITIONS ARE MET.		SURCHARGE SHALL ACCO c. SEISMIC = 3
14.		ALL BE RESPONSIBLE FOR CONSTRUCTION SAFETY, AND MEANS RFORM AND COMPLETE THE WORK.	6	THE WALL MINIMUM BACKFILL
15.		ALL BE RESPONSIBLE FOR REPAIRING ANY DAMAGE TO PRIVATE OUTSIDE THE LIMITS OF CONSTRUCTION SHOWN ON THE PLANS		MAXIMUM BACKFILL
		RACTOR, AT THE SOLE COST TO THE CONTRACTOR.		MAXIMUM COEFFICI
16.	MANCHESTER-BY-THE	IST COORDINATE ALL WORK WITH THE TOWN OF -SEA, ALL UTILITY COMPANIES, THE ENGINEER, AND ANY WORK SHALL NOT PROCEED WITHOUT WRITTEN APPROVAL FROM IESTER-BY-THE-SEA.	9.	0.70 (DELTA= 35 DI SITE CLASS = C
17.		ALL SUBMIT LITERATURE (MANUFACTURER'S LITERATURE, CUT	10.	DESIGN PEAK SEISN FACTOR $(A^s) = 0.10$
	SHEETS, APPLICATION ON THE PROJECT, FOR BE IN ACCORDANCE V	N PROCEDURES, ETC.) FOR ALL PRODUCTS PROPOSED FOR USE R APPROVAL BY THE ENGINEER. APPROVAL OF MATERIALS SHALL WITH THE APPLICABLE REQUIREMENTS OF MASSDOT STANDARD R HIGHWAYS AND BRIDGES, LATEST EDITION AS AMENDED,		DESIGN SPECTRAL I
		D SECTION 6.00, CONTROL OF MATERIALS.		DESIGN SPECTRAL

#### RY MEASURES AND PROVIDE ALL NECESSARY CONTINUOUS CIENT TYPE, SIZE AND STRENGTH TO PREVENT ACCESS TO ALL S AT THE COMPLETION OF EACH DAY'S WORK.

S OF CONCRETE SHALL BE CHAMFERED 3/4", UNLESS OTHERWISE

BE 3" HIGH BY ONE-THIRD THE WIDTH OF THE CONCRETE ), WITH 3" MIN. CLEAR EACH SIDE.

RRIER MEMBRANE SHALL BE 2' WIDE WITH PROTECTION BOARD PLACED CENTERED OVER ALL HORIZONTAL AND VERTICAL NSTRUCTION JOINTS.

DINT ADHESIVE ALONG ALL LONGITUDINAL JOINTS BETWEEN AND ALONG BRIDGE CURB LINES AND EXPANSION JOINT TO PLACING ALL PAVEMENT COURSES.

ROLS SEE SHEETS C-001 TO C-004 (CIVIL SHEETS).

SEE SHEET S-003.

TA SEE SHEET S-001.

TRAFFIC MANAGEMENT PLAN SEE SHEET C-702 (CIVIL SHEETS).

THOD FOR REMOVAL OF THE EXISTING BRIDGE SHALL BE GINEER FOR REVIEW AND ACCEPTANCE PRIOR TO THE IY REMOVAL OPERATIONS.

BRIDGE STRUCTURE SHALL INCLUDE THE COMPLETE , FOOTINGS, HEADWALLS, AND WINGWALL. REFER TO SHEET FOR DEMOLITION PLAN.

IN FOR FINAL DESIGN] (CIVIL SHEETS) FOR WATER CONTROL

LTERED, IF NECESSARY, TO SUIT CONDITIONS ENCOUNTERED N, WITH THE APPROVAL OF THE ENGINEER.

BE PLACED IN WATER OR ON FROZEN GROUND.

ON ELEVATIONS PROVIDED ON DRAWINGS SHALL BE DEPTHS. CONTRACTOR SHALL REMOVE UNSUITABLE

TIONS SHALL BE VERIFIED AND APPROVED BY THE ENGINEER OF FORMWORK FOR CONCRETE FOUNDATION.

FOOTINGS SHALL BE FINISHED BY HAND FOR THE LAST 6". IONS SHALL BE INSPECTED BY THE ENGINEER PRIOR TO ANY

R ADJACENT TO ANY PORTION OF THE STRUCTURE SHALL BE CE WITH MASSDOT STANDARD SPECIFICATIONS.

OF FOOTINGS, REVIEW IN-SITU CONDITIONS WITH THE ENGINEER.

ARAMETERS

T FOR FROST PROTECTION = 4 FEET BELOW ADJACENT GROUND

I LIMIT STATE BEARING RESISTANCE = 45.0 TONS PER SQUARE

DESIGNER SHALL VERIFY THE BEARING RESISTANCE BASED ON IDGE AND WINGWALL FOUNDATION DIMENSIONS AND

E SETTLEMENT = 1 INCH TOTAL,  $\frac{1}{2}$  INCH DIFFERENTIAL

ARTH PRESSURES FOR RESTRAINED ARCH WALLS: POUNDS PER SQUARE FOOT PER FOOT (PSF/FT) AS AN EQUIVALENT IRE, 200 PSF/FT MINIMUM

0.5 TIMES THE VERTICAL SURCHARGE LOAD UNIFORMLY

OVER THE HEIGHT OF THE WALL. THE MINIMUM VERTICAL HALL BE AN AASHTO HL-93 VEHICULAR LOAD.

9H<sup>2</sup> DISTRIBUTED AS AN INVERSE TRIANGLE OVER THE HEIGHT OF

ARTH PRESSURES FOR UNRESTRAINED WING WALLS: PSF/FT AS AN EQUIVALENT FLUID PRESSURE, 200 PSF/FT MINIMUM 0.28 TIMES THE VERTICAL SURCHARGE LOAD UNIFORMLY OVER THE HEIGHT OF THE WALL. THE MINIMUM VERTICAL HALL BE AN AASHTO HL-93 VEHICULAR LOAD. THE DESIGN NT FOR SLOPING GROUND SURFACE ABOVE THE WALLS. H<sup>2</sup> DISTRIBUTED AS AN INVERSE TRIANGLE OVER THE HEIGHT OF

JNIT WEIGHT = 130 POUNDS PER CUBIC FOOT (PCF)

ANGLE OF INTERNAL FRICTION = 32 DEGREES

NT OF FRICTION FOR CONCRETE ON CLEAN, SOUND BEDROCK =

C GROUND ACCELERATION MODIFIED BY THE SHORT-PERIOD SITE

ESPONSE ACCELERATION AT 0.2-SECOND PERIODS  $(S^{DS}) = 0.202$ 

ESPONSE ACCELERATION AT 1-SECOND PERIODS  $(S_{D1}) = 0.068$ 

#### PRECAST CONCRETE BRIDGE STRUCTURE NOTES:

- 1. ITEM 995.01, BRIDGE STRUCTURE STRUCTURE NO. 1, SHALL INCLUDE THE PRECAST CONCRETE ARCH, CURBS/HEADWALLS, PEDESTAL FOOTINGS USED TO SUPPORT THE RIGID FRAME, U-WINGWALL, AND WINGWALL FOOTING. JOINT MATERIALS, MEMBRANE, AND ANY OTHER MATERIALS REQUIRED FOR INSTALLATION OF THE PRECAST CONCRETE BRIDGE OR WINGWALL STRUCTURE SHALL BE SUBSIDIARY.
- THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AND DESIGN CALCULATIONS, SEALED AND SIGNED BY A CURRENTLY REGISTERED MASSACHUSETTS PROFESSIONAL ENGINEER TO THE MUNICIPALITY'S DESIGNER OF RECORD FOR REVIEW AND ACCEPTANCE FOR REVIEW TO ENSURE CONFORMANCE WITH THE CONTRACT DOCUMENTS. SHOP DRAWINGS AND CALCULATIONS SHALL BE SUBMITTED PRIOR TO FABRICATION FOR ALL PRECAST CONCRETE ELEMENTS. SHOP DRAWINGS SHALL SHOW JOINT DETAILS AND REINFORCEMENT SIZE AND LOCATION.
- CHANGES OR MODIFICATIONS DURING THE FABRICATION PROCESS MUST BE SUBMITTED TO THE MUNICIPALITY'S DESIGNER OF RECORD FOR ACCEPTANCE AND INCORPORATED INTO THE FINAL AS-BUILT DRAWINGS.
- 4. DIMENSIONS SHOWN FOR THE PRECAST CONCRETE ELEMENTS ARE ASSUMED AND ARE BELIEVED TO BE PRACTICABLE. NO ADJUSTMENTS TO QUANTITIES OR PAYMENTS WILL BE MADE AS A RESULT OF PROVIDING PRECAST UNITS SIZED DIFFERENTLY THAN SHOWN ON THE PLANS.
- 5. THE QUALITY OF MATERIALS, THE PROCESS OF MANUFACTURE, AND THE FINISHED PRECAST UNITS SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE ENGINEER.
- 6. JOINTS BETWEEN ABUTTING PRECAST UNITS SHALL BE MECHANICALLY CONNECTED, WATERTIGHT, GROUTED, AND MEMBRANED.
- 7. JOINTS BETWEEN ABUTTING PRECAST ARCH, WINGWALL, AND CURB/HEADWALL ELEMENTS SHALL BE MECHANICALLY CONNECTED, WATER TIGHT, AND MEMBRANED.
- 8. WATERPROOF MEMBRANE SHALL BE PROVIDED OVER THE STRUCTURE ACROSS THE ENTIRE ROADWAY WIDTH.
- 9. MEMBRANED SURFACES TO BE BACKFILLED AGAINST SHALL BE PROTECTED BY A PROTECTION BOARD.
- 10. EXPOSED CONCRETE SURFACES SHALL BE TREATED WITH WATER REPELLENT (SILANE/SILOXANE).
- 11. PRECAST CONCRETE CURB/HEADWALL ANCHORAGES, CURB, U-WINGWALL, AND ARCH SECTIONS SHALL BE DESIGNED TO ACCOUNT FOR ALL EARTH PRESSURE, LIVE LOAD SURCHARGES, AND BRIDGE RAILING LIVE LOAD AS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS FOR NCHRP 350 TL-2 TEST LEVEL.
- 12. WEEP HOLES SHALL BE PLACED 1'-0" (TYP.) ABOVE THE TOP OF THE PEDESTAL FOOTING AND ONE (1) WEEP PROVIDED ON BOTH SIDES OF EACH ARCH OR WINGWALL UNIT OR 10'-0" (MAX.) SPACING ALONG FOOTING.
- 13. FOOTINGS SHALL HAVE A KEYWAY WITH THE SPECIFIED DIMENSIONS. GROUT SHALL BE PLACED AROUND THE BOTTOM OF THE ARCH OR WINGWALL AND TO THE TOP OF THE KEYWAY.
- 14. TOP SURFACES OF FOOTING UNITS SHALL BE SET UNIFORMLY TRUE & LEVEL TO A TOLERANCE OF +/- 1/8". PRECAST UNITS SHALL UNIFORMLY BEAR ON SUPPORTING MATERIAL.
- 15. ANY UNSUITABLE MATERIALS SUCH AS BOULDERS, ROOTS, ORGANIC SOILS, SILT/CLAY, OR FRACTURED BEDROCK ENCOUNTERED AT THE PROPOSED BOTTOM OF EXCAVATION ELEVATION SHALL BE REMOVED AND REPLACED WITH CONCRETE, AS DIRECTED BY THE ENGINEER.
- 16. DEWATERING SHALL BE REQUIRED AT EACH FOUNDATION LOCATION TO CONTROL THE WATER INFLOW AND ADEQUATELY DEWATER THE FOOTING EXCAVATION. SUMP PUMPING AREAS AROUND THE ENTIRE PERIMETER SHALL BE REQUIRED TO ADEQUATELY CONTROL THE GROUNDWATER WITHIN THE EXCAVATION AREAS. DEWATERING SHALL BE CONTINUOUS UNTIL THE PRECAST CONCRETE ARCH AND WINGWALLS ARE BACKFILLED EVENLY ON BOTH SIDES TO THE ELEVATIONS OF THE SURROUNDING WATER TABLE, UNLESS OTHERWISE DIRECTED.
- 17. ANY PROPOSED DEWATERING AND SHORING PROCEDURES SHALL BE SUBMITTED TO THE ENGINEER OF RECORD FOR REVIEW AND ACCEPTANCE.
- 18. WATER PUMPED FROM DEWATERING LOCATIONS SHALL BE FILTERED ADEQUATELY TO REMOVE FINE MATERIALS PRIOR TO RETURNING THE WATER TO THE RIVER/BROOK. ACTUAL LOCATION OF SEDIMENTATION BASIN TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER PRIOR TO INSTALLATION.
- 19. ANY FOUNDATION MATERIALS WEAKENED AS A RESULT OF INSUFFICIENT CARE WHILE MAINTAINING A DEWATERED CONDITION SHALL BE REMOVED AND REPLACED WITH CONCRETE AT NO EXPENSE TO THE OWNER.
- 20. REINFORCEMENT SHALL HAVE A 2" MINIMUM CLEAR COVER.
- 21. A CORROSION INHIBITOR CONCRETE ADDITIVE SHALL BE USED FOR ALL CONCRETE.
- 22. DATE TO BE PLACED ON THE INSIDE NORTHEAST FACE AND INSIDE SOUTHWEST FACE HIGHWAY GUARDRAIL TRANSITIONS. A SHEET SHOWING SIZE AND CHARACTER OF NUMERALS WILL BE FURNISHED. THE DATE USED SHALL BE THE LATEST YEAR OF CONTRACT COMPLETION AS OF THE DATE THE FIRST HIGHWAY GUARDRAIL TRANSITION IS CONSTRUCTED. ALL HIGHWAY GUARDRAIL TRANSITIONS SHALL FEATURE THE SAME DATE.

CHAPTER 85 SECTION 35 REVIEW AND APPROVAL NOTES:

1. IN ACCORDANCE AND COMPLIANCE WITH THE REQUIREMENTS OF CHAPTER 85 SECTION 35 OF THE MASSACHUSETTS GENERAL LAWS, THE CONTRACTOR SHALL SUBMIT TO THE MASSACHUSETTS DEPARTMENT OF TRANSPORTATION ALL CONSTRUCTION DRAWINGS AND DESIGN CALCULATIONS THAT SHALL BE USED TO FABRICATE AND CONSTRUCT THE STRUCTURE DENOTED ON THESE PLANS FOR REVIEW AND APPROVAL. THIS APPROVAL SHALL CONSTITUTE THE FINAL APPROVAL AS STIPULATED BY CHAPTER 85 SECTION 35 OF THE MASSACHUSETTS GENERAL LAWS.

Tighe&Bond Engineers   Environmental Specialists
Digitally signed by David Loring Date: 2020.09.09 15:58:56-04'00'
Permit Set Not For Construction
Bridge Replacement
Department of Public Works
MassDOT Bridge No. M-02-001, BIN 8AM
Town of Manchester-By- The-Sea, Massachusetts
MARK DATE DESCRIPTION
PROJECT NO:         M1476 - 011           DATE:         JUNE 2019
PROJECT NO:M1476 - 011DATE:JUNE 2019FILE:M1476-011-S-002.dwgDRAWN BY:D.BISHOPCHECKED:EAO
PROJECT NO:       M1476 - 011         DATE:       JUNE 2019         FILE:       M1476-011-S-002.dwg         DRAWN BY:       D.BISHOP
PROJECT NO:M1476 - 011DATE:JUNE 2019FILE:M1476-011-S-002.dwgDRAWN BY:D.BISHOPCHECKED:EAOAPPROVED:DLL

COMMONWEALTH OF MASSACHUSETTS MassDOT, Highway Division CONCEPTUAL DESIGN IS ACCEPTABLE TO MASSDOT FOR CONTRACTING

		Rest Participation Provide American Prov		Location:	Central Stree Central Stree Town of Man	t, Mancheste	er-by-the-Sea,	MA	_	Boring No Page File No. Checked	1	M-14	<b>B-1</b> 1 176011 2. Haker
)rilling C oreman		ingland Borin Porter	g Contractors		Туре	Casing HW	Sampler Split Spoon	Date	Time	Groundwat Depth		adings sing	Sta. Time
&B Rep late Sta location SS. Elev	See E	ovato 0/09/18 xploration Lo Datum: N/		08/09/18	I.D./O.D. Hammer Wt. Hammer Fall Other	4"/4.5"	1-3/8"/2" 140# 30" Auto hammer	8/9/2018	13:45	6.3'			End of Boring
Depth	Casing Blows	Sample No.	Sample Depth	Blows Per 6"	-	Sample D			General S	tratigraphy	N o t	w	ell Construction
(ft.)	Per Ft.	Rec. (in)	(ft.)						4.00		s		
_		S-1/-	0-2				ver brown, fi		ASP 1.2'	HALT	1		
_					coarse SAN	ID, some G	ravel, trace S	silt					
		S-2/-	2-4		· · · · · · · · · · · · · · · · · · ·	to coarse S	GAND and G	RAVEL,				No	Well Installed
					little Silt								
5 -													
5		S-3/8	5-7	9 - 12	Medium der	nse, brown,	GRAVEL, so	ome fine	FI	FILL			
				2 - 13	to coarse S	and, trace §	Silt						
											2		
		S-4/4	8-10	50/6"	Verv dense	, brown, GF	RAVEL, little f	ine to					
					coarse San		•		9.9'	9 3			
10		C-1/58	10.5-15.5	2:04		Very hard to hard, moderate to slightly					2		
				1:37	÷		÷	-					
_				1:53	weathered, slightly fractured to sound, very coarse to coarse-grained GRANITE, with close to moderately close, horizontal to moderately dipping fractures; RQD = 95%								
_				2:09									
-				2:12	incontactory	upping no.		0070					
15		C-2/60	15.5-20.5	2:17	-				BED	ROCK			
-		0 2,00	10.0 20.0	2:09			nt to very slig ctured to sour						
_				1:44	coarse to co	parse-grain	ed GRANITE	, with					
				2:12	close to mo shallow frac		se, horizonta	al to					
-				3:09	Shanow hat		/ - 30 /0						
20				3.09	-								
┝					Bot	tom of expl	oration at 20.	5'					
┝													
-			├───┤		4								
┝					4								
25					4								
Ļ					4								
Ļ			<b>└───</b> ┤		-								
					4								
30													
lotes: ) Vacuu	im excava	ted to approx	imately 5 fee	t below grad	le. Samples S-1	and S-2	Proportio					Consiste VER	ency RY SOFT <2
ere col	lected by h		-	_			TRACE (TR.)	0 - <10% 10 - <20%			0-4 4-10 10-30	SOF	T 2-4

**BORING LOG B-1** 

BORING LOCATIONS									
BORING STATION OFFSET									
B-1	0+52.3	RT. 16.2'							

BORING NOTES:

- MATERIALS TO BE ENCOUNTERED DURING CONSTRUCTION.
- WATER LEVEL.
- ROCK SAMPLES BY CONTACTING THE DESIGN ENGINEER.
- 6. ALL BORINGS WERE MADE IN SEPTEMBER 2018.
- NEW HAMPSHIRE.

B-1 1. LOCATION OF BORINGS SHOWN ON SHEET S-001 THUS:

2. BORINGS WERE TAKEN FOR PURPOSE OF DESIGN AND SHOW CONDITIONS AT BORING POINTS ONLY, BUT DO NOT NECESSARILY SHOW THE NATURE OF

3. WATER LEVELS SHOWN ON THE BORING LOGS WERE OBSERVED AT THE TIME OF TAKING BORINGS AND DO NOT NECESSARILY SHOW THE TRUE GROUND

4. FIGURES IN COLUMNS INDICATE NUMBER OF BLOWS REQUIRED TO DRIVE A 1%" I.D. SPLIT SPOON SAMPLER 6" USING A 140 POUND WEIGHT FALLING 30".


5. BORING SAMPLES ARE STORED AT TIGHE & BOND'S OFFICE, 53 SOUTHAMPTON ROAD, WESTFIELD, MA 01085. THE CONTRACTOR MAY EXAMINE THE SOIL AND


7. BORINGS WERE MADE BY NEW ENGLAND BORING CONTRACTORS OF DERRY,


- 8. THE NORTH AMERICAN VERTICAL DATUM (NAVD) OF 1988 IS USED THROUGHOUT.
- 9. THE SURFACE ELEVATION ON EACH BORING LOG IS THE ELEVATION OF THE EXISTING GROUND AT THE TIME THE BORING WAS TAKEN.
- 10. SEE SHEET S-002 FOR GEOTECHNICAL DESIGN PARAMETERS.
- 11. ENGINEERING JUDGEMENT WAS EXERCISED IN PREPARING THE SUBSURFACE INFORMATION PRESENTED HEREIN. ANALYSIS AND INTERPRETATION OF SUBSURFACE DATA WAS PERFORMED FOR DESIGN AND ESTIMATING PURPOSES. PRESENTATION OF THE INFORMATION IN THE CONTRACT IS INTENDED TO PROVIDE THE CONTRACTOR ACCESS TO THE SAME DATA AVAILABLE TO THE OWNER. THE SUBSURFACE INFORMATION IS PRESENTED IN GOOD FAITH AND IS NOT INTENDED AS A SUBSTITUTE FOR PERSONAL INVESTIGATION, INDEPENDENT INTERPRETATION, INDEPENDENT ANALYSIS OR JUDGEMENT BY THE CONTRACTOR.

Tighe&Bond Engineers   Environmental Specialists
bigitally signed by David Loring Date: 2020.09.09 15:59:16-04'00'
Permit Set Not For Construction
Department of Public Works
MassDOT Bridge No. M-02-001, BIN 8AM
Town of Manchester-By- The-Sea, Massachusetts
MARK DATE DESCRIPTION PROJECT NO: M1476 - 011 DATE: JUNE 2010
DATE: JUNE 2019 FILE: M1476-011-S-003.dwg DRAWN BY: D.BISHOP
CHECKED: EAO APPROVED: DLL
CHECKED: EAO

COMMONWEALTH OF MASSACHUSETTS MassDOT, Highway Division CONCEPTUAL DESIGN IS ACCEPTABLE TO MASSDOT FOR CONTRACTING







APPENDIX B

SITE PHOTOGRAPHS



**Job Number:** M-1476-011

Site: Central Street Bridge

Photograph No.: 1	Date: 8/13/2018	Direction Taken: North

**Description:** Roadway view of Central Street bridge and Elm Street from the Manchester Harbor side of the bridge.



Photograph No.: 2	Date: 8/13/2018	Direction Taken: East
-------------------	-----------------	-----------------------

Description: Roadway view of Central Street bridge. Elm Street is on the bottom left.





**Job Number:** M-1476-011

Site: Central Street Bridge

Photograph No.: 3	Date: 8/13/2018	Direction Taken: West
-------------------	-----------------	-----------------------

**Description:** A view of the downstream (Manchester Harbor) side of the bridge from Central Street.



Photograph No.: 4	Date: 8/13/2018	Direction Taken: West
-------------------	-----------------	-----------------------

**Description:** View of the tide gate structure and bridge wall on the downstream side of Central Street Bridge.





**Job Number:** M-1476-011

Site: Central Street Bridge

Photograph No.: 5	Date: 8/13/2018	Direction Taken: East
-------------------	-----------------	-----------------------

**Description:** View of the tide gate on the downstream side of Central Street Bridge.



Photograph No.: 6	Date: 8/13/2018	Direction Taken: South
<b>Description:</b> View of the	e underside of the porc	h adjacent to the upstream side of Central Street





**Job Number:** M-1476-011

Site: Central Street Bridge

Photograph No.: 7	Date: 8/13/2018	Direction Taken: South
-------------------	-----------------	------------------------

**Description:** Looking downstream at the tide gate structure from within the bridge opening.



Photograph No.: 8	Date: 8/13/2018	Direction Taken: North
-------------------	-----------------	------------------------

**Description:** Looking upstream from within the bridge opening.






**Job Number:** M-1476-011

Site: Central Street Bridge

Photograph No.: 9 Date: 5/3/2018	Direction Taken: North
----------------------------------	------------------------

Description: View of Sawmill Brook upstream of the Central Street Bridge.



Photograph No.: 10	Date: 9/26/2018	Direction Taken: South
--------------------	-----------------	------------------------

Description: View of the Central Street Bridge and Manchester Harbor from Elm Street.



APPENDIX C


# ABUTTER NOTIFICATION INFORMATION

	Town of Manche Abutter	esterBvTheSea s List	Central F	ad Ora	A	Page 1 of 2
	Subject Parcel ID:					
	Subject Property Location:					
Location	Owner	Co-Owner	Mailing Address	City	State	Zip
	HAWLEY ANDREW J.		P.O.BOX 537	MANCHESTER		01944
	MAESTRANZI MAUREEN A	OBRIEN MICHAEL J	4 SIAS LN	WENHAM		01984
	RADTSCH I ALIDA	RADTOCH IFFEDEV	40 42 CENTRAL ST, UNIT 1	MANCHESTER		01944
40 42C CENTRAL ST	BARTI ETT JOHN A	BARTI ETT I ISA SKINNER	40 42 CENTRI ST UNIT 3	MANCHESTER		01944
38 CENTRAL ST	BARCLAY PAUL		38 CENTRAL STREET	MANCHESTER		01944
1 PEELE HOUSE SQ	SEA ROCK ESTATE INC		5C PEELE HOUSE SQUARE	MANCHESTER		01944
5 PEELE HOUSE SQ	SEA ROCK ESTATE INC		5C PEELE HOUSE SQUARE	MANCHESTER		01944
	MANCHESTER TOWN OF	TOWN HALL + POLICE STA	10 CENTRAL ST	MANCHESTER		01944
0	WOOD DAVID N & MARYANN A		6 HIGHWOOD RD	MANCHESTER		01944
	SEA ROCK ESTATE INC		5C PEELE HOUSE SQUARE	MANCHESTER		01944
TOWN COMMON	FIRST PARISH CHURCH	CONGREGATIONAL	P.O. BOX 187	MANCHESTER		01944
TOWN COMMON	T MOBILE	PROPERTY TAX DEPT	12920 SE 38TH ST	BELLEVUE	-	98006
3	MUNICIO M CUBICTIONE	SERIES MORSE CT EXT	12 MOBEE COUDT UNIT 2	MANCHESTER		01944
	MUNKHOLM CHRISTIANE		12 MORSE COURT, UNIT 2	MANCHESTER		01944
35 CENTRAL ST	HALGREN DONALD & NANCY	NANCY W. HALGREN REVO	35 CENTRAL ST.	MANCHESTER		01944
	JONATHAN B. LEAVITT TRUST OF		75 NORTH MAIN ST. SUITE 1	EAST LONGMEAD		01028
2			5 ANCIENT COUNTY WAY	MANCHESTER		01944
	STEACH ROBERT	STEACH PATRICIA	11 PULASKI DR	MANCHESTER		01944
5 7 SAW MILL CR	MANCHESTER SAW MILL REALTY	ADAM M ZAIGER, CHOATE,	40 BEACH ST, UNIT 304	MANCHESTER		01944
29 UNIT 1 CENTRAL ST	MEGA, LLC		40 BEACH ST, UNIT 304	MANCHESTER		01944
UNIT 2	MEGA, LLC		40 BEACH ST, UNIT 304	MANCHESTER		01944
ELM S	WADIA-ELLS SUSAN		0 ELM ST. UNIT A	MANCHESTER		01944
	MARTIN KRISTIN	Hodges, JR. Jonathan B.	0 ELM ST., UNIT B	MANCHESTER		01944
m	TORY ANTHONY D.	TORY JEMMA	0 ELM ST., UNIT C	MANCHESTER	MA	01944
1	DUNGENESS MANCHESTER REA	CHARLES P. CLAP	10 COUNTRY RD	BOYNTON BEACH		33436
2 ELMIST 21.23 SAW/ MILL CR	MANCHESTER SAW MILL REALTY	ADAM M. ZAIGER,	40 BEACH ST, UNIT 304	MANCHESTER	-	01944
22 ELM ST	PETER LEIGH, LLC.		5 ANCIENT COUNTY WAY	MANCHESTER		01944
1 ELM ST	1 ELM ST LLC		5 ELM ST	MANCHESTER	-	01944
ELM ST	MANCHESTER TOWN OF		10 CENTRAL ST	MANCHESTER		01944
5 ELM ST	COWAN LIVIA A TR	C/O 5 ELM ST RLTY TR	5 ELM ST	MANCHESTER		01944
17 23 ELM ST	<b>127 PINE ST LTD PARTNERSHIP</b>	C/O SUSAN WILENSKI	P.O. BOX 413	LONG KEY		33001-0413
Ш	MANCHESTER TOWN OF		10 CENTRAL ST	MANCHESTER	-	01944
	ROLENATIO	C/O ROLANDA STURTEVAN	AD BEACH ST LINIT 201	MANCHESTER	-	01944
			40 BEACH ST, UNIT 304	MANCHESTER		01944
	Cention Centio	cationSubjectCentral ST CENTRAL ST CENTRAL ST 428 CENTRAL ST CENTRAL ST CENTRAL ST CENTRAL ST PEELE HOUSE SQ CENTRAL ST CENTRAL ST CENTRAL ST PEELE HOUSE SQ CENTRAL ST CENTRAL ST PEELE HOUSE SQ PEELE HOUSE SQ CENTRAL ST CENTRAL ST CENTR	Town of Manches Abutters       Subject Parcel ID: Subject Property Location: Subject Property Location: CENTRAL ST       CENTRAL ST CENTRAL ST CE	Town of ManchesterByTheSea           Subject Property Location:           Subject Property Location:           Central st central st cent	Town of ManchesterByTheSea           Abutters List           Subject Property Location:           Subject Property Location:           Central St           Montest Central St           Central St           Central St           Central St           Monte	Town of ManchesterByTheSea         Carrent List         Carrent List         Carrent List           Subject Property Location:         Subject Property Locat

09/03/2020 1:03:08PM		Town of ManchesterBvTheSea Abutters List	esterBvTheSea s List				Page 2 of 2
		Subject Parcel ID:					
		Subject Property Location:					
	Focation	CWIC	CO-OWIIGI		City	State	Ę
53 0 32	7 CENTRAL ST	7 CENTRAL NOMINEE TRUST ADA	C/O CHOATE, HALL, & STEW	40 BEACH ST, UNIT 304	MANCHESTER	MA	01944
53 0 33		2 SCHOOL NOMINEE TRUST	C/O MEGA, LLC ADAM ZAIG	40 BEACH ST., UNIT 304	MANCHESTER	MA	01944
53 0 34	S	HOOPERS GROCERY INC	C/O JAMIE KNEISEL TYLER   14 EAGLE HEAD RD	14 EAGLE HEAD RD	MANCHESTER		01944
53 0 41	19 CENTRAL ST	19 CENTRAL ST. LLC	C/O CHARLES BENEVENTO	PO BOX 85	PRIDES CROSSIN		01944
53 0 45A	≥	DILLON WENDY H		24 ELM ST. UNIT A	MANCHESTER	MA	01944
53 0 45B	24 B ELM ST	SUSAN R. JACKSON TRUST	SUSAN R. JACKSON, TR	24 ELM ST, UNIT B	MANCHESTER		01944
53 0 45C	24 C ELM ST	HELLIWELL FABYAN HOLLY		1 OLD ESSEX RD.	MANCHESTER	-	01944
53 0 45D	24 D ELM ST	MORGAN SUSAN		4 CANAL PARK #306	CAMBRIDGE	-	02141
53 0 46	1 3 SAW MILL CR	MANCHESTER SAW MILL REALTY	ADAM M ZAIGER, CHOATE,	40 BEACH ST., UNIT 304	MANCHESTER	MA	01944
53 0 47	13 ELM ST	MBTS 13 ELM STREET LLC		100 CUMMINGS CENTER ST	BEVERLY		01915
53 0 49	16 MORSE CT	SR ESTATE LLC	SERIES 16 MORSE CT	5C PEELE HOUSE SQ	MANCHESTER	MA	01944
5305	39 CENTRAL ST	LEVENDUSKÝ JASON	LEVENDUSKY ABIGAIL	39 CENTRAL ST	MANCHESTER	MA	01944
53 0 50	18 MORSE CT	SR ESTATE LLC	SERIES 18 MORSE CT	<b>5C PEELE HOUSE SQUARE</b>	MANCHESTER	MA	01944
53 0 51	20 MORSE CT	SR ESTATE LLC	SERIES 20 MORSE CT	5C PEELE HOUSE SQUARE	MANCHESTER	MA	01944
53 0 53	24 MORSE CT	SR ESTATE LLC	SERIES 24 MORSE CT	5C PEELE HOUSE SQUARE	MANCHESTER	MA	01944
53 0 54	17 19 SAW MILL CR	MANCHESTER SAW MILL REALTY	ADAM M ZAIGER, CHOATE,	40 BEACH ST, UNIT 304	MANCHESTER	-	01944
53 0 57	13 15 SAW MILL CR	MANCHESTER SAW MILL REALTY	ADAM M ZAIGER, CHOATE,	40 BEACH ST, UNIT 304	MANCHESTER	MA	01944
53 0 58	9 11 SAW MILL CR	MANCHESTER SAW MILL REALTY	ADAM M ZAIGER, CHOATE,	40 BEACH ST, UNIT 304	MANCHESTER	MA	01944
5306	37 CENTRAL ST	BUSSONE ANTONIO		37 CENTRAL ST	MANCHESTER	MA	01944
53 0 7	6 MORSE CT	CARPENTER WILLIAM J	CARPENTER JEANNE T	7 VINE ST	MANCHESTER	MA	01944
5308	8 MORSE CT	SEA ROCK ESTATE INC		5C PEELE HOUSE SQUARE	MANCHESTER	MA	01944
5309	14 MORSE CT	FINNERTY MARK J	FINNERTY LORA P	14 MORSE CT	MANCHESTER	MA	01944
Parcel Count	Count: 63						
		End of Report	eport A		>>>	1120	

2

Cutified abouttens within 300° of Central Hend aller, an of September 3, 2020, for Conservation Commission, for Virgina Mittiger, MAA Virgina Mittiger, MAA



#### Notification to Abutters under the Massachusetts Wetlands Protection Act and the Manchester-by-the-Sea General Wetlands By-Law

In accordance with the second paragraph of Massachusetts General Laws Chapter 131, Section 40 and the Town of Manchester's Wetlands By-Law, you are hereby notified of the following public hearing on the matter described below.

- A. The name of the applicant is <u>Town of Manchester-by-the-Sea</u>
- B. The address of the lot where the activity is proposed is: Central Street Bridge
- C. The work proposed is in the jurisdiction of the Wetlands Protection Act and/or Manchester Wetlands By-Law is as follows:

The Town of Manchester-by-the-Sea proposed to remove the tide gate structure, replace the existing Central Street culvert with a 20-foot span bridge and conduct minor roadway improvements on Central Street.

- D. Copies of the Notice of Intent or the Request to Amend an Existing Order of Conditions may be examined at Manchester Town Hall in the Conservation Commission office between the hours of 2:00pm and 5:00pm Monday through Thursday.
- E. Copies of the Notice of Intent or the Request to Amend an Existing Order of Conditions may be obtained from either (check one) the applicant\_\_\_\_\_ or the applicant's representative \_\_X\_, by calling this telephone number (<u>413</u>) <u>875-1622</u> between the hours of <u>8:00 AM</u> and <u>4:00 PM</u>, on the following days of the week: <u>Monday through Friday</u>.
- F. The Public Hearing will be held on <u>October 13, 2020</u> at 6:30 pm at Manchester Town Hall, located at 10 Central Street.
- NOTE: Notice of the public hearing, including its date, time, and place, will be published at least five (5) days in advance in the Manchester Cricket or the Gloucester Times.
- NOTE: Notice of the public hearing, including its date, time, and place, will be posted in the Manchester Town Hall not less than forty-eight (48) hours in advance.
- NOTE: You also may contact the Manchester Conservation Commission or the Department of Environmental Protection Northeast Regional Office for more information about this application. To contact the Manchester Conservation Commission, please call the Conservation Administrator at 978-526-4397.

#### **AFFIDAVIT OF SERVICE**

Under the Massachusetts Wetlands Protection Act and the Manchester General Wetlands By-Law

To be submitted to the Massachusetts Department of Environmental Protection and the Manchester-by-the-Sea Conservation Commission when filing a Notice of Intent or a Request to Amend an Order of Conditions.

I, <u>Richard Canavan, Tighe & Bond</u>, hereby certify under the pains and penalties of perjury that on <u>September 14, 2020</u> I gave notification to abutters in compliance with the second paragraph of Massachusetts General Laws Chapter 131, Section 40, and the Manchester-by-the-Sea General Wetlands By-Law.

A Notice of Intent X or a Request to Amend an existing Order of Conditions \_\_\_\_\_ was filed under the Massachusetts Wetlands Protection Act and the Manchester General Wetlands By-Law by <u>the Town of Manchester-by-the-Sea</u> with the Town of Manchester on <u>September 28, 2020</u> for property located at:

Central Street Bridge

The form of the notification, and a list of the abutters to whom it was given and their addresses are attached to this Affidavit of Service.

Wile Canne

Signature

September 28, 2020

Date

APPENDIX D

STORMWATER CHECKLIST



# Massachusetts Department of Environmental Protection Bureau of Resource Protection - Wetlands Program Checklist for Stormwater Report

# A. Introduction

Important: When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.



A Stormwater Report must be submitted with the Notice of Intent permit application to document compliance with the Stormwater Management Standards. The following checklist is NOT a substitute for the Stormwater Report (which should provide more substantive and detailed information) but is offered here as a tool to help the applicant organize their Stormwater Management documentation for their Report and for the reviewer to assess this information in a consistent format. As noted in the Checklist, the Stormwater Report must contain the engineering computations and supporting information set forth in Volume 3 of the Massachusetts Stormwater Handbook. The Stormwater Report must be prepared and certified by a Registered Professional Engineer (RPE) licensed in the Commonwealth.

The Stormwater Report must include:

- The Stormwater Checklist completed and stamped by a Registered Professional Engineer (see page 2) that certifies that the Stormwater Report contains all required submittals.<sup>1</sup> This Checklist is to be used as the cover for the completed Stormwater Report.
- Applicant/Project Name
- Project Address
- Name of Firm and Registered Professional Engineer that prepared the Report
- Long-Term Pollution Prevention Plan required by Standards 4-6
- Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan required by Standard 8<sup>2</sup>
- Operation and Maintenance Plan required by Standard 9

In addition to all plans and supporting information, the Stormwater Report must include a brief narrative describing stormwater management practices, including environmentally sensitive site design and LID techniques, along with a diagram depicting runoff through the proposed BMP treatment train. Plans are required to show existing and proposed conditions, identify all wetland resource areas, NRCS soil types, critical areas, Land Uses with Higher Potential Pollutant Loads (LUHPPL), and any areas on the site where infiltration rate is greater than 2.4 inches per hour. The Plans shall identify the drainage areas for both existing and proposed conditions at a scale that enables verification of supporting calculations.

As noted in the Checklist, the Stormwater Management Report shall document compliance with each of the Stormwater Management Standards as provided in the Massachusetts Stormwater Handbook. The soils evaluation and calculations shall be done using the methodologies set forth in Volume 3 of the Massachusetts Stormwater Handbook.

To ensure that the Stormwater Report is complete, applicants are required to fill in the Stormwater Report Checklist by checking the box to indicate that the specified information has been included in the Stormwater Report. If any of the information specified in the checklist has not been submitted, the applicant must provide an explanation. The completed Stormwater Report Checklist and Certification must be submitted with the Stormwater Report.

<sup>&</sup>lt;sup>1</sup> The Stormwater Report may also include the Illicit Discharge Compliance Statement required by Standard 10. If not included in the Stormwater Report, the Illicit Discharge Compliance Statement must be submitted prior to the discharge of stormwater runoff to the post-construction best management practices.

<sup>&</sup>lt;sup>2</sup> For some complex projects, it may not be possible to include the Construction Period Erosion and Sedimentation Control Plan in the Stormwater Report. In that event, the issuing authority has the discretion to issue an Order of Conditions that approves the project and includes a condition requiring the proponent to submit the Construction Period Erosion and Sedimentation Control Plan before commencing any land disturbance activity on the site.



## **B. Stormwater Checklist and Certification**

The following checklist is intended to serve as a guide for applicants as to the elements that ordinarily need to be addressed in a complete Stormwater Report. The checklist is also intended to provide conservation commissions and other reviewing authorities with a summary of the components necessary for a comprehensive Stormwater Report that addresses the ten Stormwater Standards.

*Note:* Because stormwater requirements vary from project to project, it is possible that a complete Stormwater Report may not include information on some of the subjects specified in the Checklist. If it is determined that a specific item does not apply to the project under review, please note that the item is not applicable (N.A.) and provide the reasons for that determination.

A complete checklist must include the Certification set forth below signed by the Registered Professional Engineer who prepared the Stormwater Report.

## **Registered Professional Engineer's Certification**

I have reviewed the Stormwater Report, including the soil evaluation, computations, Long-term Pollution Prevention Plan, the Construction Period Erosion and Sedimentation Control Plan (if included), the Longterm Post-Construction Operation and Maintenance Plan, the Illicit Discharge Compliance Statement (if included) and the plans showing the stormwater management system, and have determined that they have been prepared in accordance with the requirements of the Stormwater Management Standards as further elaborated by the Massachusetts Stormwater Handbook. I have also determined that the information presented in the Stormwater Checklist is accurate and that the information presented in the Stormwater Report accurately reflects conditions at the site as of the date of this permit application.


Registered Professional Engineer Block and Signature



Checklist

**Project Type:** Is the application for new development, redevelopment, or a mix of new and redevelopment?

New development



Mix of New Development and Redevelopment



**LID Measures:** Stormwater Standards require LID measures to be considered. Document what environmentally sensitive design and LID Techniques were considered during the planning and design of the project:

	No disturbance to any Wetland Resource Areas
	Site Design Practices (e.g. clustered development, reduced frontage setbacks)
	Reduced Impervious Area (Redevelopment Only)
$\boxtimes$	Minimizing disturbance to existing trees and shrubs
	LID Site Design Credit Requested:
	Credit 1
	Credit 2
	Credit 3
	Use of "country drainage" versus curb and gutter conveyance and pipe
	Bioretention Cells (includes Rain Gardens)
	Constructed Stormwater Wetlands (includes Gravel Wetlands designs)
	Treebox Filter
	Water Quality Swale
	Grass Channel
	Green Roof
	Other (describe):

#### **Standard 1: No New Untreated Discharges**

No new untreated discharges

- Outlets have been designed so there is no erosion or scour to wetlands and waters of the Commonwealth
- Supporting calculations specified in Volume 3 of the Massachusetts Stormwater Handbook included.



#### Standard 2: Peak Rate Attenuation

- Standard 2 waiver requested because the project is located in land subject to coastal storm flowage and stormwater discharge is to a wetland subject to coastal flooding.
- Evaluation provided to determine whether off-site flooding increases during the 100-year 24-hour storm.

Calculations provided to show that post-development peak discharge rates do not exceed predevelopment rates for the 2-year and 10-year 24-hour storms. If evaluation shows that off-site flooding increases during the 100-year 24-hour storm, calculations are also provided to show that post-development peak discharge rates do not exceed pre-development rates for the 100-year 24hour storm.

#### Standard 3: Recharge

Soil Analysis provided.

- Required Recharge Volume calculation provided.
- Required Recharge volume reduced through use of the LID site Design Credits.
- Sizing the infiltration, BMPs is based on the following method: Check the method used.

Static	Simple Dynamic
--------	----------------

Dynamic Field<sup>1</sup>

- Runoff from all impervious areas at the site discharging to the infiltration BMP.
- Runoff from all impervious areas at the site is *not* discharging to the infiltration BMP and calculations are provided showing that the drainage area contributing runoff to the infiltration BMPs is sufficient to generate the required recharge volume.

	Recharge BMPs	have been	sized to infiltrat	e the Required	Recharge Volume.
--	---------------	-----------	--------------------	----------------	------------------

- Recharge BMPs have been sized to infiltrate the Required Recharge Volume *only* to the maximum extent practicable for the following reason:
  - Site is comprised solely of C and D soils and/or bedrock at the land surface
  - M.G.L. c. 21E sites pursuant to 310 CMR 40.0000
  - Solid Waste Landfill pursuant to 310 CMR 19.000
  - Project is otherwise subject to Stormwater Management Standards only to the maximum extent practicable.
- Calculations showing that the infiltration BMPs will drain in 72 hours are provided.

Property includes a M.G.L. c. 21E site or a solid waste landfill and a mounding analysis is included.

<sup>&</sup>lt;sup>1</sup> 80% TSS removal is required prior to discharge to infiltration BMP if Dynamic Field method is used.



#### Standard 3: Recharge (continued)

The infiltration BMP is used to attenuate peak flows during storms greater than or equal to the 10year 24-hour storm and separation to seasonal high groundwater is less than 4 feet and a mounding analysis is provided.

Documentation is provided showing that infiltration BMPs do not adversely impact nearby wetland resource areas.

#### **Standard 4: Water Quality**

The Long-Term Pollution Prevention Plan typically includes the following:

- Good housekeeping practices;
- Provisions for storing materials and waste products inside or under cover;
- Vehicle washing controls;
- Requirements for routine inspections and maintenance of stormwater BMPs;
- Spill prevention and response plans;
- Provisions for maintenance of lawns, gardens, and other landscaped areas;
- Requirements for storage and use of fertilizers, herbicides, and pesticides;
- Pet waste management provisions;
- Provisions for operation and management of septic systems;
- Provisions for solid waste management;
- Snow disposal and plowing plans relative to Wetland Resource Areas;
- Winter Road Salt and/or Sand Use and Storage restrictions;
- Street sweeping schedules;
- Provisions for prevention of illicit discharges to the stormwater management system;
- Documentation that Stormwater BMPs are designed to provide for shutdown and containment in the event of a spill or discharges to or near critical areas or from LUHPPL;
- Training for staff or personnel involved with implementing Long-Term Pollution Prevention Plan;
- List of Emergency contacts for implementing Long-Term Pollution Prevention Plan.
- A Long-Term Pollution Prevention Plan is attached to Stormwater Report and is included as an attachment to the Wetlands Notice of Intent.
- Treatment BMPs subject to the 44% TSS removal pretreatment requirement and the one inch rule for calculating the water quality volume are included, and discharge:
  - is within the Zone II or Interim Wellhead Protection Area
  - is near or to other critical areas
  - is within soils with a rapid infiltration rate (greater than 2.4 inches per hour)
  - involves runoff from land uses with higher potential pollutant loads.
- The Required Water Quality Volume is reduced through use of the LID site Design Credits.
- Calculations documenting that the treatment train meets the 80% TSS removal requirement and, if applicable, the 44% TSS removal pretreatment requirement, are provided.



#### Standard 4: Water Quality (continued)

The BMP is sized	(and calculations	provided) based on:
------------------	-------------------	---------------------

- The <sup>1</sup>/<sub>2</sub>" or 1" Water Quality Volume or
- The equivalent flow rate associated with the Water Quality Volume and documentation is provided showing that the BMP treats the required water quality volume.
- ☐ The applicant proposes to use proprietary BMPs, and documentation supporting use of proprietary BMP and proposed TSS removal rate is provided. This documentation may be in the form of the propriety BMP checklist found in Volume 2, Chapter 4 of the Massachusetts Stormwater Handbook and submitting copies of the TARP Report, STEP Report, and/or other third party studies verifying performance of the proprietary BMPs.
- A TMDL exists that indicates a need to reduce pollutants other than TSS and documentation showing that the BMPs selected are consistent with the TMDL is provided.

#### Standard 5: Land Uses With Higher Potential Pollutant Loads (LUHPPLs)

- The NPDES Multi-Sector General Permit covers the land use and the Stormwater Pollution Prevention Plan (SWPPP) has been included with the Stormwater Report.
- The NPDES Multi-Sector General Permit covers the land use and the SWPPP will be submitted **prior to** the discharge of stormwater to the post-construction stormwater BMPs.
- The NPDES Multi-Sector General Permit does *not* cover the land use.
- LUHPPLs are located at the site and industry specific source control and pollution prevention measures have been proposed to reduce or eliminate the exposure of LUHPPLs to rain, snow, snow melt and runoff, and been included in the long term Pollution Prevention Plan.
- All exposure has been eliminated.
- All exposure has *not* been eliminated and all BMPs selected are on MassDEP LUHPPL list.
- The LUHPPL has the potential to generate runoff with moderate to higher concentrations of oil and grease (e.g. all parking lots with >1000 vehicle trips per day) and the treatment train includes an oil grit separator, a filtering bioretention area, a sand filter or equivalent.

#### **Standard 6: Critical Areas**

- The discharge is near or to a critical area and the treatment train includes only BMPs that MassDEP has approved for stormwater discharges to or near that particular class of critical area.
- Critical areas and BMPs are identified in the Stormwater Report.



# Standard 7: Redevelopments and Other Projects Subject to the Standards only to the maximum extent practicable

- The project is subject to the Stormwater Management Standards only to the maximum Extent Practicable as a:
  - Limited Project
  - Small Residential Projects: 5-9 single family houses or 5-9 units in a multi-family development provided there is no discharge that may potentially affect a critical area.
  - Small Residential Projects: 2-4 single family houses or 2-4 units in a multi-family development with a discharge to a critical area
  - Marina and/or boatyard provided the hull painting, service and maintenance areas are protected from exposure to rain, snow, snow melt and runoff
  - Bike Path and/or Foot Path
  - Redevelopment Project
  - Redevelopment portion of mix of new and redevelopment.
- Certain standards are not fully met (Standard No. 1, 8, 9, and 10 must always be fully met) and an explanation of why these standards are not met is contained in the Stormwater Report.

☐ The project involves redevelopment and a description of all measures that have been taken to improve existing conditions is provided in the Stormwater Report. The redevelopment checklist found in Volume 2 Chapter 3 of the Massachusetts Stormwater Handbook may be used to document that the proposed stormwater management system (a) complies with Standards 2, 3 and the pretreatment and structural BMP requirements of Standards 4-6 to the maximum extent practicable and (b) improves existing conditions.

#### Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan must include the following information:

- Narrative;
- Construction Period Operation and Maintenance Plan;
- Names of Persons or Entity Responsible for Plan Compliance;
- Construction Period Pollution Prevention Measures;
- Erosion and Sedimentation Control Plan Drawings;
- Detail drawings and specifications for erosion control BMPs, including sizing calculations;
- Vegetation Planning;
- Site Development Plan;
- Construction Sequencing Plan;
- Sequencing of Erosion and Sedimentation Controls;
- Operation and Maintenance of Erosion and Sedimentation Controls;
- Inspection Schedule;
- Maintenance Schedule;
- Inspection and Maintenance Log Form.

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan containing the information set forth above has been included in the Stormwater Report.



# Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control (continued)

The project is highly complex and information is included in the Stormwater Report that explains why
it is not possible to submit the Construction Period Pollution Prevention and Erosion and
Sedimentation Control Plan with the application. A Construction Period Pollution Prevention and
Erosion and Sedimentation Control has <i>not</i> been included in the Stormwater Report but will be
submitted <i>before</i> land disturbance begins.

- The project is *not* covered by a NPDES Construction General Permit.
- The project is covered by a NPDES Construction General Permit and a copy of the SWPPP is in the Stormwater Report.
- The project is covered by a NPDES Construction General Permit but no SWPPP been submitted. The SWPPP will be submitted BEFORE land disturbance begins.

#### **Standard 9: Operation and Maintenance Plan**

The Post Construction Operation and Maintenance Plan is included in the Stormwater Report ar	nd
includes the following information:	

- Name of the stormwater management system owners;
- Party responsible for operation and maintenance;
- Schedule for implementation of routine and non-routine maintenance tasks;
- Plan showing the location of all stormwater BMPs maintenance access areas;
- Description and delineation of public safety features;
- Estimated operation and maintenance budget; and
- Operation and Maintenance Log Form.
- The responsible party is **not** the owner of the parcel where the BMP is located and the Stormwater Report includes the following submissions:
  - A copy of the legal instrument (deed, homeowner's association, utility trust or other legal entity) that establishes the terms of and legal responsibility for the operation and maintenance of the project site stormwater BMPs;
  - A plan and easement deed that allows site access for the legal entity to operate and maintain BMP functions.

#### Standard 10: Prohibition of Illicit Discharges

- The Long-Term Pollution Prevention Plan includes measures to prevent illicit discharges;
- An Illicit Discharge Compliance Statement is attached;
- NO Illicit Discharge Compliance Statement is attached but will be submitted *prior to* the discharge of any stormwater to post-construction BMPs.

# Section 1 Regulatory Compliance

The project is required to comply with the ten Massachusetts Department of Environmental Protection (MassDEP) Massachusetts Stormwater Standards (Standards) under the Massachusetts Wetlands Protection Act. The Massachusetts Stormwater Checklist is attached.

# 1.1 LID Measures

MassDEP allows for reductions in structural stormwater Best Management Practice (BMP) requirements for water quantity and quality when certain criteria are met. TSS removal at the bridges will be improved by use of curbing on the bridge structure. The curbing will eliminate direct discharges from the bridge into Sawmill Brook. The flow from the bridge will collected in a closed storm drain system and conveyed through a stormwater management unit prior to discharge, thus improving the existing TSS conditions on the bridge.

## **1.2 Standard 1: No New Untreated Discharges**

The project does not create any new point source discharges of stormwater runoff to jurisdictional areas.

The project will not result in any new stormwater conveyance discharging untreated stormwater directly to the waters of the Commonwealth. The project includes one new outfall will be connected to new deep sump catch basins and a stormwater treatment unit before discharging through the outfall. There no proposed changes in the impervious areas within this congested, fully developed, downtown project area. This outfall is designed to avoid erosive stormwater velocities at the outlet

# **1.3 Standard 2: Peak Discharge Rate Attenuation**

The proposed project matches the existing average roadway width and the impervious surface of the bridge. It can be assumed that peak discharge rates from the project are not measurably altered under proposed conditions. No further analysis has been provided. By the installation of catch basins and a new outfall, the water will be contained and treated prior to discharge

# 1.4 Standard 3: Groundwater Recharge

The proposed project does not result in a change in impervious ground surface; therefore, groundwater recharge is not required.

# 1.5 Standard 4: Water Quality

The proposed project does not result in a change in impervious ground surface; therefore, water quality provisions are not required. The project adds deep sump catch basins to help remove sediment from stormwater. The project otherwise generally maintains the existing roadway configuration. The project will improve hydraulic conditions in Sawmill Brook which may improve water quality by increasing the hydraulic

opening at the bridge to reduce velocity and scour downstream of the bridge. A Long-Term Pollution Prevention Plan is attached.

# **1.6 Standard 5: Land Uses with Higher Potential** Pollutant Loads (LUHPPLs)

The project is not considered a LUHPPL; therefore, the more stringent requirements of Standard 5 are not applicable.

# **1.7 Standard 6: Critical Areas**

The project will not result in any new untreated stormwater discharges to Sawmill Brook. Existing drainage patterns will be maintained and stormwater quality will not be impacted a result of the project.

# **1.8 Standard 7: Redevelopment Projects**

The project is considered a redevelopment, therefore Standards 2, 3 and the pretreatment and structural stormwater best management practices of Standards 4, 5, and 6 are met to the maximum extent practicable.

# **1.9 Standard 8: Construction Period Pollution** Prevention, Erosion and Sedimentation Control

Construction-period erosion and sedimentation controls are identified on the Site Plans and include straw wattles of mulch logs at a minimum. The project will not disturb more than one acre of land during construction; therefore, an EPA National Pollutant Discharge System (NPDES) Construction General Permit does not apply.

### 1.10 Standard 9: Long-Term Operation and Maintenance Plan

A site specific Operations and Maintenance Plan will not be created for this bridge. The maintenance of the project area will fall under the general plan of maintenance for local roads by the Manchester DPW.

# 1.11Standard 10: Prohibition of Illicit Discharges

Illicit discharges to the stormwater management system are discharges that are not entirely comprised of stormwater. Illicit discharge does not include discharges from the following activities or facilities: firefighting, water line flushing, landscape irrigation, uncontaminated groundwater, potable water sources, foundation drains, air conditioning condensation, footing drains, individual resident car washing, flows from riparian habitats and wetlands, dechlorinated water from swimming pools, water used for street washing, and water used to clean residential buildings without detergents.

The Owner is not aware of any existing illicit discharges at the Site and is not proposing any illicit discharges as part of the Project. If any illicit connections are found during construction of the Site, these connections will be abandoned and removed. A signed Illicit Discharge Statement is attached.

# **Illicit Discharge Compliance Statement**

Project Location:

Central Street Bridge (Bridge M-02-001)

Central Street

Manchester, MA 01944

Illicit discharges to the stormwater management system are discharges that are not entirely comprised of stormwater. Illicit discharge does not include discharges from the following activities or facilities: firefighting, water line flushing, landscape irrigation, uncontaminated groundwater, potable water sources, foundation drains, air conditioning condensation, footing drains, individual resident car washing, flows from riparian habitats and wetlands, dechlorinated water from swimming pools, water used for street washing, and water used to clean residential buildings without detergents.

To the best of my knowledge, I am not aware of any existing illicit discharges located at the Project Location and will abandon or remove such illicit discharges/connections in the future, if found.

Signature:

Printed Name & Title:

Charles Dam, Director of Public Works

### Section 1 Introduction and Purpose

### **Section 2 Responsible Parties**

### Section 3 Long Term Pollution Prevention Plan

3.1	Good Housekeeping3-1		
3.2	Potential Sources of Pollution		
3.3	3 Spill Prevention and Response		
	3.3.1	Federal and State Spill Notification3-2	
	3.3.2	Local Notification	
3.4	Fuelin	g and Maintenance of Equipment or Vehicles	
3.5	Washi	ng of Equipment and Vehicles	
3.6			
	3.6.1	Building Products	
	3.6.2	Pesticides, Herbicides, Insecticides, Fertilizers, and Landscaping Materials	
	3.6.3	Diesel Fuel, Oil, Hydraulic Fluids, Other Petroleum Products, and Other Chemicals	
	3.6.4	Hazardous or Toxic Waste	
	3.6.5	Construction and Domestic Waste	
	3.6.6	Sanitary Waste	
3.7		ng of Applicators and Containers used for Paint, Concrete or Other als	
3.8	Standa	ard 7: Redevelopment Projects3-5	

J:\M\M1476 Manchester MA Hydro Study\011-Central Street Bridge\Permitting\NOI\Appendix D - Stormwater\Stormwater OM .docx

# Section 1 Introduction and Purpose

The following Long-Term Pollution Prevention Plan (LTPPP) has been prepared for the proposed Central Street Bridge Over Sawmill Brook in Manchester-by-the-Sea, Massachusetts. The purpose of the plan is to provide guidance and procedures for proper pollution prevention following construction completion.

The proposed project has been designed in compliance with the Massachusetts Department of Environmental Protection (MassDEP) Stormwater Standard to maintain or improve stormwater runoff quality and quantity.

# Section 2 Responsible Parties

The Manchester Department of Public Works is responsible for maintaining and servicing the proposed Central Street Bridge including road surface, vegetated surfaces, utilities, and bridge structure components post construction. During construction, the contractor will be responsible for stormwater management system maintenance.

#### **Property Owner:**

Manchester, Town of 10 Central Street Manchester, MA 01944

#### **Maintenance Contact:**

Manchester, Town of 10 Central Street Manchester, MA 01944

#### Subcontractor(s):

Company or Organization Name:	
Name:	
Address:	
City, State, Zip:	
Telephone Number:	
Fax/Email:	
Area of Control:	
Subcontractor(s):	
Company or Organization Name: Name: Address: City, State, Zip: Telephone Number: Fax/Email: Area of Control:	

# Section 3 Long Term Pollution Prevention Plan

# 3.1 Good Housekeeping

The goal of the good housekeeping policy is to keep the site in a clean orderly condition. A disorderly site can lead to improper materials management, and can reduce the efficiency of any response to potential pollution problems.

The following good housekeeping measures will be followed at the site to aid in pollution prevention:

- Promptly clean and remove any spills or contamination from vehicles
- Perform preventative maintenance on all equipment and on the structural components of the stormwater system

# 3.2 Potential Sources of Pollution

**Construction Site Pollutants** 

Pollutant-Generating Activity	Pollutants or Pollutant Constituents (that could be discharged if exposed to stormwater)	Location on Site
Site work	Soil particals and fines	Where disturbance is proposed
Paving and construction areas	Petroleum, concrete, vehicle fluids, paints, solvents	Where paving and construction is proposed
General Construction Areas	Petroleum, concrete, vehicle fluids, paints, solvents	Where construction is proposed
Solid waste storage	Construction debris, trash	In dumpster locations
Fertilizing	Fertilizers	Prohibited on-site
Equipment use	Hydraulic Oils/fluids	Leaks/broken hoses from equipment
Equipment use	Antifreeze/coolant	Leaks/broken hoses from equipment
Portable toilets	Sewage	Where portable toilets are located
Staging areas	Sediment, gasoline, fuel oil, concrete, vehicle fluids, paints, solvents, fertilizers, adhesives, antifreeze/coolant, hydraulic oil/fluid, etc.	
Concrete Wash Out	Particles and Fines	Concrete wash out area

# 3.3 Spill Prevention and Response

- Manufacturer's recommended methods for cleanup will be clearly posted and site personnel will be made aware of the procedures and the location of the information and clean up supplies
- Materials and equipment necessary for spill cleanup will be kept in the material storage areas on site. Equipment and materials will include but not be limited to brooms, dustpans, mops, rags, gloves, goggles, kitty litter, sand, sawdust and plastic or metal trash containers specifically for this purpose.
- All spills will be cleaned up immediately after discovery
- The spill area will be kept well ventilated and personnel will wear appropriate protective clothing to prevent injury from contact with hazardous substances
- Spills of toxic or hazardous material will be reported to the appropriate state or local government agency regardless of size
- The Spill Prevention Plan will be adjusted to include measures to prevent this type of spill from recurring and how to cleanup the spill if it recurs. A description of the spill, its cause and the cleanup measures will be included.
- The site superintendent responsible for day to day operations will be the spill prevention and cleanup coordinator

### 3.3.1 Federal and State Spill Notification

In accordance with 310 CMR 40.0333, the superintendent shall notify the Massachusetts Department of Environmental Protection (Northeast Region) - (978) 694-3200, the Local Emergency Planning Committee (LEPC) and any other authorities or agencies within <u>two</u> <u>hours</u> if an accident or other type of incident results in a release to:

- land
  - 10 Gallons for more Oils (PCB<500 ppm)
  - 1 Gallons or more Oils (PCB  $\geq$  500 ppm)
- waterways
  - Any quantity of Oils
- Or, triggers the exposure to toxic chemical levels as listed in 301 CMR 40.1600, Revised Massachusetts Contingency Plan

The superintendent shall notify the National Response Center (NRC) at **(800) 424-8802** where a leak, spill, or other release containing a hazardous substance or oil in an amount equal to or in excess of a reportable quantity consistent with Part 2.3.3.4c and established under either 40 CFR Part 110, 40 CFR Part 117, or 40 CFR Part 302, occurs during a 24-hour period.

In either event, the NRC will work with state and federal agencies to ensure that all appropriate forms and reports are submitted in a timely manner.

• Note: Trigger volumes for other chemical spills vary. Contact the MassDEP or a Licensed Site Professional (LSP) for specific guidance on reporting thresholds and requirements for other chemicals.

### 3.3.2 Local Notification

The following local agencies will be called to provide emergency assistance at the site on the judgment of the NRC:

Fire Department:	Police Department:
911 or (978) 526-4040	911 or (978) 526-1212
Department of Public Works (978) 526-1242	

# **3.4 Fueling and Maintenance of Equipment or Vehicles** General

Equipment fueling and other activities involving petroleum, oil, or other potentially hazardous substances are to be performed at pre-approved designated areas with appropriate spill prevention and control measures. Portable secondary containment is to be used and sorbent materials are to be placed around the perimeter of the fueling area.

#### **Specific Pollution Prevention Practices**

- Site contractor/project manager shall provide an onsite vehicle fueling and maintenance area that is clean and dry.
- If possible keep area covered.
- Keep a spill kit at the fueling and maintenance area.
- Vehicles shall be inspected regularly for leaks and damage.
- Use drip pans, drip cloths or absorbent pads when replacing spent fluid.

# **3.5 Washing of Equipment and Vehicles**

#### General

Efforts shall be made to perform equipment/vehicle washing and maintenance off-site. If washing of equipment and vehicles is performed on site, the following pollution prevention practices must be provided to minimize the discharge of pollutants.

#### **Specific Pollution Prevention Practices**

- Site contractor/project manager shall provide a proper washing area.
- Discharges from washing areas shall be infiltrated or diverted into sanitary sewer system unless no soaps or detergents are used.
- If soaps, detergents or solvents are stored onsite over must be provided to prevent these detergents from coming into contact with rainwater.
- Vehicles and equipment should be washed and/or maintained off-site.

# 3.6 Storage, Handling, and Disposal of Construction Products, Materials, and Wastes

### **3.6.1 Building Products**

- Site contractor/project manager shall designate a waste collection area on the site that does not receive a substantial amount of runoff from upland areas and does not drain directly to a water body.
- Ensure that containers have lids so they can be covered before periods of rain, and keep containers in a covered area whenever possible.
- Schedule waste collection to prevent the containers from overfilling.
- Clean up spills immediately. For hazardous materials, follow cleanup instructions on the package. Use an absorbent material such as sawdust or kitty litter to contain the spill.
- During the demolition phase of construction, provide extra containers and schedule more frequent pickups.
- Collect, remove, and dispose of all construction site wastes at authorized disposal areas.

#### 3.6.2 Pesticides, Herbicides, Insecticides, Fertilizers, and Landscaping Materials

- Store new and used materials in a neat, orderly manner in their appropriate containers in a covered area. If storage in a covered area is not possible, the materials shall be covered with polyethylene or polypropylene sheeting to protect them from the elements. These materials should only be on-site in very limited quantities and should not be stored on-site overnight.
- Storage area should include precautions to contain any potential spills.
- Immediately contain and clean up any spills with absorbent materials.

# **3.6.3 Diesel Fuel, Oil, Hydraulic Fluids, Other Petroleum Products, and Other Chemicals**

- Diesel fuel, oil, hydraulic fluids, petroleum products and other liquid hazardous materials should be stored off-site and not be stored on-site.
- Immediately contain and clean up any spills with absorbent material and notify appropriate authorities.
- Have equipment available in fuel storage areas and in vehicles to contain and clean up any spills that occur.

### **3.6.4 Hazardous or Toxic Waste**

- Hazardous and toxic waste should also be stored off-site with no overnight storage allowed within the project area.
- Immediately contain and clean up any spills with absorbent materials.
- Have equipment available in fuel storage areas and in vehicles to contain and clean up any spills that occur.

Central Street Bridge Over Sawmill Brook Long-Term Pollution Prevention Plan

- To prevent leaks, empty and clean hazerdous waste containers before disposing of them.
- Never remove the original product label from the container because it contains important safety information. Follow the manufacturer's recommended method of disposal, which should be printed on the label.
- Never mix excess products when disposing of them, unless specifically recommended by the manufacturer.

#### **3.6.5 Construction and Domestic Waste**

• All materials shall be collected and stored in securely lidded receptacles, no construction waste materials will be buried. Clean up immediately if containers overflow.

#### **3.6.6 Sanitary Waste**

- Portable sanitary units will be provided throughout the course of the project for use by the site contractor/project manager's employees. A licensed sanitary waste management contractor will regularly collect all sanitary waste from the portable units. Position portable toilets so that they are secure and will not be tipped or knocked over.
- Sanitary waste facilities should be located as far away from waterbodies as possible. At a minimum, portable sanitary units should be situated more than 400' from the reservoir and more than 200' from tributaries to the reservoir.

# 3.7 Washing of Applicators and Containers used for Paint, Concrete or Other Materials

- The contractors should be encouraged where possible, to use washout facilities at their own plant or dispatch facility from stucco, paint, concrete, form release oils, curing compounds, and other construction materials.
- Washing of application and containers used for paint, concrete, and other materials should not occur on-site, as this runoff may enter Sawmill Brook.
- Washout area shall be located as far from the reservoir and reservoir tributaries as possible.
- Inspect washout facilities daily to detect leaks or tears and to identify when materials need to be removed.

# **3.8 Standard 7: Redevelopment Projects**

The project is considered a redevelopment, therefore Standards 2, 3 and the pretreatment and structural stormwater best management practices of Standards 4, 5, and 6 are met to the maximum extent practicable.

J:\M\M1476 Manchester MA Hydro Study\011-Central Street Bridge\Permitting\NOI\Appendix D - Stormwater\Stormwater OM .docx

www.tighebond.com

